Proposed Extraction System Specification

No 5 Progress Buildings Manchester

- Stainless steel extract hoods — 2 No. 2700mm x 1200mm
- Fans Solar and Palau — 2 No.TD600/400 inline
- Duty — 2.5m^3/sec
- Controller — Variable speed
- Baffle grease filters x 6 to each canopy — 495mm x 495mm
- Extracting @ — 0.65m^3/ sec
- Noise level including silencers — 37dBa @ 3m
- Ducting size — 400mm circular
- Ducting colour — Galv steel
- Avb mounts standard — Standard