

New shop front, following removal of existing door. Traffic Red RAL 3020

Proposed main fascia sign to have static internal illumination. Maximum illumination 800 cd/m², to match existing.

Shutters and frames to be refurbished and painted Traffic Red RAL 3020

Openable windows to head section removed and replaced with fixed glazed panels

Existing door to be retained, refurbished and painted Traffic Red RAL 3020.

Existing stallraiser (brick) to retain, made good where necessary, contractor allow for full clean

ENTRANCE

PROPOSED ELEVATION TO LANSDOWNE ROAD

PROPOSED

REV	DETAILS	DATE
B	Alteration to signage proposals to amend error on drawing.	24.11.16
A	Alteration to shop front proposals.	11.11.16

REVISIONS

CLIENT
DAVID PLUCK [North West Ltd].

PROJECT
11 -13
LANSDOWNE ROAD
CRUMPSALL

DRAWING TITLE
PROPOSED ELEVATION
TO LANSDOWN ROAD

DRAWN BY	CHECKED BY
LK	
DATE	SCALE
19.10.2016	1:20 @ A1

DRAWING NO CPS 16 049 005b

cube.
Project Management | Building Surveyors
Heritage Consultants | Design Services
502 Birchwood One | Dewhurst Road | Warrington | WA3 7GB
t: 01925 831 710 | f: 01925 839 129
e: mail@cubepsl.co.uk | w: www.cubepsl.co.uk