self
architects

Chartered Architects
1 Haywood House Hydra Business Park Nether Lane Ecclesfield Sheffield S35 9ZX
Telephone: 0114 246 0500 Facsimile: 0114 246 0880
E-mail: design@selfarchitects.co.uk
Web: www.selfarchitects.co.uk

23 APR 2008

Proposed Works At Didsbury Village Restaurant, 846 Wilmslow Road, Didsbury

External

- White paint finish and mock shutters to be removed from front elevation.
- Escape door to front elevation to be replaced with something more authentic and main entrance door to be replaced with double doors.
- Gable chimney to be enlarged in matching reclaimed brick to incorporate new kitchen extract fan.
- Timberwork to front elevation to be redecorated in colours suitable to the age and character of the building (to be agreed with conservation officer).
- Extract chimney to be removed from rear roof.
- Corrugated steel roof to be removed and roof structure replaced. New roof covering (material to be agreed with conservation officer) incorporating glazed roof lights to be fitted.

Internal – Ground Floor

- All kitchen equipment, bar, fixtures, fittings and furnishings to be removed and carted away.
- Internal staircase and adjacent timber wall to be removed.
- Internal wall adjacent to front door to be removed.
- Existing dry goods store to be removed.
- Structural alterations to be made to rear staircase supporting walls and new disabled WC created. New staircase in new configuration to be fitted.
- Alcoves cut in main rear internal dividing wall for fixed seating.
- Opening to be created in existing floor to expose the original cellar and stone winding cellar steps. Contemporary glass box table constructed over.
- Two new bars and glass wash area to be created.
- New dumb-waiter hoist to be fitted.
- Establishment to be redecorated throughout with new fixtures and fittings.

Internal – First Floor

- All kitchen fixtures, fittings and furnishings to be removed and carted away.
- Toilets to be reconfigured and fitted with new cubicles and sanitary ware.
- Stud partition to be installed to create a corridor to the new kitchen.
- Kitchen to be created with new stainless steel equipment, extract canopy, etc.