A1

MOSTON LANE

227

239

School House

Moston Lane Community Primary School

Hough Hall

2Nr new Fabric Architacture 7m x 5m "classroom" canopies

Extend 1.2m high roll top steel fence and gate by approx 8000mm

All 300mm high brick walls removed

2m high palisade fence and gate

3Nr picnic tables

LC

LEGEND

I.C. Inspection Chamber

Rainwater gulley

Back inlet rainwater gulley

ACO channel

Road type gulley

Trees

Specification for the tarmac:
50mm base coarse with 20mm limestone aggregate
30mm wearing coarse with 10mm aggregate for car park areas or 6mm aggregate for playgrounds
Regulating coarse using base material.

New fencing to be 1.2m high coloured 'roll-top' fencing to match existing outside foundation classroom.

Rev	Description	Date	By	Checks

MINSTRAL DEVELOPMENTS LTD
CHARTERED BUILDING SURVEYORS & ACCESS CONSULTANTS
16 The Bryceway
West Derby
Liverpool
L12 3HJ
Tel: 0151 228 8800
Fax: 0151 228 8800

This drawing is copyright. DO NOT SCALE from this drawing.
The contractor and any subcontractor shall verify ALL dimensions on site prior to making shop drawings or commencing manufacture.

JOB TITLE: **Moston Lane Primary School**

DRAWING TITLE: **Junior Playground Resurfacing**

COMPUTER FILE	DATE	SCALE	DRAWN	CHECK
CURRENT PROJECTS	JUN 08	-	MJ	MJ

JOB NUMBER	DRAWING NO.	REVISION
ED 35682	02	-