N

W E

S

PROPOSED CHS POLES AND FIXINGS TO BE REPLACED AS REQUIRED (SUBJECT TO STRUCTURAL CALCULATIONS)

PROPOSED REMOVAL & REPLACEMENT OF 1No. EXISTING VF ANTENNA WITH 1No. PROPOSED ANTENNA FIXED TO CHIMNEY ON POLE MOUNT PAINTED TO MATCH BRICKWORK

PROPOSED 2No. RRU's FIXED TO CHIMNEY & PAINTED TO MATCH BRICKWORK

PROPOSED RELOCATION & REPLACEMENT OF 1No. EXISTING VF ANTENNA WITH 1No. PROPOSED ANTENNA FIXED TO CHIMNEY ON NEW POLE MOUNT PAINTED TO MATCH BRICKWORK

EXISTING 150 WIDE CABLE TRAY FIXED TO EXTERIOR WALL & COLOUR CODED TO MATCH BRICKWORK.

ELEVATION

PROPOSED REMOVAL & REPLACEMENT OF 1No. SPITFIRE ENCLOSURE WITH 1No. JSC CABINET & 1No. 3900AL CABINET ON EXISTING GRILLAGE, EXISTING MEAS UNIT TO BE RELOCATED TO JSC CABINET

PROPOSED EXISTING MESH FLOORING TO BE MODIFIED TO ALLOW FIXINGS FOR PROPOSED CABINETS TO EXISTING STEELWORK

EXISTING VF SCREEN & SUPPORT FRAME AROUND GRILLAGE PAINTED TO MATCH BRICKWORK

EXISTING HANDRAIL AND SELF CLOSING GATE FIXED TO EXISTING GRILLAGE

EXISTING LADDER ACCESS TO GRILLAGE

EXISTING OLO DISHES

EXISTING POWER CABLE ROUTE FROM CELLAR RUNS EXTERNALLY ROUND WALLS.

EXISTING SUBMETER WITHIN BUILDING

NOTE:
EXISTING FEEDER CABLES TO BE DISCONNECTED, TESTED, RECONNECTED IF SUITABLE (OTHERWISE REPLACED) TO PROPOSED ANTENNAS. EXISTING CABLE TRAY TO BE REUTILISED WHERE POSSIBLE

UPGRADE SUBJECT TO STRUCTURAL SURVEY & CALCULATIONS

PROPOSED REMOVAL & REPLACEMENT OF 1No. EXISTING VF ANTENNA WITH 1No. PROPOSED ANTENNA FIXED TO CHIMNEY ON POLE MOUNT PAINTED TO MATCH BRICKWORK

PROPOSED 1No. RRU FIXED TO CHIMNEY & PAINTED TO MATCH BRICKWORK

EXISTING 150 WIDE CABLE TRAY FIXED TO EXTERIOR WALL (TRAY COLOUR CODED TO MATCH BRICKWORK)

GROUND LEVEL +0.0m

PROPOSED REMOVAL OF 1No. EXISTING VF ANTENNA AND FIXINGS

EXISTING 300 WIDE VERTICAL CABLE TRAY FIXED TO EXTERIOR WALL (TRAY COLOUR CODED TO MATCH BRICKWORK)

EXISTING GATE TO REAR YARD

EXISTING LANDLORDS SUPPLY TERMINATES AT LOCAL IP54 DISTRIBUTION BOARD

EXISTING ACCESS DOOR TO REAR YARD

The drawings comply with TEF & Vodafone Standard ICNIRP guidelines.
Designed in accordance with Cornerstone document: CORN/09/006

PROPOSED SITE PLAN
(1:100)

Notes:
1 ALL DIMENSIONS ARE IN MM UNLESS NOTED OTHERWISE

N.G.R.	E: 383957	N: 401452

PLANNING AND BUILDING CONTROL
13 MAR 2013

REV	MODIFICATION	BY	CH	DATE
A	Issued for Approval	SPD	DS	22.02.13

MONO CONSULTANTS LIMITED
No. 58 Cygnet Court
Timothy's Bridge Road
Stratford-upon-Avon
Warwickshire
CV37 9NW
t. 44 (0)1789 206500
f. 44 (0)1789 206529
www.monoconsultants.com

CTIL

Cell Name	Opt
515 CHEETHAM HILL ROAD	A

Cell ID No		
CTIL	Host	Sharer
(CTIL)129993	(VF)44518	(TEF) N/A

Site Address / Contact Details

515 CHEETHAM HILL ROAD
CHEETHAM HILL
MANCHESTER
GREATER MANCHESTER
M8 9HD

Drawing Title: SITE PLAN

Purpose of issue: PLANNING

Drawing Number: 201

Scale:	Drawn:	Date:	Issue:
As Shown	SPD	22.02.13	A

Checked:	Date:	Approved:	Date:
DS	22.02.13	AB	22.02.13

NOTE:
ALL NEW ANTENNAS AND FEEDER/TRAYWORK TO BE PAINTED TO MATCH BRICKWORK

PROPOSED RELOCATION & REPLACEMENT OF 1No. EXISTING VF ANTENNA WITH 1No. PROPOSED ANTENNA FIXED TO CHIMNEY ON NEW POLE MOUNT PAINTED TO MATCH BRICKWORK

PROPOSED REMOVAL & REPLACEMENT OF 1No. EXISTING VF ANTENNA WITH 1No. PROPOSED ANTENNA FIXED TO CHIMNEY ON POLE MOUNT PAINTED TO MATCH BRICKWORK

TOP OF PROPOSED ANTENNAS
+13.1m AGL

U/S OF PROPOSED ANTENNAS
+11.1m AGL

PROPOSED 2No. RRU's FIXED TO CHIMNEY & PAINTED TO MATCH BRICKWORK

EXISTING 150 WIDE CABLE TRAY PAINTED TO MATCH BRICKWORK

PROPOSED CHS POLES AND FIXINGS TO BE REPLACED AS REQUIRED (SUBJECT TO STRUCTURAL CALCULATIONS)

UPGRADE SUBJECT TO STRUCTURAL SURVEY & CALCULATIONS

PROPOSED REMOVAL OF 1No. EXISTING VF ANTENNA AND FIXINGS

TOP OF VF ANTENNA
+14.9m AGL

U/S OF VF ANTENNA
+13.3m AGL

NOTE:
EXISTING FEEDER CABLES TO BE DISCONNECTED, TESTED, RECONNECTED IF SUITABLE (OTHERWISE REPLACED) TO PROPOSED ANTENNAS



PROPOSED REMOVAL OF 150 WIDE CABLE TRAY AS REQUIRED

EXISTING 150 WIDE CABLE TRAY PAINTED TO MATCH BRICKWORK

EXISTING 300 WIDE VERTICAL CABLE TRAY PAINTED TO MATCH BRICKWORK

EXISTING VF SCREEN & SUPPORT FRAME AROUND GRILLAGE PAINTED TO MATCH BRICKWORK

PROPOSED REMOVAL & REPLACEMENT OF 1No. SPITFIRE ENCLOSURE WITH 1No. JSC CABINET & 1No. 3900AL CABINET ON EXISTING GRILLAGE, EXISTING MEAS UNIT TO RELOCATE TO JSC CABINET

GL

PROPOSED SITE ELEVATION
(1:100)

The drawings comply with TEF & Vodafone Standard ICNIRP guidelines.
Designed in accordance with Cornerstone document: CORN/09/006

Notes:
1 ALL DIMENSIONS ARE IN MM UNLESS NOTED OTHERWISE

N.G.R. E: 383957 N: 401452

PLANNING AND BUILDING CONTROL
13 MAR 2013

REV	MODIFICATION	BY	CH	DATE
A	Issued for Approval	SPD	DS	22.02.13

mono
MONO CONSULTANTS LIMITED
No. 58 Cygnet Court
Timothy's Bridge Road
Stratford-upon-Avon
Warwickshire
CV37 9NW
t. 44 (0)1789 206500
f. 44 (0)1789 206529
www.monoconsultants.com

CTIL

Cell Name	Opt
515 CHEETHAM HILL ROAD	A

Cell ID No

CTIL	Host	Sharer
(CTIL)129993	(VF)44518	(TEF) N/A

Site Address / Contact Details

515 CHEETHAM HILL ROAD
CHEETHAM HILL
MANCHESTER
GREATER MANCHESTER
M8 9HD

Drawing Title: PROPOSED SITE ELEVATION

Purpose of issue: PLANNING

Drawing Number: 302

Scale:	Drawn:	Date:	Issue:
As Shown	SPD	22.02.13	A

Checked:	Date:	Approved:	Date:
DS	22.02.13	AB	22.02.13