Exterior Front Elevation

Scope of Works

1.1 Re-finish existing wordmark black
1.2 Re-paint signage fascia grey
1.3 Replace existing blade sign logo with new logo
1.4 Replace existing barriers with new green barriers
1.5 Strip back paint work to expose original bronze mullions
1.6 Repaint existing light fittings to match signage fascia
1.7 Replace ironmongery with new to match strip backed bronze shopfront
1.8 Replace back nosing to entrance steps
1.9 Remove existing window roundel make good bulkhead





Existing Storefront



Proposed Storefront

Proposed Signage & Storefront