Copyright of this drawing is owned by Focus Design Ltd -
Do not reproduce, distribute without written consent.

NOTES

All dimensions to be checked on site and any discrepancies notified prior to commencement of work.
If in doubt, ask.

FOCUS DESIGN CONTACTS

Martin Hatchett
Mob: 07584 283750 E: martinh@focus-design.co.uk

Ian Cross
Mob: 07977 547712 E: ian@focus-design.co.uk

Lucy Henderson
Mob: 07810 873340 E: lucy@focus-design.co.uk

James Hamilton
Mob: 07810 838639 E: james@focus-design.co.uk

Emma Schofield
Mob: 07769 534 552 E: emma@focus-design.co.uk

Julia Kidd
Mob: 07779 594010 E: julia@focus-design.co.uk

FOCUS DESIGN Ltd
15a Parchment Street, Winchester, Hants, SO23 8AZ.

ESCAPE ONLY TO FRONT
CLEAR WIDTH 2350 MINIMUM

SERVICE ACCESS ONLY
CLEAR WIDTH 1500

3745
2745
13647

BREEZE SCREENS
BREEZE SCREENS TO BE SUPPLIED WITH FIXED BASES SET INTO EXISTING PAVED FINISH
BANQUETTE SEATING TO DETAIL
BAR SERVERY
TILL
2.5m x 3.5m JUMBRELLA
NEW JUMBRELLAS TO BE SUPPLIED WITH LIGHTING AND HEATING. INSTALL NEW SUNKEN JUMBRELLA BASE AND NEW UNDERGROUND CONDUIT FOR JUMBRELLA POWER SUPPLY, ALLOW TO LIFT AND RELAY EXISTING SLABS
BOOTH SEATING TO DETAIL
FEMALE W/C D9
D10
D12
D8
ALLOW FOR FULL REFURBISHMENT TO LADIES W/CS
GENTS W/C
ALLOW FOR FULL REFURBISHMENT TO GENTS W/CS
CELLAR WITH PLANT EQUIPMENT ABOVE
EXIT
D16
OFFICE
ALTER AND ADAPT EXISTING DRY STORE TO ALLOW FOR NEW OFFICE LOCATION. ALLOW FOR NEW FLOORING AND CEILINGS
D17
DRY STORE
ELECS
EXIT
D20
STAFF ROOM
D7
STORE
D6
D11
D15
D18
D19
D21
D23
D24
MALE W/C
FEMALE W/C
TILING AND ADHESIVE TO ALL FRONT OF HOUSE AREA TO BE REMOVED LEAVING APPROXIMATE 12mm FLOOR FINISH DEPTH, ALLOW FOR NEW SELF LEVELLING LATEX SCREED OVER EXISTING SCREED, CONSIDER KARNDEAN LATERATIVE FLOORING TO DINING AREA
AMEND ENTRANCE TO CUSTOMER TOILETS AS SHOWN
D5
D13
D14
D22
REFUSE
COLD STORE
FREEZER
HIGH CHAIRS
KITCHEN
NEW ALTRO FLOOR TO KITCHEN OVER EXISTING GRANOLATED SCREED
MENU BOX
PROVIDE NEW UNDERGROUND CONDUIT FOR MENU BOX POWER SUPPLY
ENTRANCE LOBBY
D2
MAIN ENTRANCE
D1
INSTALL NEW 1200mm HIGH POWDER COATED STEEL POSTS TO HOLD BACK ENTRANCE DOORS AS SHOWN
EXTERNAL DEMISE LINE
BREEZE SCREENS
2.5m x 3.5m JUMBRELLA
NEW JUMBRELLAS TO BE SUPPLIED WITH LIGHTING AND HEATING. INSTALL NEW SUNKEN JUMBRELLA BASE AND NEW UNDERGROUND CONDUIT FOR JUMBRELLA POWER SUPPLY, ALLOW TO LIFT AND RELAY EXISTING SLABS
BREEZE SCREENS TO BE SUPPLIED WITH FIXED BASES SET INTO EXISTING PAVED FINISH
BREEZE SCREENS
BANQUETTE SEATING TO DETAIL
BOOTH SEATING TO DETAIL
BOOTH SEATING TO DETAIL
BOOTH SEATING TO DETAIL
BOOTH SEATING TO DETAIL
BOOTH SEATING TO DETAIL
BANQUETTE SEATING TO DETAIL
TILING AND ADHESIVE TO ALL FRONT OF HOUSE AREA TO BE REMOVED LEAVING APPROXIMATE 12mm FLOOR FINISH DEPTH, ALLOW FOR NEW SELF LEVELLING LATEX SCREED OVER EXISTING SCREED, CONSIDER KARNDEAN LATERATIVE FLOORING TO DINING AREA
TILL
W/S
DUMPS AREA
28A.
37B.
D4
BABY CHANGE
D3
ACCESSIBLE W/C
STORE / CLEANERS
37C.
ALTER AND ADAPT EXISTING WALLS TO ALLOW FOR NEW ACCESSIBLE WC AND STORE/CLEANERS. ALLOW FOR NEW FLOORING AND CEILINGS
W/S
D25
GAS

N

PROPOSED LAYOUT
SCALE 1:50

Dates	Rev	Comments

focus design Ltd

CLIENT
TRAGUS GROUP PLC

PROJECT
BELLA ITALIA
PARRS WOOD LEISURE PARK
MANCHESTER

DRAWING TITLE
PROPOSED LAYOUT

SCALE : 1:50 @ A1
DATE : 17.01.12
DRAWN BY : AB

1137.11.P01 *