Predevelopment tree survey

Tree No	Species	Height (m)	T/dia (mm)	RPA (m2)	Crown Spread (m) N	E	S	W	H of L Branch (m)	Relative Vigour	Useful Life expectancy	Age Class	Retention Category	Structural Condition - Comments
Survey ref:	10188- Trenchard Drive, Manchester, M22 5NA												Date:	09/10/2011
T1	Scots Pine *Pinus sylvestris*	14	589	157	5.5	6	3.5	7.5	4	GOOD	>40	M	A	GOOD - Crown raise 5.5m above road. Remove deadwood
T2	Scots Pine	15.5	414	77.5	4	3	2	6	6.5	GOOD	>40	M	A	GOOD - Remove deadwood
T3	Scots Pine	15.5	668	201.9	5.5	6.0	4.5	7	4.5	GOOD	>40	M	A	GOOD - Crown raise 5.5m above road. Remove deadwood
T4	Scots Pine	12.5	477	102.9	5	6.5	3.5	0	3.5	GOOD	>40	M	C	GOOD - Crown raise 5.5m above road. Severe lean on tree. Remove deadwood
T5	Scots Pine	13	382	67.1	6.5	2	2.5	5	3.5	GOOD	>40	M	A	GOOD - Crown raise 5.5m above road. Remove deadwood.
T6	Scots Pine	13	513	119.1	5.5	6.5	4	5.5	3.2	GOOD	>40	M	C	FAIR - Heavy laterals with broken limbs at crown break. Crown raise 5.5m above road. Remove deadwood and broken limbs from crown.
T7	Scots Pine	12	382	66	3	8	3	2.5	5.5	GOOD	>40	M	B	GOOD - Suppressed by other trees. Remove deadwood
T8	Scots Pine	14	493	110	6	6	4	5	5	GOOD	>40	M	A	GOOD - Scarred at base. Crown raise 5.5m above road. Remove deadwood.
T9	Scots Pine	12.5	700	221.7	4	7	10	4.5	3.2	GOOD	>40	M	A	GOOD - Ivy present on stem of tree. Crown raise 5.5m above road. Remove deadwood.
T10	Sycamore *Acer pseudoplatanus*	6	318	45.8	3	3.5	5.5	3	1.5	GOOD	10-20	Y	C	GOOD - Twin stem with defects within crown. Remove tree to improve the standard of tree stock.
T11	Ash *Fraxinus excelsior*	13.5	553	138.4	7	9	11	8	4	GOOD	20-40	M	B	GOOD - Stubs present within crown. Crown raise 5.5m above road. Remove deadwood.
T12	Silver Birch *Betula pendula*	12	228	23.5	2	2	4	4	2.5	GOOD	>40	MA	B	GOOD - Located outside site boundary. Crown raise 5.5m above road.
T13	Elder *Sambuca nigra*	3.5	191	16.5	3	2	3	2	1	GOOD	10-20	MA	C	GOOD - Self seeded.

Tree No	Species	Height (m)	T/dia (mm)	RPA (m2)	Crown Spread (m) N	E	S	W	H of L Branch (m)	Relative Vigour	Useful Life expectancy	Age Class	Retention Category	Structural Condition - Comments
Survey ref:	10041 - Trenchard Drive, Manchester												Date:	09/10/2011
T14	Hawthorn *Crataegus monogyna*	6	240	26.1	3	4	3	4	1.2	GOOD	>40	MA	C	GOOD
T15	Ash	11	800	289.6	9	7	5	6.5	1.5	GOOD	20-40	M	C	FAIR - Twin stem. Crown raise 5.5m above road. Remove deadwood.
T16	Beech *Fagus sylvatica*	10	624	176.2	3	4	5	6	1	GOOD	<10	MA	R	FAIR - Climber present on scarred stem located very close to boundary of neighbouring property. Remove tree as tree is suffering in its location and from previous work.
T17	Beech	9	656	194.7	6	5	2	6	1	GOOD	20-40	MA	C	FAIR - Close to T16 but is a better specimen with fewer defects.
T18	Ash	11	678	208	5	6	5	5	2.4	POOR	<10	M	C	FAIR - Twin stem with die back to crown. Barbed wire present deep within stem. Remove tree.
G1	Hawthorn and mixed species hedge	5.5	200	NA		2		3	0.1	GOOD	20-40	Y	C	GOOD
G2	Hawthorn and mixed species hedge	4	200	NA		2		2	0.1	GOOD	20-40	Y	C	GOOD

This survey is a reissue of data collected October 2010. Three pruning wounds have been made to the group of Scotts Pine (T1-T9).

All trees except T12 are located within the site boundary.

T1, T2, T3, T5, T8 and T9 are classed as grade A trees.

T7, T11 and T12 are classed as grade B trees.

T4, T6, T10, T13, T14, T15, T17 and T18 are classed as grade C trees.

T16 is classed as grade R not worthy of retention.

