Design & Access Statement

Increase in the height of the existing yard wall at The Sherwood Public House Claremont Road Rushholme.

The applicant wishes to formalise existing construction that was carried-out approx. 2 years ago by the previous owners of the site. The existing brick wall was 1100 mm height to the yard area of the public house and subsequently was in creased a further 1100mm to a total height of 2200mm for security reasons (cars were being vandalised). The new brickwork marches the existing in colour and type .New timber gates are to be erected at the existing entrance location and the existing pavement crossing unaltered..

