Ref 2106

28 Roseneath Avenue

| Item No | Description | Unit | Num (nr) | | |
|---|---|---|---|---|---|
| | The contractor is required to include for everything necessary to complete the works in their entirety. | | | | |
| | The contractor will be responsible for taking his own site dimensions and should allow for this in his prices. | | | | |
| R201 | Provide and install new double gate; as detail on drawing HTS/AS/01/2 without panels; complete with supporting posts, width of the gate to suite existing opening; overall opening size: 2750mm wide illustrated in photograph 1; include for associated ironmongery as indicated on the drawing and specification ref: Q40 - Gates; make good all work disturbed to match exisiting. | Nr | 1 | | |
| | | | | | |
| R201 | Provide and install new double gate; as detail on drawing HTS/AS/01/2 with side panel; complete with supporting posts, width of the gate to suite existing opening; overall opening size: 2760mm wide illustrated in photograph 2; include for associated ironmongery as indicated on the drawing and specification ref: Q40 - Gates; make good all work disturbed to match exisiting. | Nr | 1 | | |
| | | | | | |
| R96 | Allow for decoration to the gates and posts; in accordance with specification; finished colour black. | M2 | 13.3 | | |
| | The cylinder locks and mastered keys are to be obtained from the Community Ironworks, The Security Park, Cambrian Street, Beswick, Manchester M11 3FY; or other approved supplier to be agreed with the CA. | | | | |
| R215 | Allow for a one off "mastering" charge per cylinder (one off cost for each new master keyed cylinder) Note: each subsequent replacement cylinder ordered will not incur the one off mastering charge.(Double gate) | Nr | 1 | | |
| | | | | | |
| R209 | Allow for providing keys to all residents of properties on the alleyways enclosed; keys ordered at time of cylinder. | Nr | 39 | | |
| | | | | | |
| R214 | Complete Padlock and core (Double gate) | Nr | 2 | | |

** Price is subject to change depending on size of gate/ panel.