999 Stockport Road,
Manchester,
Lancashire
M19 2SY

30 April 2013

To Whom It May Concern

Further to my recent visit to your premises.

I have assessed the work that needs to be carried out at the premises. I expect the project to require a 12ft Canopy with 5 baffle filters &
6 Sheets on the wall

The project will also require a ventilation system which will have to be taken through the property internally. The ventilation would require a 500mm fan, 2 silencers, 1 pre paper filter & 1 carbon filter for the odour.

Based on the 500mm duct and a 50jm fan and an air volume of 1.4m3/s, the pressure would be approx 196pa, I would use 2 silencers then the noise level would be approx 48db at 3m.

If you need any further information please do not hesitate to contact us.

Kind Regards,

Mohammad Awais