Seymour Road School – Design Statement

The existing 2 no. GRP barrel rooflights are to be replaced due to repeated maintenance and vandalism issues. A new steel roof deck will be installed and covered with a new Garland built up roofing system. The cap sheet will be dark grey.



Photograph 1 – Existing Rooflight



Photograph 2 – Existing Rooflight

Other works will include:

Repairs to existing roof vent following theft of leadwork. Replacement will be either GRP or aluminium sheeting.

Repairs will be carried out to the existing perimeter parapets and all valley gutters to include Garland system coating to existing GRP inserts.

N.B. Due to previous issues with theft any missing leadwork will be replaced with GRP or similar.



Photograph 3 – Existing decorative roof vent