Proposed ball stop fence on kerb edge to perimeter refer to Thornton specification

Proposed floodlights refer to Thornton specification

Existing Coop Academy

CP101 CP103 CP104 CP102 CP105 CP106

8000 15463 6000 24534 2000 24000

Proposed dividing net between practice pitches

2 No. trees to be relocated

Existing Athletics Lanes

Proposed All Weather Pitches

nominal level +87.45

nominal fall 1:100 ——>

96926 31858 6000

Proposed dividing net between practice pitches

existing concrete planter walls to be removed

new paths & single gates to AWP

2 No. trees to be replanted adjacent athletics lanes

2 No. lanes to be removed remedial works to outer lanes as required

24534 6000 1546 8000

26175 8000 26175

CP100 CP111 CP108 CP110 2000 CP109 CP107

new double gate to AWP to be installed - location tbc

Existing car park

Notes

Copyright: All rights reserved.
This drawing must not be reproduced without permission.
This drawing must not be scaled. Dimensions are in millimetres unless specified.

REFER TO SPECIALIST INFORMATION FOR SYNTHETIC ALL WEATHER PITCH SPECIFICATION

- PITCH PERIMETER FENCE TO BE GENERALLY 3M HIGH TWIN BAR WELDMESH INCLUDING 1.2M HIGH LOWER REBOUND SECTION OF FENCE.

- 24M LONG X 4M HIGH FENCE AT EACH END BEHIND GOALS

- FENCE MATERIAL TO BE GALVANISED STEEL WITH BLACK POWDER COATED FINISH.

- 2 NO. 1.2M WIDE X 2.4M HIGH GATES AND 1 NO. 3M WIDE X 2.4M HIGH GATE TO BE INSTALLED

- 2 NO. RETRACTABLE DIVIDER NETS

North Point.

Key Plan.

Rev	Date	Revision Note	By	Check

Keepmoat
PROMISE. DELIVERED.

The Lighthouse
The Quays
Salford
M50 3BF.

Tel: 0161 876 6000
Email : info@keepmoat.com

Job title: Cooperative Academy of Manchester					
Drawing title: Proposed All Weather Pitch Plan					
Status: PLANNING		File Name: siteplan		XrRef File:	
Drawn by: GMcD	date: Aug'13	checked by	date	Scale at A1: 1:200	Scale at A3: 1:400
Job No.		CPI cat. AL		Dwg No. CA 03	Revision -
Contractors Drawing No.					