

Side Elevation



Rear Elevation

Specification:

100 x 100mm Timber Posts with 150 x 50mm Softwood equally spaced Timber Rafters fixed to Timber Wall plate. 20 x 100mm fascia board secured to Rafters; uPVC guttering to match existing fixed to fascia board. Roof Covering triplex Glazing secured to rafters



Front Elevation

Covered Area to finish in line with Window Mullion

Specification:

100 x 100mm Timber Posts with 150 x 50mm Softwood equally spaced Timber Rafters fixed to Timber Wall plate. 20 x 100mm fascia board secured to Rafters; uPVC guttering to match existing fixed to fascia board. Roof Covering triplex Glazing secured to rafters

PLANNING

25 FEB 2009

REV	DESCRIPTION	DATE	BY	CHECKED	APPROVED
A	ISSUED FOR APPROVAL	16.02.09	SAJH	SP	SP

ESPEE DESIGN & DEVELOPMENT

33 Chapel Lane
Wilmslow
SK9 5HW

Tel 01625 521904

Email: Spool@espee.fsnet.co.uk

project	The Portway, Wythenshaw		
drawing	Elevations as Proposed		
date	Feb '09	drawn	S. Hamilton
scale	1:50	dwg N°	Pun/Pway-003