925.000E | 950.000E | 975.000E | 1000.000E | 1025.000E

3000.000N

2975.000N

2950.000N

2925.000N

SOUTH ELEVATION

EAST ELEVATION

NORTH ELEVATION

WEST ELEVATION



CO-ORDINATED STATIONS

STATION	EASTING	NORTHING	LEVEL (m)
A	1000.000	3000.000	100.000
B	1000.000	3000.000	100.000
C	1000.000	3000.000	100.000
D	1000.000	3000.000	100.000

ABBREVIATIONS

AV	AIR VALVE/VENT	IC	INSPECT CHAMBER
BOL	BOLLARD	IL	INVERT LEVEL
BB	BELISHA BEACON	JKW	JAPANESE KNOTT WEED
BM	BENCH MARK	LH	LAMP HOLE
BL	BED LEVEL	LP	LAMP POST
BS	BUS STOP	NP	NAME PLATE
BT	BRITISH TELECOM	MH	MANHOLE
CL	COVER LEVEL	PS	POST/SIGN POST
Dil	DILAPIDATED	PB	POST BOX
Dis	DISUSED	PX	UNKNOWN SERVICE
EL	EAVES LEVEL	RE	RODDING EYE
ELE	ELEC JUNCT. BOX	RL	RIDGE LEVEL
EP	ELECTRICITY POLE	RS	ROAD SIGN
FH	FIRE HYDRANT	ST	STOP TAP
FL	FLOOR LEVEL	TH	TRIAL HOLE
FOS	FULL OF SEDIMENT	TL	TRAFFIC LIGHT
FP	FLAG POLE	TP	TELEGRAPH POLE
G	GULLY	TV	CABLE TV BOX
GM	GAS METER	UtI	UNABLE TO LIFT
GV	GAS VALVE	WM	WATER METER

SYMBOLS

	SURVEY STATION		TREE
E	O\H ELEC CABLE		BENCH MARK
T	O\H PHONE LINE		TRIAL PIT
	CANOPY\HEDGE		BOREHOLE

NOTES

A) ONLY MANHOLES AND SERVICES VISIBLE AT TIME OF SURVEY SHOWN

B) LOCAL GRID USED AND ORIENTATED TO MAGNETIC NORTH

C) LEVELS IN METRES RELATED TO O.S.B.M.

D) DRAINAGE INFORMATION TAKEN FROM LOCAL AUTHORITY RECORDS. INFORMATION MUST BE CHECKED PRIOR TO WORK COMMENCING

Rev	Description	Date

PROPOSED DEVELOPMENT AT CHAPTMAN STREET, GORTON.

ARCHITCTURAL DESIGN SERVICES

TOPOGRAPHICAL SURVEY

AD067 / T00

Drawn	S. FAIRHURST
Date	FEBRUARY 2012
Scale	1:200 @ A1

RJP Surveying Consultants Ltd
LAND SURVEYORS & SITE ENGINEERS
AYREFIELD COTTAGE
AYREFIELD ROAD
ROBY MILL
UPHOLLAND
LANCASHIRE
WN8 0QP
TEL: 01257 251554
MOBILE: 07710 308709
WEBSITE : www.rjpsurveyors.co.uk
E-MAIL: mail@rjpsurveyors.co.uk