DV8DESIGNS
ARCHITECTURAL & INTERIOR DESIGNERS

PROJECT NAME:
Bukhara (Former Cheetham Town Hall)

PROJECT NO:
1564

ADDRESS:
107, Cheetham Hill Road, Manchester, M47EP

Ref	Description	Quantity	Unit	Rate	Ext
	Demolition and Alteration				
	Basement				
	Ground Floor				
1	Removal of double doors (in replacement of new fire rated windows and stud wall (See window schedule drawing 1564-xxx))				-
2	Break through existing wall and ground floor ceiling - - to form new lintelled opening for new disabled platform lift. Make good to reveals, floor and head soffit and line. See manufacturers technical and booklet information.				-
3	Removal of an external window to allow for new cold store door				-
4	Removal of sections of tiles in staircase area to allow for new tiles				-
5	Allow for removal of tiles in left hand area for new tiles				-
6	Removal of Ceiling bulkhead and lighs in right hand room (on stairside wall)				-

7	Removal of flooring and Ceiling to allow for lift plate and shaft					-
						-
	First Floor					-
8	Removal of vinyl on window to rear elevation					-
						-
	Mezzanine					-
						-
9	Removal of boiler room stud wall - to be relocated					-
10	Relocation of existing boiler					
11	Removal of existing urinals					
12	Relocation of existing sinks, with the removal of vanity unit					-
					Demolition and Alteration	**-**