

aa projects

Notes:

Key

Site Boundary

Extent of Boundary Treatments

Boundary Treatments

1. Approximately 9m length of existing masonry wall to be retained at existing height.

2. Approximately 32m length of wall to be reduced to a height of approximately1.2m above ground level. Sports fence to be erected immediately adjacent t the reduced height masonry. Sports fence to be approximately 3m above ground level. Modesty panels to be secured to site side of the fence (Arrangement as per drawing 3224.104 Rev A).

3. Approximately 20m length of wall to be reduced to a height of approximately1.2m above ground level. Sports fence to be erected immediately adjacent t the reduced height masonry. Sports fence to be approximately 3m above ground level. Modesty panels to be secured to site side of the fence (Arrangement as per drawing 3224.104 Rev A).

Copyright: All rights reserved. This drawing must not be reproduced without permission from AA Projects Ltd. Do not scale off this drawing. All dimensions are to be checked on site by contractor / sub contractor. Any discrepancies to be reported to AA Projects Ltd.

Rev	Date	Revision notes	By	Che
A	28.4.14	Notes amended to include description of modesty panels	JK	SI

aa projects
6 Pullan Way
Howley Park Business Village
Morley
Leeds
LS27 0BZ
Tel: 0113 238 3379
Fax: 0113 238 3370
Additional offices in Birmingham, Liverpool, London, Manchester and Newcastle
www.aaprojects.co.uk

Client
University of Manchester
Design Services Unit

Drawing Title
Proposed Works
Site Setting Out Plan

Project Title
St Gabriel's Hall
Netball Court Boundary
Wall Repair

Drawn: JK | Date: 02-04-14
Checked: SC | Date: 02-04-14

DWG No. 3224.105 | Scale: 1:500 | Revision:

A3