The use of this data by the recipient acts as an agreement of the following statements. Do not use this data if you do not agree with any of the following statements.

All drawings are based upon site information supplied by third parties and as such their accuracy cannot be guaranteed. All features are approximate and subject to clarification by a detailed topographical survey, statutory service enquiries and confirmation of the legal boundaries.

The controlled version of this drawing should be viewed in DWF or PDF format not DWG or other formats.

Where this drawing has been based upon Ordnance Survey data, it has been reproduced under the terms of Ryder Licence No. 100020144. Reproduction of this drawing in whole or in part is prohibited without the prior permission of Ordnance Survey.

Do not scale the drawing. Use figured dimensions in all cases. Check all dimensions on site. Report any discrepancies in writing to Ryder before proceeding.



Knauf Apertura perforated rafts and lining to soffit, with moulded plaster perimeter all on MF grid supported from existing soffit.

2 x 12.5mm Wallboard on MF grid supported from existing soffit. K10-225

1 x 12.5mm Wallboard on MF grid supported from existing soffit (to suspended rafts dressed into GRG perimeter upstand's and apertura panels). K10-225B.

2 x 12.5mm Wallboard on MF grid supported from existing soffit. (Moisture Resistant). K10-225A.

GRG soffit / ceiling mounted rafts supported from existing soffit. (150mm upstand to raft).

2 x 15mm Fireshield on MF Grid supported from existing soffit with insulation between framing. K10-226.

Metal perforated ceiling panel system. With openable panels to provide services access.

K10/228 -TLFR board 136mm thick direct fix to existing soffit. To receive uni-strut supports for services.

K10/891 - TLFR board with 40mm Vermiculux fixed directly to soffit (with no voids above) to provide a minimum 4hr FR.

Concrete Sealer to underside of proposed slab.

Lift shaft internal metal soffit.

Existing perimeter of ceiling and coving retained with new lath and plaster ceiling to tie in with existing.

Existing ceiling and coving retained with minor alterations where required - General ceiling

NB - Min. 300mm (subject to existing coving) strip to perimeter of room to be maintained to allow new ceiling to blend seamlessly into this ceiling.

Existing ceiling retained - High Significance

Proposed Apertura random circular perforated plasterboard ceiling with integrated access panels and lighting. (Pattern proposed shown).

Proposed Access Hatch

Proposed new coving to match existing coving to room highlighted.

Proposed location of projector and suspended light fittings to feature areas. with furniture location below.

Indicates proposed locations of roller racking below.

Indicates indicative locations of PA system TBC with NG Bailey proposals. Indicates indicative locations of CCTV, PIR system TBC with NG Bailey proposals.

Indicates indicative locations of recessed downlighters.

Indicates indicative locations of recessed strip lighting

Indicates indicative locations of grilles for specification refer to NG Bailey design.

Indicates indicative locations of burgess access panels.

PB SO — Indicates Plasterboard structural opening for lights, access panels etc.

VA SD CCTV RL HD — Indicates indicative location of Voice Alarm (VA) speakers, Smoke Detectors (SD), CCTV cameras, recessed Luminaire's (RL), Heat Detectors (HD).

Full co-ordination between Mechanical and Electrical services required prior to installation.

Light lengths shown based on information provided by NG Bailey. Should light lengths shown change setting out shown will need to be revised.

CL-03-04
Chief Librarian's Office
Meeting Room
45 m²

CL-03-03
Circulation
33 m²

CL-03-02
Store
4 m²

CL-LG-52
Lift 01
7 m²

CL-LG-53
Lift 02
7 m²

CL-03-01
Circulation Core
146 m²

CL-03-31
Female W.C.
11 m²

CL-03-32
Cl. St.
2 m²

CL-03-35
Toilet Lobby
3 m²

CL-03-43
Riser 02
4 m²

Stair D

3820 mm

3980 mm

3970 mm
Existing Ceiling Level

3970 mm
Existing ceiling level0
Riser 06
5 m²

3970 mm
Existing ceiling level

3500 mm

2435 mm
250mm min. ceiling void

2435 mm
250mm min. ceiling void

2435 mm
250mm min. ceiling void

2435 mm
250mm min. ceiling void

CL-AH-03-028
CL-AH-03-027
CL-AH-03-025
CL-AH-03-026
CL-AH-03-024
CL-AH-03-023
CL-AH-03-029
CL-AH-03-030
CL-AH-03-031
CL-AH-03-032
CL-AH-03-033
CL-AH-03-034
CL-AH-03-035
CL-AH-03-036
CL-AH-03-037

B-B
451-03451-Rev-

C-C
451-03451-Rev-

F-F
451-03451-Rev-

Outside face of bulkhead (to line through with steel plate fascia above)

26727 mm

24740 mm

23148 mm

22944 mm

22584 mm

22584 mm

22584 mm

22584 mm

Centreline of access road/TX, floodlighter and CCTV, PIR's etc

Outside face 150mm steelwork upstand

Outside face 150mm steelwork upstand

Outside face 150mm steelwork upstand

Bulkhead line beyond upstand

Bulkhead line beyond upstand

Bulkhead line beyond upstand

Heritage light fittings to retained female WC at third floor.

No Ceiling

No Ceiling

600x600mm plasterboard faced access panel to access control gear.

Metreel Track zone. Cleaning and maintenance strategy to windows above VCC. Max. 500mm from wall line. Access on to track from landing in front of store (CL-03-02) only.

Metreel Track zone. Cleaning and maintenance strategy to lift glazing

3820mm ceiling level upstand to line through with bulkhead to back of 150mm upstand to 3500mm raft below.

Aligned to edge of perimeter

cl/ 12.40
cl/ 12.20
cl/ 12
cl/ 11.40
cl/ 11.20
cl/ 11
cl/ 10.40
cl/ 10.20
cl/ 10
cl/ 09.40
cl/ 09.20

Revision	Date	Drawn By
G	16/08/13	SAy

Access panels added.

Revision	Date	Drawn By
F	21/06/13	TTa

Layout updated.

Revision	Date	Drawn By
E	11/06/13	SAy

Ceilings to WC's revised and proposed lighting shown. Refer to NG Bailey's drawings for final lighting types.

Revision	Date	Drawn By
D	29/04/13	DcN

Access hatch 300x300 added to access M&E control gear above ceiling level.

Revision	Date	Drawn By
C	28/01/13	DcN

3 additional hatches added for access in VCC area

Revision	Date	Drawn By
B	27/11/12	SAy

Ceiling layout revised in line with M&E requirements. Metreel rail setting out length added.

Revision	Date	Drawn By
A	21/01/12	SAy

Construction Issue

Status
Construction

Project
Manchester City Council
Central Library
St Peters Square, Manchester

Ryder Project Ref: 2164

Drawing
Proposed Detailed Ceiling Plan - Third Floor Plan 2

Project No. — Drawing No.
1255-RYD-DR355-03351-RevG

Scale at A0 — Drawn By
As indicated SAy

info@ryderarchitecture.com
www.ryderarchitecture.com

Ryder

Detailed Ceiling Plan - Third Floor Plan 02

1 : 50