

Proposed Furnitubes College plastic coated steel cycle stand.



Existing carved log seating to be retained and relocated.



Proposed LostArt Cartmel Seat

Proposed Marshalls Ferrocast Heritage Polyurethane Litter Bin

This drawing has been prepared in accordance with the scope of URS's appointment with its client and is subject to the terms of that appointment. URS accepts no liability for any use of this drawing other than by its client and only for the purposes for which it was prepared and provided.

© URS Infrastructure & Environment UK Ltd 2012

Revision Details	By	Date	Suffix
Removal of proposed Lost Art Rustic bench, to be replaced with Lost Art Cartmel, as agreed with HLF and client. Timber resting posts added. Addition of spec. references.	JW/SD	07.05.13	C
Removal of existing 15no. Ollerton benches. Proposed benches relocated.	CB/JW	03.01.13	B
Existing bins for removal. New bin proposed.	SC/JW	30.11.12	A

KEY

BENCHES

- Proposed LostArt Cartmel Seat (35 no.) *Refer to drawing 47061939-URS-LD-119.3 for fixing detail and Q50 of the landscape specification*
- Proposed location for carved log seating (2 no.)
- Play area seating to be retained in situ (5 no.)
- Picnic benches to be retained in situ (2 no.)
- Proposed location of relocated picnic benches (8 no.)
- Existing plinth positions to be retained and reused as foundations (9 no.)

Overview:

- 51no. existing seating items to be removed (43 general seating, 6 play area benches and 2 play area picnic benches).
- 10no. existing seating items requiring temporary removal, relocation & installation (including 2 log seating and 8 picnic benches).
- Proposed area of surfacing for seating areas: 3000(l) x 1000(w)mm, asphalt concrete surface & binder, 150mm Type 1 sub base with concrete edging.
- 5no. timber resting posts to be installed in locations agreed with the client. *Refer to drawing 47061939-URS-LD-119.3 for details.*

BINS

- Existing bins to be retained (2no.)
- Proposed bin locations (14 no. new) *Refer to drawing 47061939-URS-LD-119.3 for fixing detail and Q50 of the landscape specification*

Notes:
22no. existing bins and 4no. dog bins to be removed
Refer to drawing 47061939-URS-LD-121 and C20 of landscape specification

CYCLE STORAGE

- Proposed Furnitubes college cycle stand (4 sets of 3) *Refer to drawing 47061939-URS-LD-119.3 for fixing detail and Q50 of the landscape specification*

CLAREMONT ROAD
CHORLTON LODGE
SMALLDALE AVENUE
ALEXANDRA ROAD SOUTH
Changing Room Entrance
SECURE DEPOT
PAVILION
PRINCESS ROAD
DEMESNE ROAD

120m
80m
40m
0m

Plot Date :

AutoCAD File Name :

LOTTERY FUNDED

Project Title: ALEXANDRA PARK RESTORATION

Drawing Title: PROPOSED SEATING, BIN & CYCLE STORAGE LOCATIONS

47061939-URS-LD-114

Scale at A3 : Refer to scale bar

Drw CB	App SD	Rev
Chk JW	Date 08.10.12	Date

URS
Brunel House
54 Princess Street
Manchester, M1 6HS
Telephone (0161) 907 3500
Fax (0161) 907 3501
www.ursglobal.com

DB3