

EAST ELEVATION

WORKS TO ROOFS:

RECOVERED IN SALVAGED BURLINGTON BLUE SLATE IN DIMINISHED COURSES, AS PER HATCHED AREA.

ROOF LEVEL JOINERY AND RAINWATER FITTINGS TO BE DECORATED IN GLOSS BLACK, AS EXISTING.

REMOVE EX. LEAD CAPPINGS FROM PARAPET (SOUTH TRANSEPT & FOYER ROOF TO GABLE VERGE COPINGS), STONE COPINGS TO BE LIFTED OFF, SUPPLY AND FIX NEW LEAD UNDERCLOAK, REPLACE STONE COPINGS AND REPOINT WITH NHL MORTAR. SUPPLY AND FIX SS VERGE GUTTERS AND COVER FLASHINGS, AS PER HATCHED AREA, SEE DRAWING 51/2015/0786/113.

FORM VERGE IN SS SHEET WITH WELTED DRIP FOR ENTRANCE LOBBY ROOF, SEE DRAWING 51/2015/0786/114.

CAREFULLY REMOVE ALL EXISTING CRESTED RIDGE TILES TO AFFECTED ROOFS. CLEAN AND SET ASIDE FOR RE-USE. RE-BED ON NHL LIME MORTAR.

SUPPLY & INSTALL NEW ROOF HATCH, TO CONCEALED ROOF VOID. TO BE BILCO HINGED HATCH WITH GAS STRUT LIFT.

WORKS TO RAINWATER GOODS:

G3:
EX. GUTTER TO BE RETAINED, PREPARE & REDECORATE GUTTER. TO BE DECORATED IN COLOUR BLACK, AS EXISTING.

G4:
NEW 125X75MM DEEP HALF ROUND CAST IRON GUTTER.

G5:
ALLOW AND ADJUST HEIGHT EX. GUTTER TO NEW SS ROOF FINISH ENTRANCE LOBBY.
PREPARE & REDECORATE GUTTER. TO BE DECORATED IN COLOUR BLACK, AS EXISTING.

R4:
SUPPLY AND FIX NEW CAST IRON 270x208x285mm HOPPER HEAD, H1, ONTO EX. RAINWATER PIPE TO EAST SIDE OF SOUTH TRANSEPT. ADJUST LOBBY GUTTER AND UPPER DOWNPIPE TO DISCHARGE ADEQUATELY INTO NEW HOPPER.

R5:
NEW ø75mm CAST IRON RAINWATERPIPE WITH OFFSET & SHOE INTO EX. GULLEY.

R8:
SUPPLY AND FIX NEW CAST IRON 270x208x285mm HOPPER HEAD, H2, ONTO NEW ø75mm CAST IRON RAINWATERPIPE WITH OFFSET & SHOE ONTO STEPPED VALLEY GUTTER.

H3:
RETAIN EXISTING HOPPER & REDECORATE.

SUPPLY AND FIX NEW GALVANISED WIRD BALLOON GRATING ON SVP TO FOYER EAST WALL.

Notes.
- All dimensions to be checked on site.
- No dimensions to be scaled from this drawing unless otherwise stated.

SALVAGED BURLINGTON BLUE SLATES IN DIMINISHED COURSES

RE-POINTING EX. COPINGS AND SS VERGE GUTTERS & COVER FLASHING

Revision No.	Date		Checked By	Revision By
B	11.17	RAMP, STAIRS AND RAILING ADDED TO DRAWING		JdG
A	10.17	ISSUED FOR TENDER	.	JdG

BYROM CLARK ROBERTS
ARCHITECTS • SURVEYORS • ENGINEERS

Unit 2 Millwright 49 Byron Street Leeds LS2 7NA
Tel: 0113 388 8000 Fax: 0113 388 8001

Washbrook House Talbot Road Old Trafford M32 0FP
Tel: 0161 875 0800 Fax: 0161 875 0801

First Floor Swan House Russell Street Chester CH3 5AL
Tel: 01244 348 849 Fax: 01244 320 783

6th Floor, St James House Vicar Lane Sheffield S1 2EX
Tel: 0114 288 6283

©Byrom Clark Roberts Ltd

Client.
THE RECTOR & PCC OF EMMANUEL CHURCH DIDSBURY

Project.
URGENT REPAIRS & RESTORATION WORKS PHASE 1

Drawing Title.
EAST ELEVATION AS PROPOSED

Scale.	Date.	Drawn.	Check.
1:100 @A3	9.17	JdG	IWL

Job No.	Drawing No.	Rev.
51/2015/0786	110	B