



PLANTING SCHEDULE					
Species	Stock type	Spacing	Quantity	Notes	
Alnus incana (Hed) A	Standard 15-18m girth single sided	5m	2		
Betula pubescens (Hed) B	with exposed 1.8m x 1.8m single sided	5m	13		
Thuja x orientalis (European Line) T	Standard 15-18m girth single sided	5m	9		
Quercus robur (Oak) Qr	Standard 15-18m girth single sided	5m	3		
Sorbus aucuparia (Rowan) Sa	Standard 15-18m girth single sided	5m	8		

FORMAL HEDGING					
Species	Stock type	Spacing	Quantity	Notes	
Fagus sylvatica (Beech) Fs	60-80cm bare rooted 1+0 seedling		755	New hedging to run either side of post and wire fence. Maintain at 120cm height.	

SPECIES RICH HEDGEROW AS DETAIL 02				
Species	Stock type	Spacing	Quantity	
STRUCTURAL LAYER				
Corylus avellana Hazel H 10%	40-60 seedling bare rooted 1+1	2 m.	30	
Crataegus monogyna Hawthorn Cr 20%	40-60 seedling bare rooted 1+0	1 m.	50	
Prunus spinosa Blackberry Pr 20%	40-60 seedling bare rooted 1+1	1 m.	30	
Sambucus nigra Elder Sn 15%	40-60 seedling bare rooted 1+1 branched	2 m.	17	

FILLER LAYER					
Rosa canina (Dog Rose) R	40-60 seedling bare rooted 1+0	2m	40	Planted along edges	
Viburnum tinus (Laurustinus) V	40-60 seedling bare rooted 1+0	1m	40		
Eucornia europaea (Eu) E	40-60 seedling bare rooted 1+0	2m	40		

CLIMBERS					
Lonicera periclymenum (Honeysuckle) L		1m	20	Planted alongside fence	

GROUND LAYER					
Stellaria media (Pink Cornflower) S	All P10 green	1m	40		
Geranium sanguineum (Stitchwort) G	1m x 1m	1m	40		
Primula vulgaris (Primrose) P	1m x 1m	1m	40		
Primula vulgaris (Primrose) P	1m x 1m	1m	40		

ORNAMENTAL SHRUB / GROUND COVER PLANTING					
Species	Stock type	Spacing	Quantity		
Lavandula spica (Lavender) L	21cm g	5m	17		
Phlox paniculata (Phlox) P	21cm g	7m	45		
Verbena bonariensis (Verbena) V	21cm g	700mm	15	Planted in groups of 3	
Polystichum acrostichum (Polystichum) P	21cm g	700mm	9	Planted around base of tree groups of 3	

01 Amenity grass, cut 15 times minimum p.a. A19 General All purpose landscaping seed mix 20g/m² area.

Existing grassed areas removed, restored and overseeded generally Amenity grass spec and maintenance.

NOTES:

All trees, shrubs and hedges shall be supplied and planted in accordance with the requirements of British Standard BS5831, Specification for Nursery Stock, Accredited by the Forestry Commission, and shall be supplied in accordance with the requirements of BS5831, Specification for Nursery Stock, Accredited by the Forestry Commission, and shall be supplied in accordance with the requirements of BS5831, Specification for Nursery Stock, Accredited by the Forestry Commission.

01 Amenity grass, cut 15 times minimum p.a. A19 General All purpose landscaping seed mix 20g/m² area.

Existing grassed areas removed, restored and overseeded generally Amenity grass spec and maintenance.

MAINTENANCE:

Establishment of new trees and shrubs shall be undertaken in accordance with the requirements of BS5831, Specification for Nursery Stock, Accredited by the Forestry Commission, and shall be undertaken in accordance with the requirements of BS5831, Specification for Nursery Stock, Accredited by the Forestry Commission.

Establishment of new trees and shrubs shall be undertaken in accordance with the requirements of BS5831, Specification for Nursery Stock, Accredited by the Forestry Commission, and shall be undertaken in accordance with the requirements of BS5831, Specification for Nursery Stock, Accredited by the Forestry Commission.

KEY

Proposed hedging new formal hedging 4ft m total

Swath hedging Fs

Native Hedgerow (65 linear metres)

Ornamental shrub/groundcover planting

Lawn/amenity grass

Wildflower meadow

Existing green space/no action proposed

Existing trees retained as indicated in the Arboricultural Impact Assessment

Existing hedges retained

Trees removed (13)

Proposed trees 35

Biodiversity net gain areas

Native replacement tree species

Wildflower meadow and Native hedgerow, as per guidelines in the BIODIVERSITY NET GAIN study by ERM.

PAVED SURFACES

Existing macadam paths and carriageway retained

Proposed backpaving lifted, cleaned and re-laid

Proposed macadam surfacing to parking area (hedges and access roads) (Civil Engineer's specification)

Proposed mesh fencing and gates to match existing

REVISIONS

A Car park amendments BNG changes with Wildflower Meadow planting and additional trees added 28/08/2025

B Tree numbers increased in line with BNG revised calculations 01/09/25

C Purple Beech hedging omitted 02/09/25

PLANNING ISSUE

Stephen Martlew Landscape Architecture

Unit 2, 8a, Loom Street, Manchester, M4 6AN
TELEPHONE 0161 907 3228

DRAWING TITLE Landscape General Arrangement

DRAWING No 2501P/01

PROJECT BRIDGE COLLEGE

CLIENT TOGETHER TRUST

SCALE 1:250 @ A0

DATE JUNE 2025

DRAWN SM

CHECKED SM