

K10 Gypsum board dry linings/ partitions/ ceilings

To be read with preliminaries/ general conditions.

100 Note

1.0 Information to be read in conjunction with MOJO Architecture drawings and Structural Engineer's information.

101 MOJO standards

- 1.0 To avoid doors from becoming loose in their frames, all door openings must be specified to achieve BS5234 Parts 1 & 2: 1992 - heavy & severe duty.
- 2.0 All openings within dry lining systems to be provided with timber nogging within the formed stud opening to supplement fixing and rigidity.
- 3.0 All partition walls to be founded on the structural slab, where screeds are required timber sole plates are to be utilised.

125A Metal stud partition system

- 1.0 Description: New partitions
- 2.0 Manufacturer: British Gypsum
- 2.1 Product reference: A206003 (EN)
- 3.0 Studs: C' Stud
- 3.1 Type: Gypframe 48 S 50
- 3.2 Centres: 600mm
- 4.0 Head condition: To be restrained back to existing walls or new intermediate structure required - subcontractor to review detail with manufacturer
- 4.1 Deflection allowance: 10mm
- 5.0 Insulation: Not required
- 6.0 Resilient layer: Not required
- 7.0 Linings: Two layers of Gyproc WallBoard 12.5mm (Allow for MR board to WCs and shower rooms)
- 8.0 Finishing: Plaster finish as per clause 680
- 8.1 Primer/ Sealer: One coat of Gyproc Drywall Primer
- 8.2 Accessories: Rigid beads/ stops
- 9.0 Other requirements: Minimum duty rating "Severe"

145A Wall lining system (metal studs)

- 1.0 Description: New linings to box out pipework and structure etc
- 2.0 Manufacturer: British Gypsum
- 3.0 Product reference: As per B216003(C) (EN) but no insulation
- 4.0 Cavity between wall and studs: Nominal 100mm to allow for depth of pipes - refer to drawings
- 5.0 Wall lining height: Allow for 3.4m max.
- 6.1 Studs: I' Stud
- 6.2 Type: Gypframe 60 I 70 'I' Stud
- 6.3 Centres: 600mm
- 7.0 Intermediate bracing: Refer to manufacturers recommendations
- 8.0 Head condition: To be restrained back to existing wall - subcontractor to review detail with manufacturer
- 8.1 Deflection allowance: N/A
- 9.0 Structural performance: Ensure board and studs provide required structural rigidity
- 10.0 Fire performance: Not required
- 11.0 Metal framing: Type recommended by board manufacturer to complete the partition assembly and achieve specified performance.
- 12.0 Insulation: Not required
- 13.0 Moisture vapour resistance (minimum): Allow for MR board to WCs and shower rooms
- 14.0 Resilient layer: Not required
- 15.0 Linings: Two layers of Gyproc WallBoard 12.5mm (Allow for MR board to WCs and shower rooms)
- 16.0 Finishing: Plaster finish as per clause 680
- 16.1 Primer/ Sealer: One coat of Gyproc Drywall Primer
- 16.2 Accessories: Rigid beads/ stops
- 17.0 Other requirements: Minimum duty rating "Severe"

165A Wall lining system (metal framing)

1.0	Description:	New linings to existing walls
2.0	Manufacturer:	British Gypsum
2.1	Product reference:	GypLynr Universal
3.0	Substrate:	Existing masonry walls
4.0	Cavity between wall and back of lining:	Nominal 20mm to allow for tolerance
4.1	Framing centres:	600mm
4.2	Bracket centres (maximum):	800mm
5.0	Insulation:	Not required
6.0	Resilient layer:	Not required
7.0	Linings:	Two layers of Gyproc WallBoard 12.5mm (Allow for MR board to WCs and shower rooms)
8.0	Finishing:	Plaster finish as per clause 680
8.1	Primer/ Sealer:	One coat of Gyproc Drywall Primer
8.2	Accessories:	Rigid beads/ stops
9.0	Other requirements:	Minimum duty rating "Severe"

220A Proprietary suspended ceiling system

1.0	Standard:	To BS EN 13964
2.0	Evidence of compliance:	All ceilings kits to be CE marked. Submit Declaration of Performance
3.0	Manufacturer:	British Gypsum
3.1	Product reference:	GypCeiling MF suspended ceiling
4.0	Linings:	12.5mm Wallboard
4.1	Finishing:	Plaster finish as per clause 680
4.2	Accessories:	
5.0	Suspension system	Gypframe MF7 Primary Support Channel Primary and Gypframe MF5 Ceiling Section Secondary
5.1	Grid centres:	1200mm Primary, 450mm Secondary
5.2	Hangers:	Gypframe MF8 Strap Hanger
5.3	Top fixing:	To be reviewed on site - allow for fixing to existing primary roof structure
6.0	Insulation:	Not Required
7.0	Other requirements:	Refer to manufacturers recommendations

305 Compliance with performance requirements

- 1 Testing/ Assessment: Submit UKAS accredited laboratory reports for the following:
- 2 Materials, components and details: As used in testing/ assessment reports. If discrepancies arise, give notice.

325 Preparation of masonry to receive wall linings

- 1 General: Suitable to receive lining system. Redundant fixtures and services removed. Cutting, chasing and making good completed.
- 2 Holes, gaps, service penetrations, perimeter junctions and around openings: Seal.
- 3 Adhesive fixings: Prepare substrate to achieve effective bonding.
- 3.1 Contaminants: Remove loose material, dirt, grease, oil, paper, etc.
- 3.2 Absorption: Control by dampening, priming or applying bonding agents as necessary.

335 Additional supports

- 1 Framing: Accurately position and securely fix to give full support to:
 - 1.1 Partition heads running parallel with, but offset from main structural supports.
 - 1.2 Fixtures, fittings and service outlets. Mark framing positions clearly and accurately on linings.
 - 1.3 Board edges and lining perimeters, as recommended by board manufacturer to suit type and performance of lining.

Components**400 Gypsum boards generally**

- 1.0 Standard
- 1.1 Gypsum plasterboard to BS EN 520.
- 1.2 Gypsum fibre board to BS EN 15283-2.
- 1.3 Evidence of compliance: All sheets to be CE marked. Submit Declaration of Performance (DoP).

Installation

435 Dry linings generally

- 1.0 General: Use fixing, jointing, sealing and finishing materials, components and installation methods recommended by board manufacturer.
- 2.0 Cutting gypsum boards: Neatly and accurately without damaging core or tearing paper facing.
- 2.1 Cut edges: Minimize and position at internal angles wherever possible. Mask with bound edges of adjacent boards at external corners.
- 3.0 Fixings boards: Securely and firmly to suitably prepared and accurately levelled backgrounds.
- 4.0 Finishing: Neatly to give flush, smooth, flat surfaces free from bowing and abrupt changes of level.

445 Ceilings

- 1.0 Sequence: Fix boards to ceilings before installing dry lined walls and partitions.
- 2.0 Orientation of boards: Fix with bound edges at right angles to supports and with ends staggered in adjacent rows.
- 3.0 Two layer boarding: Stagger joints between layers.

485 Suspended ceiling grids

- 1.0 Setting out: Accurately aligned and level.
- 1.1 Grid members and hangers: Centres to suit specified linings and imposed loads.
- 1.2 Additional grid members: Provide bracing and stiffening at upstands, partition heads, access hatches, etc.
- 2.0 Fixing: Securely at perimeters, grid joints, top and bottom hanger fixings.

560 Joints between boards

- 1.0 Tapered edged gypsum boards
- 1.1 Bound edges: Lightly butted.
- 1.2 Cut/ unbound edges: 3 mm gap.
- 2.0 Square edged plasterboards: 3 mm gap.
- 3.0 Square edged gypsum fibre boards: 5 mm gap.

565 Vertical Joints

- 1.0 Joints: Centre on studs.
- 1.1 Partitions: Stagger joints on opposite sides of studs.
- 1.2 Two layer boarding: Stagger joints between layers.

570 Horizontal joints

- 1.0 Surfaces exposed to view: Horizontal joints not permitted. Seek instructions where height of partition/ lining exceeds maximum available length of board.
- 2.0 Two layer boarding: Stagger joints between layers by at least 600 mm.
- 3.0 Edges of boards: Support using additional framing.
- 3.1 Two layer boarding: Support edges of outer layer.

595 Deflection heads

- 1.0 Fixing boards: Do not fix to head channels.

670 Seamless jointing to gypsum boards

- 1.0 Cut edges of boards: Lightly sand to remove paper burrs.
- 2.0 Filling and taping: Fill joints, gaps and internal angles with jointing compound and cover with continuous lengths of paper tape, fully bedded.
- 3.0 Protection of edges/ corners: Reinforce external angles, stop ends, etc. with specified edge/ angle bead.
- 4.0 Finishing: Apply jointing compound. Feather out each application beyond previous application to give a flush, smooth, seamless
- 5.0 Nail/ screw depressions: Fill with jointing compound to give a flush surface.
- 6.0 Minor imperfections: Remove by light sanding.

680 Skim coat plaster finish

- 1.0 Plaster type As recommended by board manufacturer.
- 1.1 Thickness: 2-3 mm.
- 2.0 Joints: Fill and tape except where coincident with metal beads.
- 3.0 Finish: Tight, matt, smooth surface with no hollows, abrupt changes of level or trowel marks.

692 Rigid beads/stops

- 1.0 Internal: To BS EN 13658-1.
- 2.0 External: To BS EN 13658-2.

695 Installing beads/ Stops

- 1.0 Cutting: Neatly using mitres at return angles.
- 2.0 Fixing: Securely using longest possible lengths, plumb, square and true to line and level, ensuring full contact of wings with substrate.
- 3.0 Finishing: After joint compounds/ plasters have been applied, remove surplus material while still wet from surfaces of beads exposed to view.

725 Repairs to existing gypsum board

- 1.0 Filling small areas with broken cores: Cut away paper facing, remove loose core material and fill with jointing compound.
- 1.1 Finish: Flush, smooth surface suitable for redecoration.
- 2.0 Large patch repairs: Cut out damaged area and form neat hole with rectangular sides. Replace with matching gypsum board.
- 2.1 Fixing: Use methods to suit type of dry lining, ensuring full support to all edges of existing and new gypsum board.
- 2.2 Finishing: Fill joints, tape and apply jointing compound to give a flush, smooth surface suitable for redecoration.