

1 REFER TO DWG NO. 2500/10 FOR SLAB NOTES.

2 REFER TO DWG NO. 2500/08 FOR STEELWORK NOTES.



1000mm LONG H10 ANTI-CRACK CORNER
BARS TIED TO MESH IN SLAB TYPICAL TO
ALL SLAB CORNER POSITIONS

TOP OF SLAB SET TO SUIT FINISHES
REFER TO ARCHITECTS DETAILS FOR
FINISHES/TOLERANCES/SEALANT TYPES

WHERE REQUIRED: ENDS OF BLOCKWORK WALLS TO
BE RESTRAINED TO RETAINING WALL USING MULTI-
STARTER WALL TIES FIXED IN ACCORDANCE WITH
MANUFACTURERS DETAILS

WHERE REQUIRED: HEAD OF BLOCKWORK WALLS TO
BE RESTRAINED TO U/S OF METALDECK FLOORING
USING REINCLER ANGLES, 1NO. TO EACH SIDE OF WALL
10mm SOFT JOINT BETWEEN HEAD OF BLOCKWORK
WALLS & U/S OF METALDECK FLOORING

A INDICATES NAYLOR R6 CONCRETE LINTEL OR
SIMILAR APPROVED (145X100mm WIDE)

E	20.04.23	ADDED ADDITIONAL STAIRWELL REVISED CORE AREA TO SUIT ARCH/LIFT SUPPLIERS LATEST DETAILS REVISED POSITION OF GL4 & RETAINING WALL REVISED POSITION OF UC TO REAR OF LIFT	S.P.M
D	22.02.23	UPDATED DIMENSIONS TO GL4 ADDED RHS POST ADJACENT TO LIFT	S.P.M
C	01.02.23	REVISED COLUMN SIZES TO GLC5,C6,G1&F1a ADDED COLUMN TO REAR OF LIFT REVISED POSITION OF GL1c ADDED CONCRETE PIERS	S.P.M
B	20.01.23	REVISED SETTING OUT TO CONCRETE PIERS	S.P.M
A	13.01.23	CONSTRUCTION ISSUE	S.P.M
P5	23.12.22	ADDED RETAINING WALL PIER SETTING OUT REVISED SET OUT BETWEEN GL2-3	S.P.M
P4	14.12.22	REVISED CAR PARKING ARRANGEMENT ADJACENT TO COLUMN ON GLD7	S.P.M
P3	13.12.22	DRAWING UPDATED	S.P.M
P2	08.12.22	DRAWING UPDATED	S.P.M
P1	18.10.22	PRELIMINARY ISSUE	S.P.M
rev	date	revisions	initials

client

CHALLENGER GROUP

project

GREENWOOD ROAD
WYTHENSHAW

drawing

COLUMN LAYOUT & DETAILS

PWA Philip Wright Associates
Consulting Structural Engineer
21 Union Street, Ramsbottom,
Bury, BL0 9AN
Telephone: 07939 547865
Email: info@philipwrightassociates.co.uk

drawn	S.P.M.	date	19.10.22
scale	1:100	checked	
contract no.	2500	drawing no.	07 E