



1 Bed 1 Planting Plan
Scale: 1:100

Bed 1 - Sun/Partial Shade Mix - Total Area = 116 sqm						
Species Symbol	Species Latin	Specification	Pot size (Ltr)	Density	Percentage	Total Quantity
Al	<i>Alchemilla mollis</i>	Full Pot	3L	7	5	41
An	<i>Anemone x hybrida</i> 'Honorine Jobert'	Full Pot	3L	5	7	41
BmBb	<i>Brunnera macrophylla</i> 'Betty Bowring'	Full Pot	3L	9	5	52
Cc	<i>Carex comans</i> 'Frosted Curly'	Full Pot	3L	9	10	105
Cm	<i>Carex morrowii</i> 'Ice Dance'	Full Pot	3L	5	10	58
Dc	<i>Deschampsia cespitosa</i> 'Goldschleier'	Full Pot	3L	5	10	58
Eb	<i>Echinops bannaticus</i> 'Taplow Blue'	Full Pot	3L	5	5	29
Gc	<i>Geranium cinerum</i> 'Ballerina'	Full Pot	3L	7	7	57
Gw	<i>Geranium phaeum</i> 'Walküre'	Full Pot	3L	9	6	63
Bp	<i>Bergenia purpurascens</i> 'Irish Crimson'	Full Pot	3L	5	10	58
Ep	<i>Eutrochium purpureum</i>	Full Pot	3L	5	5	29
Vp	<i>Verbasicum phoeniceum</i> 'Violetta'	Full Pot	3L	5	10	58
Vm	<i>Vinca minor f. alba</i> 'Gertrude Jekyll'	Full Pot	3L	9	10	105
Total:					100	754

Bed 1 - Feature Plants			
Species Symbol	Species Latin	Specification	Pot Size (Ltr)
Vt	<i>Viburnum opulus</i> 'Compactum'	Full Pot	10L
Em	<i>Euphorbia x martini</i>	Full Pot	5L
Sg	<i>Stipa gigantea</i> 'Pixie'	Full Pot	5L
Ph	<i>Penstemon heterophyllus</i> 'Electric Blue'	Full Pot	5L
SI	<i>Salvia leucantha</i> 'Purple Velvet'	Full Pot	5L
Sr	<i>Salvia rosmarinus</i> 'Miss Jessopp's Upright'	Full Pot	5L

Tree Planting					
Botanical Name	Common Name	Root Zone	Height cm	Girth / Dia. cm	Specification
<i>Alnus Cordata</i>	Italian Alder	RB	400-450	18-20	EHS, 3x Clear stem min 200cm
<i>Amelanchier lamarckii</i>	Juneberry	RB	400-450	18-20	3x Multi-stem, Bushy 3 stems min
<i>Betula Nigra</i>	River Birch	RB	400-450	18-20	EHS, 3x Clear stem min 200cm
<i>Betula Utilis Jacquemontii</i>	Himalayan birch	RB	400-450	18-20	3x Multi-stem, Bushy 3 stems min
<i>Cornus Kousa</i>	Dogwood	RB	400-450	18-20	3x Multi-stem, Bushy 3 stems min
<i>Illex Aquifolium</i>	Holly	RB	400-450	18-20	EHS, 3x Clear stem min 200cm

Small planters - Full Shade/ Partial Shade			
Code	Species - Latin	Specification	Pot size (Ltr)
Ct	<i>Carex testacea</i>	Full Pot	3L
Al	<i>Anemanthella lessoniiana</i>	Full Pot	3L
Ca	<i>Calamagrostis arundinacea</i>	Full Pot	3L

PLANTING NOTES

- Plant handling at the nursery, and during transit up to delivery, shall be in accordance with 'Plant Handling', published by the Committee for Plant Supply and Establishment (CPSE). The contractor shall comply with clauses 3 & 4 of the stated document (obtained from the Horticulture Trades Association) which refers to the receipt, unloading and temporary storage of plants.
- Plants shall be first class examples of their species or variety, free from all pests and diseases with good fibrous root systems and materially undamaged. (Refer to relevant sections of BS3936 Parts 1-10 'Specification of Nursery Stock')
- All planting is to be in general compliance with BS4428: 1989 'Code of Practice for general landscape operations (excluding hard surfaces)'.
i) All semi-mature trees are to be underground guyed using approved anchor fixing system
- All trees are to be staked and secured as follows:
i) All semi-mature trees are to be underground guyed using approved anchor fixing system
- The contractor must ascertain for himself the exact location of any underground services and maintenance points.
- Species to be installed in groups of 3-5 unless indicated otherwise. Planting to be a random pattern throughout all planting area.
- Water as necessary to ensure the establishment and continued thriving of planted and grassed matter.
- Carry out all work when soil and weather conditions are suitable:
i) Do not plant during periods of frost or strong winds. Plant only during the following periods
- Bare root deciduous trees and shrubs: Late October to late March
- Container grown plants: At any time if ground water and weather conditions are favourable.
Ensure that adequate watering and weed control is available.
- Bulbs- autumn.
- Wildflower- spring.
- All planting areas are to be mulched to a consolidated depth of 75mm using approved Grade A Amenity Bark.

THIS DRAWING IS COPYRIGHT PROTECTED AND MAY NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN AUTHORITY FROM THE OWNER.

- NOTES:
- Do not scale from this drawing.
 - Always work to noted dimensions.
 - All dimensions are in millimetres unless otherwise stated.
 - All setting out, levels and dimensions to be agreed on site.
 - The dimensions of all materials must be checked on site before being laid out.
 - This drawing must be read with the relevant specification clauses and detail drawings.
 - Order of construction and setting out to be agreed on site.



Please note, planters and trees, etc to be undertaken by Embassy.

- Proposed Feature Plants:
- Vt Viburnum opulus 'Compactum'
 - Em Euphorbia x martini
 - Sg Stipa gigantea 'Pixie'
 - SI Salvia leucantha 'Purple Velvet'
 - Ph Penstemon heterophyllus 'Electric Blue'
 - Sr Salvia rosmarinus 'Miss Jessopp's Upright'

SL-P09	24-09-25	Planting Plan and Schedule Update	MC	KR
SL-P08	08-05-25	Northern Edge / Paving Spec Update	RMC	KR
SL-P07	28-04-25	GA Update	KR	
SL-P06	15-07-24	Planter planting list added	EKH	KR
SL-P05	04-08-23	Stage 4 Draft Issue	EKH	KR
SL-P04	23-02-23	Stage 3	EKH	KR
SL-P03	13-02-23	Stage 3	EKH	KR
SL-P02	22-03-21	Updated arrangement as part of water safety strategy	CS	GB
SL-P01	08-02-21	First Issue	CS	GB

Planit I.E. Limited
E: info@planit-ie.com W: planit-ie.com
MANCHESTER
2 Back Grafton St., Altrincham, WA14 1DY
T: 0161 928 9281
LONDON
Unit 6 Waterside, 44-48 Wharf Road, London, N1 7UX
T: 0207 253 5678
LIVERPOOL
Tempest 5.3, 12 Tithesbarn Street, Liverpool, L2 2DT
T: 0151 363 1230

Client Embassy

Project Embassy Village

Drp Title Planting Plan 1 of 2

Created on 08/02/2021 Created by CS Approved by GB

Scale 1:100 Size A1 Workstage Stage 5

Drp No. 2596-PLA-XX-XX-DR-L-2001 Suitability S1 Revision P09

Location Plan:

