




This document and its contents are the property of the Purchaser/Employer and Crookes Walker Consulting. They may not be copied or reproduced in any way, in part or whole, without prior written approval of both parties. Violations will result in legal action.
This drawing shall be read in conjunction with the CWC Mechanical and / or Electrical Specification(s).
DO NOT SCALE FROM THIS DRAWING

DESIGNERS RISK ASSESSMENT
REFER TO DESIGNERS RISK ASSESSMENT SCHEDULE

DRAWING BACKGROUND(S):
NOTES:

- Electrical Supply Details**
The provision for the tenant's electrical supply is 400V 3-Phase, 90kVA and shall terminate into a utility cut out and meter module unit located in the ground floor LV switch room.
The utility cut out and meter modules shall provide a connection for tenants to enable their preferred utility service supplier to provide an energy meter.
- Data / Comms**
Containment provisions are provided within the ground floor service rooms for incoming supplies. Incoming comms / data services, telephone lines, ICT structured cabling will be provided direct by the tenant.
- Broadband**
Containment provisions are provided within the ground floor service rooms for incoming supplies. No broadband apparatus or cabling is installed and the tenant is advised to make direct enquiries with the telecom organisations to arrange a suitable broadband service.
- Fire Alarm**
The tenant shall provide a full fire alarm system within their demise. It shall be in compliance with BS 5839-1:2017 and have an interface to signal a fire / fault alarm to the landlord's fire alarm system.
This interface shall be demonstrated by the Tenants Fire Alarm Specialist with the Landlords Fire Alarm Specialist Installer present.
- All plant and equipment shall be installed to manufacturers recommendations, allowing full access for testing, commissioning, maintenance, removal and replacement.
- The precise location of all equipment shall be co-ordinated with other map services and architect details.

LEGEND	
SYMBOL	DESCRIPTION
	1500mm LED surface mounted luminaire c/w emergency 3hr back-up
	1500mm LED surface mounted luminaire
	ETCH WEB Pendant Brass/Steel
	Emergency LED luminaire c/w 3hr Battery Back-up
	GU10 Uplighter
	Smoke/Heat Detector c/w Sounder
	Sounder/Beacon c/w Strobe
	Fire Alarm Interface Unit for Landlords Fire Alarm System
	Break Glass Unit
	Fire Alarm Panel

T1	24.04.18	TENDER ISSUE	RJ	SW
P2	29.03.18	PRELIMINARY ISSUE	RJ	SW
P1	09.03.18	PRELIMINARY ISSUE	RJ	SW
Rev	Date	Description	Eng	Chk



Alberton House, 30 St Mary's Parsonage
Manchester M3 2WJ
Tel: 0161 834 9999
The Plaza, Old Hall Street,
Liverpool L3 5QJ
Tel: 0151 600 5409
E-mail: admin@cwcon.co.uk
Website: www.cwcon.co.uk

Client
RIBEYE STEAKHOUSE

Project
FIRST STREET BUILDING 8 UNIT 1A

Drawing Title
GROUND FLOOR FIRE ALARM AND EMERGENCY LIGHTING

Status TENDER	
Project No. 1663	Drawn RJ
Scale / Paper Size 1:100 @ A1	
Drawing No. 1663-GF-6701	Rev T1

