Studio Egret West

0424 Mayfield Threshold
Planting Schedule
Status: Stage 5

Doc No. 0424-SEW-ZZ-ZZ-SH-L-001000

Revision Record

Revision	Date	Reason for Issue	Description of updates	Issued by
00	30.08.24	DRAFT Stage 4	DRAFT Stage 4 Issue	TH
1	13.11.24	Stage 4	Stage 4 issue	MA
2	29.07.25	Stage 5	Stage 5 issue	SH

Studio Egret West

0424 Mayfield Threshold
Planting Schedule
Status: Stage 5

Doc No. 0424-SEW-ZZ-ZZ-SH-L-001000

Rain Gardens (S01)
Refer to plan 0424-SEW-ZZ-ZZ-DR-L-005200

Structural Species

Abb	Name	Height	Specification	Quantity
CdAP	*Choisya × dewitteana 'Aztec Pearl'*	50cm+	Bushy to base; 20L pot	2
SrvDG	*Sarcococca ruscifolia var. chinensis*	30-40cm+	Full to base/bushy; 20L pot	4
HaA	*Hydrangea arborescens 'Annabelle'*	80cm+	Full to base/bushy; 20L pot	2
MS	*Matteuccia struthiopteris*	50cm+	Full to base	7

Final setting out of plants to be agreed with Landscape Architect prior to planting

Mix 01a - Sunnier Beds

Abb	Name	Root	Container	Density /m2	Distribution	Quantity	Note
Ac	*Astrantia 'Claret'*	C	9cm	9	15%	33	
AcG	*Achillia 'Cloth of Gold'*	C	9cm	9	5%	10	
Al	*Anemanthele lessoniana*	C	9cm	9	10%	20	
AmRV	*Achillia millefolium 'Red Velvet'*	C	9cm	9	15%	33	
Ch	*Crocosmia 'Hellfire'*	C	9cm	9	10%	20	
Cv	*Chrysogonum virginianum*	C	9cm	9	5%	10	
Hxh	*Helleborus x hybridus*	C	9cm	9	10%	20	
IBA	*Iris'Benton Apollo'*	C	9cm	9	10%	20	
Ln	*Luzula nivea*	C	9cm	9	10%	20	
TGR	*Tellima Grandiflora Rubra*	C	9cm	9	10%	20	

Mix 01b - Shadier beds

Abb	Name	Root	Container	Density /m2	Distribution	Quantity	Note
Ac	*Astrantia 'Claret'*	C	9cm	9	20%	73	
Al	*Anemanthele lessoniana*	C	9cm	9	10%	36	
Ch	*Crocosmia 'Hellfire'*	C	9cm	9	20%	73	
Cv	*Chrysogonum virginianum*	C	9cm	9	10%	36	
Hxh	*Helleborus x hybridus*	C	9cm	9	10%	36	
Ln	*Luzula nivea*	C	9cm	9	10%	36	
TGR	*Tellima Grandiflora Rubra*	C	9cm	9	20%	73	

Plant randomly in single-species groups of 3-5 within the planting bed.
Final setting out of plants to be agreed with Landscape Architect prior to planting

Bulbs

Abb	Name	Grade	Density /m2	Distribution	Quantity
Ge	*Galanthus elwesii*	5/+	150	33%	3169
NPE	*Narcissus 'Pheasant's Eye'*	12/14+	60	33%	1268
Ns	*Nectaroscordum siculum*	7/+	80	33%	1690

Final setting out of plants to be agreed with Landscape Architect prior to planting

Studio Egret West

0424 Mayfield Threshold
Planting Schedule
Status: Stage 5

Doc No. 0424-SEW-ZZ-ZZ-SH-L-001000

Pot Planting (S02)
Refer to plan 0424-SEW-ZZ-ZZ-DR-L-005200

Structural Species

Abb	Name	Height	Specification	Quantity
Au	*Arbutus Unedo*	250cm	Umbrella; min 3 stems; 16-18 girth; 70/40 rootball; 3x transplanted	5
CcGF	*Cotinus coggygria 'Green Fountain'*	200cm+	Branched to base, 70/50 rootball, 2-3x transplanted	3
CG	*Cotinus 'grace'*	200cm+	Branched to base; 70/50 rootball, 2-3x transplanted	3
Fp	*Fatsia polycarpa*	100-150cm	Leader; Bushy	5
Hv	*Hamamelis virginiana*	150-175cm	Bushy to base; min 3 stems branching stems; 3-4 min of 16-18 stem girth. Rootball 60x40 rootball.	6
Ckc	*Cornus kousa 'chinensis'*	200-250	Multi stem; min 3 stems, 3-4 transplant, 70/40/50 rootball	3

The above species will be planted in pots on an individual basis. Where indicated to be planted within a pot, they must be centrally located.
Final setting out to be agreed with Landscape Architect prior to planting.

Herbaceous Perennials

Abb	Name	Root	Container	Quantity
Al	*Anemanthele lessiona*	C	9cm	50
Ek	*Erigeron karvinskianus*	C	9cm	39
ER	*Epimedium 'Rik'*	C	9cm	56
GpA	*Geranium phaeum 'Album'*	C	9cm	22
Hm	*Hakonechloa macra (AGM)*	C	9cm	107
Pr	*Phlomis russeliana*	C	9cm	57
St	*Stipa tenuissima*	C	9cm	39

The above species of perennials will be planted in combinations across the pots.
Final setting out to be agreed with Landscape Architect prior to planting.

Bulbs

Abb	Name	Grade	Density /m2	Distribution	Quantity
Nc	*Narcissus cordubensis*	6/+	60	50%	416
Nm	*Narcissus 'Minnow'*	12/14+	75	50%	512

Final setting out to be agreed with Landscape Architect prior to planting.

Studio Egret West

0424 Mayfield Threshold
Planting Schedule
Status: Stage 5

Doc No. 0424-SEW-ZZ-ZZ-SH-L-001000

Southern Baring Street (S03)
Refer to plan 0424-SEW-ZZ-ZZ-DR-L-005200

Structural Species

Abb	Name	Height	Specification	Quantity
CdAP	*Choisya × dewitteana 'Aztec Pearl'*	50cm+	Bushy to base; 20L pot	4
SrvDG	*Sarcococca ruscifolia var. chinensis*	30-40cm+	Full to base/bushy; 20L pot	3

Mix 03a

Abb	Name	Root	Container	Density /m2	Distribution	Quantity	Note
ACG	*Achillia 'Cloth of Gold'*	C	9cm	9	20%	66	
AI	*Anemanthele lessoniana*	C	9cm	9	10%	33	Plant in linear drifts
Am	*Alchemilla mollis*	C	9cm	9	20%	66	
APC	*Artemisia 'Powis Castle'*	C	9cm	9	10%	33	
EpWS	*Echinacea purpurea 'White Swan'*	C	9cm	9	20%	66	
Hxh	*Helleborus x hybridus*	C	9cm	9	10%	33	
PaH	*Pennisetum alopecuroides 'Hameln'*	C	9cm	9	10%	33	

Plant randomly in single-species groups of 5-7 within the planting bed.
Final setting out to be agreed with Landscape Architect prior to planting.

Bulbs

Abb	Name	Grade	Density /m2	Distribution	Quantity
NPE	*Narcissus 'Pheasant's Eye'*	12/14+	60	50%	1092
Ct	*Crocus tommasinianus*	5/+	120	50%	2184

The above bulbs are examples of species that will be planted across all pots.