

1 Landscape Hardworks
Scale: 1:250

Existing paving/ steps/ corduroy hazard paving and planters to remain
Protect during works on site



PLANE OFF TO SUIT LEVELS & NEW THRESHOLDS OF BLOCK A - ALONG DUTTON STREET
SURVEY TO BE CARRIED OUT ON SITE - TO ASSESS EXISTING KERBS / DROP KERBS

NOTES
31-01-25
PAVING AROUND COLLEGE ENTRANCE
Existing paving removed to top of existing small steps
Kellen used in place

No dimensions are to be scaled from this drawing. All dimensions are to be checked on site.
Area measurements for indicative purposes only.

This drawing is the property of Wright Landscapes Limited. No part of the drawing may be reproduced in any manner without permission from Wright Landscapes Limited.

All Wright Landscapes drawings to read in conjuction with architectual / engineers plans & details.

BLOCK PAVING
Product: ARTRO Block Paving
Size: 220mm x 55mm X 80mm
Colour: Heather/Bracken 50:50 mix
Laying pattern: mixed random herringbone
Supplier: Tobermore

BLOCK PAVING, KELLEN
Product: Breccia Magma
Size: 200mm x 100mm x 80mm
Colour: Magma
Laying bond: staggered
Supplier: Hardscape

BLOCK PAVING, KELLEN
Product: Kellen, Tagenta E (type TBC)
Size: 400mm x 400mm x 60mm (TBC)
Colour: Silver Grey
Laying bond: Staggered, angle to match existing
TO MATCH EXISTING BY COLLEGE ENTRANCE

NATURAL STONE PAVING
To residential areas/Building frontages
Product: Mira CS
Size: *600mm x Random lengths x 63mm*
Supplier: Tectonix

MACADAM
Wearing Course only

EXISTING MACADAM AND PEDESTRIAN KERBS
Retain/ protect existing

STONE STEPS
Step unit with contrasting nosing/inlay strips
Product: Granite Trino
Finish: Fine picked
Size: Tread and riser varies, refer to Hardwork Plans
Including underlit handrails by Others
Supplier:n Tectonix

CONCRETE STEPS
Product: Conservation Step Unit
Finish: Textured
Size: 255mm x 205mm x 915mm
Supplier: Marshalls

HAZARD CODUROY WARNING PAVING
Product: Trino Granite
400mm x 400mm x 50mm
To top and bottom of steps
Supplier:Tectonix

CONTRAST INFILL PAVING STRIP
Contrasting colour paving infill strip

FOR PAVING BUILD UPS SPECIFICATION
SEE DWG NO BRW-REN-ZZ-XX-DR-C-03400-C01

Macadam Wearing course/ new kerbs
Refer to
000382-SLR-XXX-XXX-DR-CH-100
S278 GENERAL ARRANGEMENT P07
000382-SLR-XXX-XXX-DR-CH-200
S278 SITE CLEARANCE P03
000382-SLR-XXX-XXX-DR-CH-1100
S278 FOOTWAY * KERBS P04

Revision	Date	Description	Drawn	Approved
S5-P08	17-06-25	Changes to notes	SB	NW
S5-P07	02-06-25	Layout changes in line with GA	SB	NW
S5-P06	21-02-25	Conservation Step to Dutton St added	NW	CB
S5-P05	18-02-25	Kellen Paving Removed	SB	NW
S5-P04	28-11-24	Changes to material sizes and specification	SB	NW
S5-P03	23-10-24	For Construction	SB	NW
S4-P02	07-06-24	For Comment	PH	NW
S4-P01	07-02-24	First Issue	NW	CB

WRIGHT LANDSCAPES LIMITED

E: info@wrightlandscapes.co.uk
W: www.wrightlandscapes.co.uk
T: 01244 541959

HEAD OFFICE
Pickmere Lane, Pickmere, Knutsford,
WA16 0JL

CLIENT DOMIS CONSTRUCTION

PROJECT WATERHOUSE GARDENS

DRAWING TITLE Hardworks

DATE	SCALE
06/02/2024	1:250
DRAWN	**SIZE**
NW	A1
APPROVED	**WORKSTAGE**
CB	Stage 5

DRAWING NUMBER 1174-WRI-XX-XX-DR-L-0029
SUITABILITY S5
REVISION P08

© Wright Landscapes Limited