


## SOFT LANDSCAPE

- Existing tree/vegetation to be removed. Subject to Tree Survey to confirm
- Existing Trees retained
- EH1 – Existing Formal Hedge retained
- EH2 – Existing Informal Hedge / dense vegetation retained
- EG1 – Existing Grass retained
- G2 – Proposed Grass. As NBS Q30 / 400
- Proposed tree planting in soft landscape. Please refer to drawing FS0998-IBI-A-14-XX-D-L-7015 and NBS Q31
- PS1 – Proposed shrub planting. Please refer to drawing FS0998-IBI-A-14-XX-D-L-7015 and NBS Q31
- PH1 – Proposed Hedge Planting. Please refer to drawing FS0998-IBI-A-14-XX-D-L-7015 and NBS Q31
- BNA – Biodiversity Nature Area. WFG2 Flowering Meadow. WFG15 Countrylife, Schools & Colleges. As NBS Q30 / 312 and Q30 / 312A
- MUGA – MUGA - carpet to be replaced on existing sub-base. As NBS Q26 / 350

## Tree and Shrub Plant Schedule

### Trees

| Number | Species | Girth | Height | Specification |
|---|---|---|---|---|
| 3 | Acer campestre | 12-14cm | 3.5-4.0m | Heavy Standard :Clear Stem min. 200 :3x :RB |
| 2 | Acer campestre 'Streetwise' | 12-14cm | 3.5-4.0m | Heavy Standard :Clear Stem min. 200 :3x :RB |
| 5 | Betula utilis jacquemontii | 16-18cm | 4.0-4.5m | Extra Heavy Standard :Clear Stem min. 200 :3x :RB |
| 1 | Carpinus betulus | 12-14cm | 3.5-4.0m | Heavy Standard :Clear Stem min. 200 :3x :RB |
| 3 | Carpinus betulus 'Frans Fontaine' | 16-18cm | 4.0-4.5m | Extra Heavy Standard :Clear Stem min. 200 :3x :RB |
| 4 | Prunus 'Accolade' | 16-18cm | 4.0-4.5m | Extra Heavy Standard :Clear Stem min. 200 :3x :RB |
| 1 | Prunus serrula tibetica | 16-18cm | 4.0-4.5m | Extra Heavy Standard :Clear Stem min. 200 :3x :RB |
| 5 | Pyrus calleryana | 16-18cm | 4.0-4.5m | Extra Heavy Standard :Clear Stem min. 200 :3x :RB |
| 3 | Sorbus aria 'Lutescens' | 12-14cm | 3.5-4.0m | Heavy Standard :Clear Stem min. 200 :3x :RB |
| 1 | Sorbus aucuparia | 16-18cm | 4.0-4.5m | Extra Heavy Standard :Clear Stem min. 200 :3x :RB |
| 5 | Sorbus aucuparia 'Sheerwater Seedling' | 16-18cm | 4.0-4.5m | Extra Heavy Standard :Clear Stem min. 200 :3x :RB |
| 2 | Tilia cordata | 16-18cm | 4.0-4.5m | Extra Heavy Standard :Clear Stem min. 200 :3x :RB |

### Shrubs

| Number | Pot Size | Species | Specification | Density |
|---|---|---|---|---|
| 38 | 5L | Ceanothus 'Blue Mound' | Bushy :3/5 brks :C | 4/m² |
| 93 | 5L | Euonymus fortunei 'Silver Queen' | Bushy :3/4 brks :C | 4/m² |
| 129 | 5L | Hebe 'White Gem' | Bushy :3/5 brks :RB | 4/m² |
| 98 | 3L | Pachysandra terminalis | Bushy :3/5 brks :C | 5/m² |
| 165 | 3L | Pittosporum tenuifolium | Bushy :5 brks :C | 4/m² |
| 43 | 5L | Prunus laurocerasus 'Otto Luyken' | Bushy :5 brks :C | 4/m² |
| 66 | 3L | Skimmia japonica 'Rubella' | Bushy :3 brks :C | 5/m² |
| 41 | 3L | Viburnum davidii | Bushy :3 brks :C | 4/m² |

### Herbaceous

| Number | Pot Size | Species | Specification | Density |
|---|---|---|---|---|
| 48 | | Achillea millefolium 'Fire King' | Full Pot :C | 4/m² |
| 72 | 3L | Heuchera 'Plum Pudding' | Full Pot :C | 5/m² |
| 38 | 5L | Salvia officinalis 'Icterina' | Full Pot :C | 4/m² |

### Grasses

| Number | Species | Pot Size | Specification | Density |
|---|---|---|---|---|
| 83 | Stipa tenuissima | 5L | Full Pot | 4/m² |

### Hedge 1

Trees

| Number | Species | Girth | Height | Specification |
|---|---|---|---|---|
| 248 | Carpinus betulus | | 80-100cm | 1+1 :3/5 brks :BR |

Biodiversity Nature Area
Wildflower Mixes

Product Name: WFG15 (Countrylife, Schools & Colleges)
Mixture Breakdown
2.0% Cornflower (Centaurea cyanus)
3.0% Oxeye Daisy (Leucanthemum vulgare)
2.0% Corn Poppy (Papaver rhoeas)
2.0% Corncockle (Agrostemma githago)
1.0% Yellow Rattle (Rhinanthus minor)
0.2% Shepherds Purse (Capsella bursa-pastoris)
2.0% Sainfoin (Onobrychis vicifolia)
1.6% Leo (Birdsfoot Trefoil) (Lotus cornculatus)
0.5% Common Vetch (Vicia sativa)
1.0% Lance-Leaved Coreopsis (Coreopsis lanceolata)
1.0% Cosmos "Sensation Mix" (Cosmos "sensation mix")
1.0% Calendula Art Shades (Calendula art shades)
1.0% Purple Coneflower (Echinacea)
1.0% Oxeye Sunflower (Heliopsis helianthoides)
0.7% Smooth Blue Aster (Symphyotrichum laeve)
40.0% Sheeps Fescue (Fescue ovina)
20.0% Strong Creeping Red Fescue (Festuca rubra rubra)
5.0% Crested Dogstail (Cynosurus cristatus)
5.0% Meadow Foxtail (Alopecurus pratensis)
5.0% Tall Oat-grass (Arrhenatherum elatius)
5.0% Chewings Fescue (Festuca rubra commutata)

Product Name: WFG2 (Flowering Meadow)
Mixture Breakdown
1.0% Purple Coneflower (Echinacea)
1.5% Cornflower (Centaurea cyanus)
2.0% Corncockle (Agrostemma githago)
0.5% Oxeye Daisy (Leucanthemum Vulgare)
0.3% Foxglove (Digitalis purpurea)
0.2% Smooth Blue Aster (Symphyotrichum laeve)
0.5% Rudbeckia (Rudbeckia hirta)
2.5% Oxeye Sunflower (Heliopsis helianthoides)
0.5% Ribwort Plantain (Plantago lanceolata)
3.5% Corn Poppy (Papaver rhoeas)
2.0% Corn Chamomile (Anthemis arvensis)
1.0% Lance-leaved Coreopsis (Coreopsis lanceolata)
1.0% Leo (Birdsfoot Trefoil) (Lotus corniculatus)
1.0% Phacelia (Phacelia tanacetifolia)
0.4% Hyssop (Hyssopus officinalis)
0.5% Yarrow (Achilles millefolium)
0.2% Calendula Art Shades (Calendula art shades)
0.5% Corn Marigold (Chrysanthemum segetum)
0.5% Evening Primrose (Oenothera biennis)
0.2% Red Campion (Silene dioica)
0.2% Common Knapweed (Centaurea nigra)
30.0% Sheeps Fescue (Festuca Ovina)
24.0% Slender Creeping Red Fescue (Festuca rubra litoralis)
9.5% Crested Dogstail (Cynosurus cristatus)
4.5% Tall Oat-grass (Arrhenatherum elatius)
5.0% Chewings Fescue (Festuca rubra commutata)
1.0% Browntop Bent (Agrostis capillaris)
1.0% Tufted Hair Grass (Deschampsia cespitosa)
5.0% Timothy (Small eared) (Phleum bertolonii)

Notes:
- This drawing is copyright.
- Do not scale dimensions from this drawing.
- This drawing is to be read in conjunction with all other relevant drawings
- All discrepancies on this drawing are to be reported to the architect.
- Do not modify any element of this drawing.
- Use drawing only for purpose(s) issued.

North Sign / Key Plan

The following external model files are included within this drawing:

0mm — 100mm

| Rev | Date | Revision Notes | Dn | Rv |
|---|---|---|---|---|
| P01 | 26/05/23 | First Issue | DW | DW |

Client / Contractor

**Intelligence Buildings Infrastructure**
www.ibigroup.com

Project
DIXON ACADEMY

Drawing Title
PLANTING PLAN

| Job Number | Drawing Originated Date | PAS 1192 Status Code |
|---|---|---|
| 142037 | 22/05/2023 | S5 |

| Scale@A1 | Purpose |
|---|---|
| 1:500 | CLIENT REVIEW |

| Drawing Number | Revision |
|---|---|
| FS0998-IBI-A-14-XX-D-L-7015 | P01 |

(S5) A Status - (NO COMMENTS)