

The Alan Johnston Partnership		Page 1
1 Dale Street Liverpool L2 2ET	220-096 - Project Red Electrical Infrastructure Existing Brownfield Runoff	
Date 06/05/2022 08:50	Designed by JRS	
File Existing Brownfield Runoff.MDX	Checked by PB	
Micro Drainage	Network 2019.1	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	2	PIMP (%)	100
M5-60 (mm)	18.000	Add Flow / Climate Change (%)	0
Ratio R	0.358	Minimum Backdrop Height (m)	0.200
Maximum Rainfall (mm/hr)	50	Maximum Backdrop Height (m)	1.500
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	1.00
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Time Area Diagram for Storm

Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.055	4-8	0.024

Total Area Contributing (ha) = 0.079

Total Pipe Volume (m³) = 0.530

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.000	10.000	0.101	99.0	0.079	5.00	0.0	0.600	o	150	Pipe/Conduit	
S1.001	10.000	0.101	99.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
S1.002	10.000	0.101	99.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.000	50.00	5.17	38.650	0.079	0.0	0.0	0.0	1.01	17.8	10.7
S1.001	50.00	5.33	38.549	0.079	0.0	0.0	0.0	1.01	17.8	10.7
S1.002	50.00	5.50	38.448	0.079	0.0	0.0	0.0	1.01	17.8	10.7

The Alan Johnston Partnership		Page 2
1 Dale Street Liverpool L2 2ET	220-096 - Project Red Electrical Infrastructure Existing Brownfield Runoff	
Date 06/05/2022 08:50	Designed by JRS	
File Existing Brownfield Runoff.MDX	Checked by PB	
Micro Drainage	Network 2019.1	

Area Summary for Storm

Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)
1.000	-	-	100	0.079	0.079	0.079
1.001	-	-	100	0.000	0.000	0.000
1.002	-	-	100	0.000	0.000	0.000
				Total	Total	Total
				0.079	0.079	0.079

Free Flowing Outfall Details for Storm

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
---------------------	--------------	--------------	--------------	------------------	----------	--------

S1.002	S	40.000	38.347	0.000	0	0
--------	---	--------	--------	-------	---	---

Simulation Criteria for Storm

Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m³/ha Storage	2.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1

Number of Input Hydrographs	0	Number of Offline Controls	0	Number of Time/Area Diagrams	0
Number of Online Controls	0	Number of Storage Structures	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Profile Type	Summer
Return Period (years)	2	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	18.000	Storm Duration (mins)	30
Ratio R	0.358		

The Alan Johnston Partnership		Page 3
1 Dale Street Liverpool L2 2ET	220-096 - Project Red Electrical Infrastructure Existing Brownfield Runoff	
Date 06/05/2022 08:50	Designed by JRS	
File Existing Brownfield Runoff.MDX	Checked by PB	
Micro Drainage	Network 2019.1	

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coefficient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
 Number of Online Controls 0 Number of Storage Structures 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR M5-60 (mm) 18.000 Cv (Summer) 0.750
 Region England and Wales Ratio R 0.358 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0 DVD Status OFF
 Analysis Timestep Fine Inertia Status OFF
 DTS Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440
 Return Period(s) (years) 1, 2, 30, 100
 Climate Change (%) 0, 0, 0, 0

									Water	Surcharged	Flooded
	US/MH		Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Level	Depth	Volume
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	(m)	(m)	(m³)
S1.000	SSW01	15 Winter	1	+0%	30/15 Summer				38.734	-0.066	0.000
S1.001	SSW02	15 Winter	1	+0%	30/15 Summer				38.633	-0.066	0.000
S1.002	SSW03	15 Winter	1	+0%	30/15 Summer				38.532	-0.066	0.000

				Pipe	
PN	US/MH Name	Flow / Cap.	Overflow (l/s)	Flow (l/s)	Level Exceeded
S1.000	SSW01	0.59		9.4	OK
S1.001	SSW02	0.60		9.5	OK
S1.002	SSW03	0.60		9.5	OK

The Alan Johnston Partnership		Page 4
1 Dale Street Liverpool L2 2ET	220-096 - Project Red Electrical Infrastructure Existing Brownfield Runoff	
Date 06/05/2022 08:50	Designed by JRS	
File Existing Brownfield Runoff.MDX	Checked by PB	
Micro Drainage	Network 2019.1	

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coefficient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
 Number of Online Controls 0 Number of Storage Structures 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR M5-60 (mm) 18.000 Cv (Summer) 0.750
 Region England and Wales Ratio R 0.358 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0 DVD Status OFF
 Analysis Timestep Fine Inertia Status OFF
 DTS Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440
 Return Period(s) (years) 1, 2, 30, 100
 Climate Change (%) 0, 0, 0, 0

									Water	Surcharged	Flooded
	US/MH		Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Level	Depth	Volume
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	(m)	(m)	(m³)
S1.000	SSW01	15 Winter	2	+0%	30/15 Summer				38.751	-0.049	0.000
S1.001	SSW02	15 Winter	2	+0%	30/15 Summer				38.650	-0.049	0.000
S1.002	SSW03	15 Winter	2	+0%	30/15 Summer				38.548	-0.050	0.000

					Pipe
PN	US/MH Name	Flow / Cap.	Overflow (l/s)	Flow (l/s)	Level Exceeded
S1.000	SSW01	0.77		12.2	OK
S1.001	SSW02	0.77		12.3	OK
S1.002	SSW03	0.77		12.3	OK

The Alan Johnston Partnership		Page 5
1 Dale Street Liverpool L2 2ET	220-096 - Project Red Electrical Infrastructure Existing Brownfield Runoff	
Date 06/05/2022 08:50	Designed by JRS	
File Existing Brownfield Runoff.MDX	Checked by PB	
Micro Drainage	Network 2019.1	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coefficient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
 Number of Online Controls 0 Number of Storage Structures 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR M5-60 (mm) 18.000 Cv (Summer) 0.750
 Region England and Wales Ratio R 0.358 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0 DVD Status OFF
 Analysis Timestep Fine Inertia Status OFF
 DTS Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440
 Return Period(s) (years) 1, 2, 30, 100
 Climate Change (%) 0, 0, 0, 0

									Water	Surcharged	Flooded
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Level (m)	Depth (m)	Volume (m³)
S1.000	SSW01	15 Winter	30	+0%	30/15 Summer				38.991	0.191	0.000
S1.001	SSW02	15 Winter	30	+0%	30/15 Summer				38.815	0.116	0.000
S1.002	SSW03	15 Winter	30	+0%	30/15 Summer				38.653	0.055	0.000

		Pipe		Level	
PN	US/MH Name	Flow / Cap.	Overflow (l/s)	Flow (l/s)	Status
S1.000	SSW01	1.30		20.7	SURCHARGED
S1.001	SSW02	1.28		20.3	SURCHARGED
S1.002	SSW03	1.27		20.1	SURCHARGED

The Alan Johnston Partnership		Page 6
1 Dale Street Liverpool L2 2ET	220-096 - Project Red Electrical Infrastructure Existing Brownfield Runoff	
Date 06/05/2022 08:50	Designed by JRS	
File Existing Brownfield Runoff.MDX	Checked by PB	
Micro Drainage	Network 2019.1	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coefficient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
 Number of Online Controls 0 Number of Storage Structures 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR M5-60 (mm) 18.000 Cv (Summer) 0.750
 Region England and Wales Ratio R 0.358 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0 DVD Status OFF
 Analysis Timestep Fine Inertia Status OFF
 DTS Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440
 Return Period(s) (years) 1, 2, 30, 100
 Climate Change (%) 0, 0, 0, 0

									Water	Surcharged	Flooded
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Level (m)	Depth (m)	Volume (m³)
S1.000	SSW01	15 Winter	100	+0%	30/15 Summer				39.250	0.450	0.000
S1.001	SSW02	15 Winter	100	+0%	30/15 Summer				38.986	0.287	0.000
S1.002	SSW03	15 Winter	100	+0%	30/15 Summer				38.741	0.143	0.000

		Pipe		Level	
PN	US/MH Name	Flow / Cap.	Overflow (l/s)	Flow (l/s)	Status
S1.000	SSW01	1.61		25.5	SURCHARGED
S1.001	SSW02	1.58		25.0	SURCHARGED
S1.002	SSW03	1.56		24.8	SURCHARGED