EXTENT OF FLOORING BEING REPLACED

GROUND FLOOR PLAN

Extent of flooring being replaced due to new underfloor heating installation, concealed speedgates base, and concealed containment routes.

STONE SAMPLE AGAINST EXISTING FLOORING

STONE SPECIFICATION

TI-01	TILE & STONE		HARDSCAPE / BRICK AND STONE	TO MATCH EXISTING SMITHWORTH BLUE FINISH: SAWN SIZE: 400mm WIDTH VARIABLE LENGHT TO MATCH EXISTING THICKNESS: 40mm (TBC WITH CORE SAMPLE) GROUT: MAPEI ULTRACOLOUR PLUS COLOUR TO MATCH EXISTING