


PLOT VERIFICATION REPORT

Environmental Cover System Validation

Site Name	Levenshulme Road, Gorton		
Developer	Watson Construction Ltd	Inspection Date	10/04/2025 (Area 1-7), 28/04/2025 (Area 8)
Plot Number	7-37 (Apartment Block)	Inspected By	LGD / AE
Construction phase remedial requirements specified in the Updated Phase 2 Geo-Environmental Investigation, Risk Assessment and Remediation Strategy by LKC (ref: LKC 22 1031-B1-GI R1, dated July 2023) and comprised: • Front and Rear Gardens: Geotextile membrane and at least 600mm comprising clean inert fill and sufficient topsoil for a growing medium. • Shared Landscaping: Geotextile membrane and at least 450mm comprising clean inert fill and sufficient topsoil for a growing medium. Results of the topsoil used in the gardens is provided in a letter report undertaken by LKC (Ref. LKC 23 1665-E01-SSR-R1). Results of the subsoil used in the gardens is provided in a letter report undertaken by LKC (Ref. LKC 23 1665-E02-SSR-R1).			
			
View of landscaped Area 1.	View of membrane and soil in capping layer excavation in landscaped Area 1.	Depth measurement of the capping layer in landscaped Area 1 (c.550mm).	
			
View of landscaped Area 2.	View of membrane and soil in capping layer excavation in landscaped Area 2.	Depth measurement of the capping layer in landscaped Area 2 (c.500mm).	
			
View of landscaped Area 3.	View of membrane and soil in capping layer excavation in landscaped Area 3.	Depth measurement of the capping layer in landscaped Area 3 (c.490mm).	

PLOT VERIFICATION REPORT

Environmental Cover System Validation

		
View of landscaped Area 4.	View of membrane and soil in capping layer excavation in landscaped Area 4.	Depth measurement of the capping layer in landscaped Area 4 (c.470mm).
		
View of landscaped Area 5.	View of membrane and soil in capping layer excavation in landscaped Area 5.	Depth measurement of the capping layer in landscaped Area 5 (c.480mm).
		
View of landscaped Area 6.	View of membrane and soil in capping layer excavation in landscaped Area 6.	Depth measurement of the capping layer in landscaped Area 6 (c.450mm).
		
View of landscaped Area 7.	View of membrane and soil in capping layer excavation in landscaped Area 7.	Depth measurement of the capping layer in landscaped Area 7 (c.450mm).

PLOT VERIFICATION REPORT

Environmental Cover System Validation



View of landscaped Area 8.

View of membrane and soil in capping layer excavation in landscaped Area 8.

Depth measurement of the capping layer in landscaped Area 8 (c.450mm).

Location	Topsoil Depth (mm)	Subsoil Depth (mm)	Membrane Present?	Total Depth (mm)	Required Depth (mm)	Pass (✓) or Fail (x)
Area 1	150	400	Yes	550	450	✓
Area 2	150	350	Yes	500	450	✓
Area 3	150	340	Yes	490	450	✓
Area 4	170	300	Yes	470	450	✓
Area 5	180	300	Yes	480	450	✓
Area 6	200	250	Yes	450	450	✓
Area 7	150	300	Yes	450	450	✓
Area 8	200	250	Yes	450	450	✓

LKC has completed the inspection of the capping depth and conclude the correct depth was installed in accordance with the remedial requirements.

Report Prepared By Alex Evans **Report Reviewed By** Rachel Peart

DISCLAIMER

This report has been prepared by LK Consult Ltd (LKC) who have exercised such professional skill, care and diligence as may reasonably be expected of a properly qualified and competent consultant, experienced in preparing reports of a similar scope. However, to the extent that the report is based or relies upon information contained in records, reports or other materials provided to LKC, which have not been independently produced or verified, LKC gives no warranty, representation, or assurance as to the accuracy or completeness of such information.

This report is issued on the condition that LKC will not be held liable for any loss arising from ground conditions between sampling points (i.e., boreholes/trial pits/hand augers/surface samples) which have not been shown by the sampling points or related testing carried out during the investigation, nor for any loss arising from conditions below the maximum depth of the investigation. Opinions on such conditions, where given, are for general guidance only.



Other works including inter alia hotspot removal, drainage, soil texture, nutrients, permitting, invasive species management and geotechnical requirements are out with this scope and should be dealt with by others.

This report is prepared solely for the benefit of the client named above. It may not be relied upon by or submitted to a third party for their reliance for the purposes of valuation, mortgage, insurance, and regulatory approval until all invoices have been settled in full. Those using this information in subsequent assessments or evaluations do so at their own risk.

Enclosed:

Validation Area Location Plan

Soil suitability Report



Extract from: TADW Architects
Drawing Ref: Proposed Site Plan, No.02, Issue:P18 (14/12/2022)

KEY



Site Boundary

Schedule of Accommodation

- 11no. 2B3P apartments at 61sqm each
- 20no. 1B3P apartments at 50sqm each
- 6no. 2B3P two storey houses at 70sqm each
- Total 37 units**

Surface Finishes

- Grassed Area (200mm mowing strip where lawn meets buildings)
- Footpaths, pavements and paved areas
- Block paving to parking bays and raised crossings / rumble strips on access road
- Tarmac to adopted road and parking courtyards
- Refer to Landscape Plan by Trevor Bridge Associates for landscaping proposals
- EVCP Electric vehicle charging point
- Secure external bike storage container

- 1 Validation Area Ref

Sampling Locations and features annotated by LK Consult Ltd are approximate and are based upon observed measurements unless otherwise stated. Do not scale from this drawing and work from marked dimensions only. All dimensions and features should be confirmed on site by the Contractor. Where this drawing includes information provided to LK Consult Ltd by others, LK Consult Ltd gives no warranty, representation or assurance as to the accuracy of such information.



Client:			
Watson Construction Ltd			
Site:			
Levenshulme Road, Gorton			
Title:			
Validation Area Plan			
Job No.:	Scale (See Scale Bar):	Figure:	Revision:
LKC 23 1665	See Scale Bar	1	A
Drawn By:	Checked By:	Drawn:	
AC	RP	Apr 2025	



SOIL VERIFICATION REPORT

Topsoil Suitability

Site Name	Levenshulme Road, Gorton		
Developer	Watson Construction Ltd	Report Reference	LKC 23 1665-E01-SSR
Material Source	Gleaves View, Daresbury Garden Village, WA4 4AN	Test Location	Tested at site
Material Volume	Approx. 187m ³	Inspection Date	23/01/2025 10/04/2025
No. Samples Tested	4	Inspected By	FP / LGD

Rationale

Sampling rates and sampling suites were specified in Section 9.2 in the Updated Phase 2 Geo-Environmental Investigation, Risk Assessment and Remediation Strategy by LKC (ref: LKC 22 1031-B1-GI R1, dated July 2023) The table below details the sampling requirements:

Material Type	Source	Suite of Analysis	Sampling Rate (min. 3 per source) *		
			Garden	Landscape	Other **
Topsoil / subsoil / Fill material	Proven Greenfield	Suite A	200m ³	200m ³	200m ³
	Remediated	Suite A / B dependent upon original SI	100m ³	150m ³	200m ³
	Brownfield / Unknown	Suite B	50m ³	150m ³	200m ³

Notes:

Suite A - Arsenic, cadmium, total chromium, hexavalent chromium, copper, lead, zinc, selenium, nickel, mercury, boron, USEPA PAH 16, asbestos identification, pH, water soluble sulphate and Soil Organic Matter (SOM).

Suite B - Arsenic, cadmium, total chromium, hexavalent chromium, copper, lead, zinc, selenium, nickel, mercury, boron, USEPA PAH 16, asbestos identification, pH, water soluble sulphate, Soil Organic Matter (SOM), TPHCWG, BTEX Compounds, MTBE, phenols, and cyanide suite.

** Other assumed to be stone / 6F2 / mass fill etc.

It was unknown if the topsoil that was imported was from a greenfield source, therefore a 'Suite B' and 1 sample per 50m³ was undertaken as a conservative measure.

Methodology

Composite samples were taken from the garden areas by hand digging following methodology presented in ISO 10381-8:2006 and collected in plastic tubs and amber jars and stored in ice packed coolboxes for same day collection by DETS. Soil results are enclosed.

Risk Assessment – Human Health

Remedial targets followed rationale described in the Updated Phase 2 Geo-Environmental Investigation, Risk Assessment and Remediation Strategy. Imported material to be used in gardens have been compared against residential with plant uptake criteria. Appropriate criteria are enclosed.

LKC has inspected the soil, tested the appropriate number and risk assessed the data. With regards to human health, LKC can confirm that the soil is 'suitable for use'.

Report Prepared By:	Fraser Peers	Report Reviewed By	Rachel Peart
----------------------------	--------------	---------------------------	--------------

DISCLAIMER

This report has been prepared by LKC who have exercised such professional skill, care and diligence as may reasonably be expected of a properly qualified and competent consultant experienced in preparing reports of a similar scope. However, to the extent that the report is based on or relies upon information contained in records, reports or other materials provided to LKC which have not been independently produced or verified, LKC gives no warranty, representation, or assurance as to the accuracy or completeness of such information.

This report is issued on the condition that LKC will not be held liable for any loss arising from ground conditions between sampling points (i.e., boreholes/trial pits/hand augers/surface samples) which have not been shown by the sampling points or related testing carried out during the validation investigation, nor for any loss arising from conditions below the maximum depth of the validation investigation, or for any works done to the garden areas following the date of inspection. Opinions on such conditions, where given, are for general guidance only.

Other works including inter alia hotspot removal, drainage, soil texture, nutrients, permitting, invasive species management and geotechnical requirements are out with this scope and should be dealt with by others.

This report is prepared solely for the benefit of the client named above. It may not be relied upon by, or submitted to a third party for their reliance for the purposes of valuation, mortgage, insurance and regulatory approval, until all invoices have been settled in full. Those using this information in subsequent assessments or evaluations do so at their own risk.

Enclosed:

Laboratory Results, Generic Assessment Criteria



Rachel Peart
LK Consult Limited
Unit 29 Eton Business Park
Eton Hill Road
Manchester
M26 2ZS

Normec DETS Limited
Unit 1
Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Kent
ME17 2JN
t: 01622 850410

DETS Report No: 25-00778

Site Reference: Levenshulme Road, Gorton

Project / Job Ref: LKC231665

Order No: PO-C000837

Sample Receipt Date: 28/01/2025

Sample Scheduled Date: 28/01/2025

Report Issue Number: 1

Reporting Date: 05/02/2025

Authorised by:

Steve Knight
Customer Support Manager

Dates of laboratory activities for each tested analyte are available upon request.

Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate						
DETS Report No: 25-00778	~Date Sampled	23/01/25	23/01/25	23/01/25		
LK Consult Limited	~Time Sampled	None Supplied	None Supplied	None Supplied		
~Site Reference: Levenshulme Road, Gorton	~TP / BH No	TS1	TS2	TS3		
~Project / Job Ref: LKC231665	~Additional Refs	None Supplied	None Supplied	None Supplied		
~Order No: PO-C000837	~Depth (m)	None Supplied	None Supplied	None Supplied		
Reporting Date: 05/02/2025	DETS Sample No	761391	761392	761393		

Determinand	Unit	RL	Accreditation					
Asbestos Screen ^(S)	N/a	N/a	ISO17025	Not Detected	Not Detected	Not Detected		
pH	pH Units	N/a	MCERTS	7.3	7.1	7.4		
Total Cyanide	mg/kg	< 1	NONE	< 1	< 1	< 1		
Free Cyanide	mg/kg	< 1	NONE	< 1	< 1	< 1		
W/S Sulphate as SO ₄ (2:1)	mg/l	< 10	MCERTS	31	35	31		
W/S Sulphate as SO ₄ (2:1)	g/l	< 0.01	MCERTS	0.03	0.03	0.03		
Organic Matter (SOM)	%	< 0.1	MCERTS	2.7	2.2	2.2		
Arsenic (As)	mg/kg	< 2	MCERTS	8	7	8		
W/S Boron	mg/kg	< 1	NONE	< 1	< 1	< 1		
Cadmium (Cd)	mg/kg	< 0.2	MCERTS	0.3	0.3	0.3		
Chromium (Cr)	mg/kg	< 2	MCERTS	16	15	16		
Chromium (hexavalent)	mg/kg	< 2	NONE	< 2	< 2	< 2		
Copper (Cu)	mg/kg	< 4	MCERTS	26	23	23		
Lead (Pb)	mg/kg	< 3	MCERTS	34	30	31		
Mercury (Hg)	mg/kg	< 1	MCERTS	< 1	< 1	< 1		
Nickel (Ni)	mg/kg	< 3	MCERTS	11	11	12		
Selenium (Se)	mg/kg	< 2	MCERTS	< 2	< 2	< 2		
Vanadium (V)	mg/kg	< 1	MCERTS	18	17	18		
Zinc (Zn)	mg/kg	< 3	MCERTS	40	44	43		
Total Phenols (monohydric)	mg/kg	< 2	NONE	< 2	< 2	< 2		

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Method Description page describes if the test is performed on the dried or as-received portion

Subcontracted analysis (S)

~Sample details provided by customer and can affect the validity of results

Subcontracted analysis (S)



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - Speciated PAHs						
DETS Report No: 25-00778	~Date Sampled	23/01/25	23/01/25	23/01/25		
LK Consult Limited	~Time Sampled	None Supplied	None Supplied	None Supplied		
~Site Reference: Levenshulme Road, Gorton	~TP / BH No	TS1	TS2	TS3		
~Project / Job Ref: LKC231665	~Additional Refs	None Supplied	None Supplied	None Supplied		
~Order No: PO-C000837	~Depth (m)	None Supplied	None Supplied	None Supplied		
Reporting Date: 05/02/2025	DETS Sample No	761391	761392	761393		

Determinand	Unit	RL	Accreditation					
Naphthalene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Acenaphthylene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Acenaphthene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Fluorene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Phenanthrene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Anthracene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Pyrene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Benzo(a)anthracene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Chrysene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Benzo(b)fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Benzo(k)fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Benzo(a)pyrene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Indeno(1,2,3-cd)pyrene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Dibenz(a,h)anthracene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Benzo(ghi)perylene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1		
Total EPA-16 PAHs	mg/kg	< 1.6	MCERTS	< 1.6	< 1.6	< 1.6		

~Sample details provided by customer and can affect the validity of results



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - TPH CWG Banded

DETS Report No: 25-00778	~Date Sampled	23/01/25	23/01/25	23/01/25		
LK Consult Limited	~Time Sampled	None Supplied	None Supplied	None Supplied		
~Site Reference: Levenshulme Road, Gorton	~TP / BH No	TS1	TS2	TS3		
~Project / Job Ref: LKC231665	~Additional Refs	None Supplied	None Supplied	None Supplied		
~Order No: PO-C000837	~Depth (m)	None Supplied	None Supplied	None Supplied		
Reporting Date: 05/02/2025	DETS Sample No	761391	761392	761393		

Determinand	Unit	RL	Accreditation					
Aliphatic >C5 - C6 : HS_1D_MS_AL	mg/kg	< 0.01	NONE	< 0.01	< 0.01	< 0.01		
Aliphatic >C6 - C8 : HS_1D_MS_AL	mg/kg	< 0.05	NONE	< 0.05	< 0.05	< 0.05		
Aliphatic >C8 - C10 : EH_CU_1D_AL	mg/kg	< 2	MCERTS	< 2	< 2	< 2		
Aliphatic >C10 - C12 : EH_CU_1D_AL	mg/kg	< 2	MCERTS	< 2	< 2	< 2		
Aliphatic >C12 - C16 : EH_CU_1D_AL	mg/kg	< 3	MCERTS	< 3	< 3	< 3		
Aliphatic >C16 - C21 : EH_CU_1D_AL	mg/kg	< 3	MCERTS	< 3	< 3	< 3		
Aliphatic >C21 - C34 : EH_CU_1D_AL	mg/kg	< 10	MCERTS	< 10	< 10	< 10		
Aliphatic >C34 - C44 : EH_CU_1D_AL	mg/kg	< 10	NONE	< 10	< 10	< 10		
Aliphatic (C5 - C44) : HS_1D_MS+EH_CU_1D_AL	mg/kg	< 21	NONE	< 21	< 21	< 21		
Aromatic >C5 - C7 : HS_1D_MS_AR	mg/kg	< 0.01	NONE	< 0.01	< 0.01	< 0.01		
Aromatic >C7 - C8 : HS_1D_MS_AR	mg/kg	< 0.05	NONE	< 0.05	< 0.05	< 0.05		
Aromatic >C8 - C10 : EH_CU_1D_AR	mg/kg	< 2	MCERTS	< 2	< 2	< 2		
Aromatic >C10 - C12 : EH_CU_1D_AR	mg/kg	< 2	MCERTS	< 2	< 2	< 2		
Aromatic >C12 - C16 : EH_CU_1D_AR	mg/kg	< 2	MCERTS	< 2	< 2	< 2		
Aromatic >C16 - C21 : EH_CU_1D_AR	mg/kg	< 3	MCERTS	< 3	< 3	< 3		
Aromatic >C21 - C35 : EH_CU_1D_AR	mg/kg	< 10	MCERTS	< 10	< 10	< 10		
Aromatic >C35 - C44 : EH_CU_1D_AR	mg/kg	< 10	NONE	< 10	< 10	< 10		
Aromatic (C5 - C44) : HS_1D_MS+EH_CU_1D_AR	mg/kg	< 21	NONE	< 21	< 21	< 21		
Total >C5 - C44 : HS_1D_MS+EH_CU_1D_Tot al	mg/kg	< 42	NONE	< 42	< 42	< 42		

~Sample details provided by customer and can affect the validity of results



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - BTEX / MTBE						
DETS Report No: 25-00778	~Date Sampled	23/01/25	23/01/25	23/01/25		
LK Consult Limited	~Time Sampled	None Supplied	None Supplied	None Supplied		
~Site Reference: Levenshulme Road, Gorton	~TP / BH No	TS1	TS2	TS3		
~Project / Job Ref: LKC231665	~Additional Refs	None Supplied	None Supplied	None Supplied		
~Order No: PO-C000837	~Depth (m)	None Supplied	None Supplied	None Supplied		
Reporting Date: 05/02/2025	DETS Sample No	761391	761392	761393		

Determinand	Unit	RL	Accreditation					
Benzene : HS_1D_MS	µg/kg	< 2	MCERTS	< 2	< 2	< 2		
Toluene : HS_1D_MS	µg/kg	< 5	MCERTS	< 5	< 5	< 5		
Ethylbenzene : HS_1D_MS	µg/kg	< 2	MCERTS	< 2	< 2	< 2		
p & m-xylene : HS_1D_MS	µg/kg	< 2	MCERTS	< 2	< 2	< 2		
o-xylene : HS_1D_MS	µg/kg	< 2	MCERTS	< 2	< 2	< 2		
MTBE : HS_1D_MS	µg/kg	< 5	MCERTS	< 5	< 5	< 5		

~Sample details provided by customer and can affect the validity of results



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - Sample Descriptions

DETS Report No: 25-00778	
LK Consult Limited	
~Site Reference: Levenshulme Road, Gorton	
~Project / Job Ref: LKC231665	
~Order No: PO-C000837	
Reporting Date: 05/02/2025	

DETS Sample No	~TP / BH No	~Additional Refs	~Depth (m)	Moisture Content (%)	Sample Matrix Description
761391	TS1	None Supplied	None Supplied	15.8	Brown sandy clay
761392	TS2	None Supplied	None Supplied	14.8	Brown sandy clay
761393	TS3	None Supplied	None Supplied	14.9	Brown sandy clay with stones

Moisture content is part of procedure E003 & is not an accredited test

Insufficient Sample ^{U/S}

Unsuitable Sample ^{U/S}

~Sample details provided by customer and can affect the validity of results



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - Methodology & Miscellaneous Information

DETS Report No: 25-00778

LK Consult Limited

~Site Reference: Levenshulme Road, Gorton

~Project / Job Ref: LKC231665

~Order No: PO-C000837

Reporting Date: 05/02/2025

Matrix	Analysed On	Determinand	Brief Method Description	Method No
Soil	D	Boron - Water Soluble	Determination of water soluble boron in soil by 2:1 hot water extract followed by ICP-OES	E012
Soil	AR	BTEX	Determination of BTEX by headspace GC-MS	E001
Soil	D	Cations	Determination of cations in soil by aqua-regia digestion followed by ICP-OES	E002
Soil	D	Chloride - Water Soluble (2:1)	Determination of chloride by extraction with water & analysed by ion chromatography	E009
Soil	AR	Chromium - Hexavalent	Determination of hexavalent chromium in soil by extraction in water then by acidification, addition of 1,5 diphenylcarbazide followed by colorimetry	E016
Soil	AR	Cyanide - Complex	Determination of complex cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Free	Determination of free cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Total	Determination of total cyanide by distillation followed by colorimetry	E015
Soil	D	Cyclohexane Extractable Matter (CEM)	Gravimetrically determined through extraction with cyclohexane	E011
Soil	AR	Diesel Range Organics (C10 - C24)	Determination of hexane/acetone extractable hydrocarbons by GC-FID	E004
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of saturated calcium sulphate followed by electrometric measurement	E022
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of water followed by electrometric measurement	E023
Soil	D	Elemental Sulphur	Determination of elemental sulphur by solvent extraction followed by GC-MS	E020
Soil	AR	EPH (C10 - C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH Product ID	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH TEXAS (C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID for C8 to C40. C6 to C8 by headspace GC-MS	E004
Soil	D	Fluoride - Water Soluble	Determination of Fluoride by extraction with water & analysed by ion chromatography	E009
Soil	D	Fraction Organic Carbon (FOC)	Determination of TOC by combustion analyser.	E027
Soil	D	Organic Matter (SOM)	Determination of TOC by combustion analyser.	E027
Soil	D	TOC (Total Organic Carbon)	Determination of TOC by combustion analyser.	E027
Soil	AR	Exchangeable Ammonium	Determination of ammonium by discrete analyser.	E029
Soil	D	FOC (Fraction Organic Carbon)	Determination of fraction of organic carbon by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	D	Loss on Ignition @ 450oC	Determination of loss on ignition in soil by gravimetrically with the sample being ignited in a muffle furnace	E019
Soil	D	Magnesium - Water Soluble	Determination of water soluble magnesium by extraction with water followed by ICP-OES	E025
Soil	D	Metals	Determination of metals by aqua-regia digestion followed by ICP-OES	E002
Soil	AR	Mineral Oil (C10 - C40)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge	E004
Soil	AR	Moisture Content	Moisture content; determined gravimetrically	E003
Soil	D	Nitrate - Water Soluble (2:1)	Determination of nitrate by extraction with water & analysed by ion chromatography	E009
Soil	D	Organic Matter	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	PAH - Speciated (EPA 16)	Determination of PAH compounds by extraction in acetone and hexane followed by GC-MS with the use of surrogate and internal standards	E005
Soil	AR	PCB - 7 Congeners	Determination of PCB by extraction with acetone and hexane followed by GC-MS	E008
Soil	D	Petroleum Ether Extract (PEE)	Gravimetrically determined through extraction with petroleum ether	E011
Soil	AR	pH	Determination of pH by addition of water followed by electrometric measurement	E007
Soil	AR	Phenols - Total (monohydric)	Determination of phenols by distillation followed by colorimetry	E021
Soil	D	Phosphate - Water Soluble (2:1)	Determination of phosphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Total	Determination of total sulphate by extraction with 10% HCl followed by ICP-OES	E013
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of sulphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of water soluble sulphate by extraction with water followed by ICP-OES	E014
Soil	AR	Sulphide	Determination of sulphide by distillation followed by colorimetry	E018
Soil	D	Sulphur - Total	Determination of total sulphur by extraction with aqua-regia followed by ICP-OES	E024
Soil	AR	SVOC	Determination of semi-volatile organic compounds by extraction in acetone and hexane followed by GC-MS	E006
Soil	AR	Thiocyanate (as SCN)	Determination of thiocyanate by extraction in caustic soda followed by acidification followed by addition of ferric nitrate followed by colorimetry	E017
Soil	D	Toluene Extractable Matter (TEM)	Gravimetrically determined through extraction with toluene	E011
Soil	D	Total Organic Carbon (TOC)	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	TPH CWG (ali: C5- C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C34, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C35. C5 to C8 by headspace GC-MS	E004
Soil	AR	TPH LQM (ali: C5-C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C35, C35-C44, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35, C35-C44)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C44. C5 to C8 by headspace GC-MS	E004
Soil	AR	VOCs	Determination of volatile organic compounds by headspace GC-MS	E001
Soil	AR	VPH (C6-C8 & C8-C10)	Determination of hydrocarbons C6-C8 by headspace GC-MS & C8-C10 by GC-FID	E001

D Dried
AR As Received

~Sample details provided by customer and can affect the validity of results



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



List of HWOL Acronyms and Operators	
DETS Report No: 25-00778	
LK Consult Limited	
~Site Reference: Levenshulme Road, Gorton	
~Project / Job Ref: LKC231665	
~Order No: PO-C000837	
Reporting Date: 05/02/2025	

Acronym	Description
HS	Headspace analysis
EH	Extractable Hydrocarbons - i.e. everything extracted by the solvent
CU	Clean-up - e.g. by florisil, silica gel
1D	GC - Single coil gas chromatography
2D	GC-GC - Double coil gas chromatography
Total	Aliphatics & Aromatics
AL	Aliphatics only
AR	Aromatics only
#1	EH_2D_Total but with humics mathematically subtracted
#2	EH_2D_Total but with fatty acids mathematically subtracted
	Operator - underscore to separate acronyms (exception for +)
+	Operator to indicate cumulative eg. EH+HS_Total or EH_CU+HS_Total
~	Sample details provided by customer and can affect the validity of results

Benzene - HS_1D_MS
Ethylbenzene - HS_1D_MS
MTBE - HS_1D_MS
TPH - Aliphatic >C34 - C44 - raw data - EH_CU_1D_AL
TPH CWG - Aliphatic >C10 - C12 - EH_CU_1D_AL
TPH CWG - Aliphatic >C12 - C16 - EH_CU_1D_AL
TPH CWG - Aliphatic >C16 - C21 - EH_CU_1D_AL
TPH CWG - Aliphatic >C21 - C34 - EH_CU_1D_AL
TPH CWG - Aliphatic >C34 - C44 - EH_CU_1D_AL
TPH CWG - Aliphatic >C5 - C44 - HS_1D_MS+EH_CU_1D_AL
TPH CWG - Aliphatic >C5 - C6 - HS_1D_MS_AL
TPH CWG - Aliphatic >C6 - C8 - HS_1D_MS_AL
TPH CWG - Aliphatic >C8 - C10 - EH_CU_1D_AL
TPH CWG - Aromatic >C10 - C12 - EH_CU_1D_AR
TPH CWG - Aromatic >C12 - C16 - EH_CU_1D_AR
TPH CWG - Aromatic >C16 - C21 - EH_CU_1D_AR
TPH CWG - Aromatic >C21 - C35 - EH_CU_1D_AR
TPH CWG - Aromatic >C35 - C44 - EH_CU_1D_AR
TPH CWG - Aromatic >C5 - C44 - HS_1D_MS+EH_CU_1D_AR
TPH CWG - Aromatic >C5 - C7 - HS_1D_MS_AR
TPH CWG - Aromatic >C7 - C8 - HS_1D_MS_AR
TPH CWG - Aromatic >C8 - C10 - EH_CU_1D_AR
TPH CWG - Total >C5 - C44 - HS_1D_MS+EH_CU_1D_Total
Toluene - HS_1D_MS
m & p-xylene - HS_1D_MS
o-Xylene - HS_1D_MS

Certificate of Analysis

Certificate Number 25-08330

Issued: 24-Apr-25

Client LK Consult Limited
Unit 29
Eton Business Park
Eton Hill Road
Radcliffe
Manchester
M26 2ZS

Our Reference 25-08330

Client Reference ~ LKC231665

Order No ~ PO-C001206

Contract Title ~ Levenshulme Road, Gorton

Description 1 Soil sample.

Date Received 14-Mar-25

Date Started 14-Apr-25

Date Completed 24-Apr-25

Test Procedures Identified by prefix DETSn (details on request).

Notes Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.

Approved By



Louise Cook
Contracts Manager



Summary of Chemical Analysis

Soil Samples

Our Ref 25-08330

Client Ref ~ LKC231665

Contract Title ~ Levenshulme Road, Gorton

Lab No	2494727
Sample ID ~	TS201
Depth ~	
Other ID ~	
Sample Type ~	SOIL
Sampling Date ~	10/04/2025
Sampling Time ~	n/s

Test	Method	LOD	Units	
Metals				
Arsenic	DETSC 2301#	0.2	mg/kg	12
Boron, Water Soluble (2.5:1)	DETSC 2311#	0.2	mg/kg	0.7
Cadmium	DETSC 2301#	0.1	mg/kg	0.8
Chromium	DETSC 2301#	0.15	mg/kg	11
Chromium, Hexavalent	DETSC 2204*	1	mg/kg	< 1.0
Copper	DETSC 2301#	0.2	mg/kg	34
Lead	DETSC 2301#	0.3	mg/kg	62
Mercury	DETSC 2325#	0.05	mg/kg	< 0.05
Nickel	DETSC 2301#	1	mg/kg	8.7
Selenium	DETSC 2301#	0.5	mg/kg	< 0.5
Vanadium	DETSC 2301#	0.8	mg/kg	14
Zinc	DETSC 2301#	1	mg/kg	100
Inorganics				
pH	DETSC 2008#		pH	8.2
Cyanide, Total	DETSC 2130#	0.1	mg/kg	0.3
Cyanide, Free	DETSC 2130#	0.1	mg/kg	0.2
Organic matter	DETSC 2002#	0.1	%	2.0
Sulphate Aqueous Extract as SO4 (2:1)	DETSC 2076*	0.001	%	0.195
Petroleum Hydrocarbons				
Aliphatic C5-C6: HS_1D_AL	DETSC 3321*	0.01	mg/kg	< 0.01
Aliphatic C6-C8: HS_1D_AL	DETSC 3321*	0.01	mg/kg	< 0.01
Aliphatic C8-C10: HS_1D_AL	DETSC 3321*	0.01	mg/kg	< 0.01
Aliphatic >EC10-EC12: EH_2D_AL	DETSC 3521#	1.5	mg/kg	< 1.50
Aliphatic >EC12-EC16: EH_2D_AL	DETSC 3521#	1.2	mg/kg	< 1.20
Aliphatic >EC16-EC21: EH_2D_AL	DETSC 3521#	1.5	mg/kg	< 1.50
Aliphatic >EC21-EC35: EH_2D_AL	DETSC 3521#	3.4	mg/kg	< 3.40
Aliphatic >EC35-EC40: EH_2D_AL	DETSC 3521*	3.4	mg/kg	< 3.40
Aliphatic >EC40-EC44: EH_2D_AL	DETSC 3521*	3.4	mg/kg	< 3.40
Aliphatic C5-C44: EH_2D+HS_1D_AL	DETSC 3521*	10	mg/kg	< 10.00
Aromatic C5-C7: HS_1D_AR	DETSC 3321*	0.01	mg/kg	< 0.01
Aromatic C7-C8: HS_1D_AR	DETSC 3321*	0.01	mg/kg	< 0.01
Aromatic C8-C10: HS_1D_AR	DETSC 3321*	0.01	mg/kg	< 0.01
Aromatic >EC10-EC12: EH_2D_AR	DETSC 3521#	0.9	mg/kg	< 0.90
Aromatic >EC12-EC16: EH_2D_AR	DETSC 3521#	0.5	mg/kg	< 0.50
Aromatic >EC16-EC21: EH_2D_AR	DETSC 3521#	0.6	mg/kg	< 0.60
Aromatic >EC21-EC35: EH_2D_AR	DETSC 3521#	1.4	mg/kg	< 1.40
Aromatic >EC35-EC40: EH_2D_AR	DETSC 3521*	1.4	mg/kg	< 1.40
Aromatic >EC40-EC44: EH_2D_AR	DETSC 3521*	1.4	mg/kg	< 1.40
Aromatic C5-C44: EH_2D+HS_1D_AR	DETSC 3521*	10	mg/kg	< 10.00
TPH Ali/Aro C5-C44: EH_2D+HS_1D_Total	DETSC 3521*	10	mg/kg	< 10.00
Benzene	DETSC 3321#	0.01	mg/kg	< 0.01

Summary of Chemical Analysis

Soil Samples

Our Ref 25-08330

Client Ref ~ LKC231665

Contract Title ~ Levenshulme Road, Gorton

Lab No	2494727
Sample ID ~	TS201
Depth ~	
Other ID ~	
Sample Type ~	SOIL
Sampling Date ~	10/04/2025
Sampling Time ~	n/s

Test	Method	LOD	Units	
Ethylbenzene	DETSC 3321#	0.01	mg/kg	< 0.01
Toluene	DETSC 3321#	0.01	mg/kg	< 0.01
Xylene	DETSC 3321#	0.01	mg/kg	< 0.01
m+p Xylene	DETSC 3321#	0.01	mg/kg	< 0.01
o Xylene	DETSC 3321#	0.01	mg/kg	< 0.01
MTBE	DETSC 3321	0.01	mg/kg	< 0.01
PAHs				
Naphthalene	DETSC 3301	0.1	mg/kg	< 0.1
Acenaphthylene	DETSC 3301	0.1	mg/kg	< 0.1
Acenaphthene	DETSC 3301	0.1	mg/kg	< 0.1
Fluorene	DETSC 3301	0.1	mg/kg	0.1
Phenanthrene	DETSC 3301	0.1	mg/kg	1.0
Anthracene	DETSC 3301	0.1	mg/kg	0.2
Fluoranthene	DETSC 3301	0.1	mg/kg	1.2
Pyrene	DETSC 3301	0.1	mg/kg	1.0
Benzo(a)anthracene	DETSC 3301	0.1	mg/kg	0.5
Chrysene	DETSC 3301	0.1	mg/kg	0.6
Benzo(b)fluoranthene	DETSC 3301	0.1	mg/kg	0.3
Benzo(k)fluoranthene	DETSC 3301	0.1	mg/kg	0.3
Benzo(a)pyrene	DETSC 3301	0.1	mg/kg	0.5
Indeno(1,2,3-c,d)pyrene	DETSC 3301	0.1	mg/kg	< 0.1
Dibenzo(a,h)anthracene	DETSC 3301	0.1	mg/kg	< 0.1
Benzo(g,h,i)perylene	DETSC 3301	0.1	mg/kg	< 0.1
PAH 16 Total	DETSC 3301	1.6	mg/kg	5.8
Phenols				
Phenol - Monohydric	DETSC 2130#	0.3	mg/kg	< 0.3

Summary of Asbestos Analysis Soil Samples

Our Ref 25-08330

Client Ref ~ LKC231665

Contract Title ~ Levenshulme Road, Gorton

Lab No	Sample ID	Material Type	Result	Comment*	Analyst
2494727	TS201	SOIL	NAD	none	Lee Kerridge

Crocidolite = Blue Asbestos, Amosite = Brown Asbestos, Chrysotile = White Asbestos. Anthophyllite, Actinolite and Tremolite are other forms of Asbestos. Samples are analysed by DETSC 1101 using polarised light microscopy in accordance with HSG248 and documented in-house methods. NAD = No Asbestos Detected. Where a sample is NAD, the result is based on analysis of at least 2 sub-samples and should be taken to mean 'no asbestos detected in sample'. Key: * -not included in laboratory scope of accreditation.

Information in Support of the Analytical Results

Our Ref 25-08330
 Client Ref ~ LKC231665
 Contract ~ Levenshulme Road, Gorton

Containers Received & Deviating Samples

Lab No	Sample ID ~	Date	Containers Received	Holding time	Incorrect
		Sampled ~		exceeded for tests	container for tests
2494727	TS201 SOIL	10/04/25	GJ 250ml, GJ 60ml, PT 1L		
Key: G-Glass P-Plastic J-Jar T-Tub Normec DETS cannot be held responsible for the integrity of samples received whereby the laboratory did not undertake the sampling. In this instance samples received may be deviating. Deviating Sample criteria are based on British and International standards and laboratory trials in conjunction with the UKAS note 'Guidance on Deviating Samples'. All samples received are listed above. However, those samples that have additional comments in relation to hold time, inappropriate containers etc are deviating due to the reasons stated. This means that the analysis is accredited where applicable, but results may be compromised due to sample deviations. If no sampled date (soils) or date+time (waters) has been supplied then samples are deviating. However, if you are able to supply a sampled date (and time for waters) this will prevent samples being reported as deviating where specific hold times are not exceeded and where the container supplied is suitable.					

Soil Analysis Notes

Inorganic soil analysis was carried out on a dried sample, crushed to pass a 250µm sieve
 Organic soil analysis was carried out on an 'as received' sample. Organics results are corrected for moisture and expressed on a dry weight basis.
 The Loss on Drying, used to express organics analysis on an air dried basis, is carried out at a temperature of 28°C +/-2°C.

Disposal

From the issue date of this test certificate, samples will be held for the following times prior to disposal :-
 Soils - 1 month, Liquids - 2 weeks, Asbestos (test portion) - 6 months

Information in Support of the Analytical Results

List of HWOL Acronyms and Operators

Acronym	Description
HS	Headspace analysis
EH	Extractable Hydrocarbons - i.e. everything extracted by the solvent
CU	Clean-up - e.g. by florisil, silica gel
1D	GC - Single coil gas chromatography
2D	GC-GC - Double coil gas chromatography
Total	Aliphatics & Aromatics
AL	Aliphatics only
AR	Aromatics only
#1	EH_2D_Total but with humics mathematically subtracted
#2	EH_2D_Total but with fatty acids mathematically subtracted
_	Operator - underscore to separate acronyms (exception for +)
+	Operator to indicate cumulative eg. EH+HS_Total or EH_CU+HS_Total

Det	Acronym
Aliphatic C5-C6	HS_1D_AL
Aliphatic C6-C8	HS_1D_AL
Aliphatic C8-C10	HS_1D_AL
Aliphatic >EC10-EC12	EH_2D_AL
Aliphatic >EC12-EC16	EH_2D_AL
Aliphatic >EC16-EC21	EH_2D_AL
Aliphatic >EC21-EC35	EH_2D_AL
Aliphatic >EC35-EC40	EH_2D_AL
Aliphatic >EC40-EC44	EH_2D_AL
Aliphatic C5-C44	EH_2D+HS_1D_AL
Aromatic C5-C7	HS_1D_AR
Aromatic C7-C8	HS_1D_AR
Aromatic C8-C10	HS_1D_AR
Aromatic >EC10-EC12	EH_2D_AR
Aromatic >EC12-EC16	EH_2D_AR
Aromatic >EC16-EC21	EH_2D_AR
Aromatic >EC21-EC35	EH_2D_AR
Aromatic >EC35-EC40	EH_2D_AR
Aromatic >EC40-EC44	EH_2D_AR
Aromatic C5-C44	EH_2D+HS_1D_AR
TPH Ali/Aro C5-C44	EH_2D+HS_1D_Total

Key:

~ Sample details are provided by the client and can affect the validity of the results

* -not accredited.

-MCERTS (accreditation only applies if report carries the MCERTS logo).

\$ -subcontracted.

n/s -not supplied.

I/S -insufficient sample.

U/S -unsuitable sample.

t/f -to follow.

nd -not detected.

End of Report

Generic Assessment Criteria Values

Contaminant		SOM	Res +	Res -	Allot.	Comm.	POS ^{resi}	POS ^{park}	Source
Metals	Inorganic Arsenic	N/A	37	40	49	640	79	168	DEFRA C4SL
	Beryllium	N/A	1.7	1.7	35	12	2.2	63	LQM S4UL
	Boron	N/A	290	11,000	45	240,000	21,000	46,000	LQM S4UL
	Cadmium	N/A	26	149	4.9	410	220	880	DEFRA C4SL
	Chromium (III)	N/A	910	910	18,000	8,600	1,500	33,000	LQM S4UL
	Chromium (VI)	N/A	21.0	21.0	170.0	49	23.0	250	DEFRA C4SL
	Copper	N/A	2,400	7,100	520	68,000	12,000	44,000	LQM S4UL
	Lead	N/A	200	310	80	2,330	630	1,300	DEFRA C4SL
	Elemental Mercury	N/A	1.2	1.2	21	58 (25.8) ^{vap}	16	30 (25.8) ^{vap}	LQM S4UL
	Inorganic Mercury	N/A	40	56	19	1,100	120	240	LQM S4UL
	Methylmercury	N/A	11	15	6.0	320	40	68	LQM S4UL
	Nickel (2015 update)	N/A	130	180	53	980	230	800	LQM S4UL
	Selenium	N/A	250	430	88	12,000	1,100	1,800	LQM S4UL
	Vanadium	N/A	410	1,200	91	9,000	2,000	5,000	LQM S4UL
Zinc	N/A	3,700	40,000	620	730,000	81,000	170,000	LQM S4UL	
Polycyclic Aromatic Hydrocarbons (PAHs)	Acenaphthene	1%	210	3,000 (57.1) ^{sol}	34	84,000 (57.0) ^{sol}	15,000	29,000	LQM S4UL
		2.5%	510	4,700 (141) ^{sol}	85	97,000 (141) ^{sol}	15,000	30,000	LQM S4UL
		6%	1,100	6,000 (336) ^{sol}	200	100,000	15,000	30,000	LQM S4UL
	Acenaphthylene	1%	170	2,900 (86.1) ^{sol}	28	83,000 (86.1) ^{sol}	15,000	29,000	LQM S4UL
		2.5%	420	4,600 (212) ^{sol}	69	97,000 (212) ^{sol}	15,000	30,000	LQM S4UL
		6%	920	6,000 (506) ^{sol}	160	100,000	15,000	30,000	LQM S4UL
	Anthracene	1%	2,400	31,000 (1.17) ^{vap}	380	520,000	74,000	150,000	LQM S4UL
		2.5%	5,400	35,000	950	540,000	74,000	150,000	LQM S4UL
		6%	11,000	37,000	2,200	540,000	74,000	150,000	LQM S4UL
	Benz(a)anthracene	1%	7.2	11	2.9	170	29	49	LQM S4UL
		2.5%	11	14	6.5	170	29	56	LQM S4UL
		6%	13	15	13	180	29	62	LQM S4UL
	Benzo(a)pyrene (only)	1%	5.0	5.3	5.70	77	10.0	21	DEFRA C4SL
		2.5%	5.0	5.3	5.70	77	10.0	21	DEFRA C4SL
		6%	5.0	5.3	5.70	77	10.0	21	DEFRA C4SL
	Benzo(a)pyrene (surrogate marker Coal Tar)	1%	0.8	1.2	0.32	15	2.2	4	LQM S4UL
		2.5%	1.0	1.2	0.67	15	2.2	5	LQM S4UL
		6%	1.1	1.2	1.20	15	2.2	5	LQM S4UL
	Benzo(b)fluoranthene	1%	2.6	3.9	0.99	44	7.1	13	LQM S4UL
		2.5%	3.3	4.0	2.1	44	7.2	15	LQM S4UL
		6%	3.7	4.0	3.9	45	7.2	16	LQM S4UL
	Benzo(ghi)perylene	1%	320	360	290	3,900	640	1,400	LQM S4UL
		2.5%	340	360	470	4,000	640	1,500	LQM S4UL
		6%	350	360	640	4,000	640	1,600	LQM S4UL
	Benzo(k)fluoranthene	1%	77	110	37	1,200	190	370	LQM S4UL
		2.5%	93	110	75	1,200	190	410	LQM S4UL
		6%	100	110	130	1,200	190	440	LQM S4UL
	Chrysene	1%	15	30	4.1	350	57	93	LQM S4UL
		2.5%	22	31	9.4	350	57	110	LQM S4UL
		6%	27	32	19	350	57	120	LQM S4UL
	Dibenzo(ah)anthracene	1%	0.24	0.31	0.14	3.5	0.57	1.1	LQM S4UL
		2.5%	0.28	0.32	0.27	3.6	0.58	1.3	LQM S4UL
		6%	0.3	0.32	0.43	3.6	0.58	1.4	LQM S4UL
	Fluoranthene	1%	280	1,500	52	23,000	3,100	6,300	LQM S4UL
		2.5%	560	1,600	130	23,000	3,100	6,300	LQM S4UL
		6%	890	1,600	290	23,000	3,100	6,400	LQM S4UL
	Fluorene	1%	170	2,800 (36.0) ^{sol}	27	63,000 (30.9) ^{sol}	9,900	20,000	LQM S4UL
		2.5%	400	3,800 (76.5) ^{sol}	67	68,000	9,900	20,000	LQM S4UL
		6%	860	4,500 (183) ^{sol}	160	71,000	9,900	20,000	LQM S4UL
	Indeno(123-cd)pyrene	1%	27	45	9.5	500	82	150	LQM S4UL
		2.5%	36	46	21	510	82	170	LQM S4UL
		6%	41	46	39	510	82	180	LQM S4UL
	Naphthalene	1%	15	15	65	1,600*	11,000*	8,400*	DEFRA C4SL
		2.5%	36	36	130	3,700*	15,000*	17,00*	DEFRA C4SL
		6%	85	85	200	8,400*	1,200*	1,900*	DEFRA C4SL
	Phenanthrene	1%	95	1,300 (36.0) ^{sol}	15	22,000	3,100	6,200	LQM S4UL
		2.5%	220	1,500	38	22,000	3,100	6,200	LQM S4UL
		6%	440	1,500	90	22,000	3,100	6,300	LQM S4UL
	Pyrene	1%	620	3,700	110	54,000	7,400	15,000	LQM S4UL
		2.5%	1,200	3,800	270	54,000	7,400	15,000	LQM S4UL
		6%	2,000	3,800	620	54,000	7,400	15,000	LQM S4UL
	Coal Tar (B(a)P as surrogate marker)	1%	0.79	1.2	0.32	15	2.2	4.4	LQM S4UL
		2.5%	0.98	1.2	0.67	15	2.2	4.7	LQM S4UL
		6%	1.1	1.2	1.2	15	2.2	4.8	LQM S4UL

Generic Assessment Criteria Values

Contaminant		SOM	Res +	Res -	Allot.	Comm.	POS ^{res} i	POS ^{park}	Source
BTEX Compounds	Benzene	1%	0.87	0.38	0.017	27	72	90	LQM S4UL
		2.5%	0.17	0.70	0.034	47	72	100	LQM S4UL
		6%	0.37	1.4	0.075	90	73	110	LQM S4UL
	Toluene	1%	130	880 (869) vap	22	56,000 (869) vap	56,000	87,000 (869) vap	LQM S4UL
		2.5%	290	1,900	51	110,000 (1,920) vap	56,000	95,000 (1,920) vap	LQM S4UL
		6%	660	3,900	120	180,000 (4,360) vap	56,000	100,000 (4,360) vap	LQM S4UL
	Ethylbenzene	1%	47	83	16	5,700 (518) vap	24,000	17,000 (518) vap	LQM S4UL
		2.5%	110	190	39	13,000 (1,220) vap	24,000	22,000 (1,220) vap	LQM S4UL
		6%	260	440	91	27,000 (2,840) vap	25,000	27,000 (2,840) vap	LQM S4UL
	o-xylene	1%	60	88	28	6,600 (478) sol	41,000	17,000 (478) sol	LQM S4UL
		2.5%	140	210	67	15,000 (1,120) sol	42,000	24,000 (1,120) sol	LQM S4UL
		6%	330	480	160	33,000 (2,620) sol	43,000	33,000 (2,620) sol	LQM S4UL
	m-xylene	1%	59	82	31	6,200 (625) vap	41,000	17,000 (625) vap	LQM S4UL
		2.5%	140	190	74	14,000 (1,470) vap	42,000	24,000 (1,470) vap	LQM S4UL
		6%	320	450	170	31,000 (3,460) vap	43,000	32,000 (3,460) vap	LQM S4UL
	p-xylene	1%	56	79	29	5,900 (576) sol	41,000	17,000 (576) sol	LQM S4UL
		2.5%	130	180	69	14,000 (1,350) sol	42,000	23,000 (1,350) sol	LQM S4UL
		6%	310	430	160	30,000 (3,170) sol	43,000	31,000 (3,170) sol	LQM S4UL
Petroleum Hydroc	Aliphatic								
	EC 5-6	1%	42	42	730	3,200 (304) sol	570,000(304) ^{sol}	95,000 (304) sol	LQM S4UL
	EC>6-8	1%	100	100	2,300	7,800 (144) sol	600,000	150,000 (144) sol	LQM S4UL
	EC>8-10	1%	27	27	320	2,000 (78) sol	13,000	14,000 (78) vap	LQM S4UL
	EC>10-12	1%	130 (48) vap	130 (48) vap	2,200	9,700 (48) sol	13,000	21,000 (48) vap	LQM S4UL
	EC>12-16	1%	1,100 (24) sol	1,100 (24) sol	11,000	59,000 (24) sol	13,000	25,000 (24) sol	LQM S4UL
	EC>16-35	1%	65,000 (8.48)	65,000 (8.48) f, sol	260,000 f	160,000 f	250,000 f	450,000 f	LQM S4UL
	EC>35-44	1%	65,000 (8.48)	65,000 (8.48) f, sol	260,000 f	160,000 f	250,000 f	450,000 f	LQM S4UL
	Aliphatic								
	EC 5-6	2.5%	78	78	1,700	5,900 (558) sol	590,000	130,000 (558) sol	LQM S4UL
	EC>6-8	2.5%	230	230	5,600	17,000 (322) sol	610,000	220,000 (322) sol	LQM S4UL
	EC>8-10	2.5%	65	65	770	4,800 (190) vap	13,000	18,000 (190) vap	LQM S4UL
	EC>10-12	2.5%	330 (118) vap	330 (118) vap	4,400	23,000 (118) vap	13,000	23,000 (118) vap	LQM S4UL
	EC>12-16	2.5%	2,400 (59) sol	2,400 (59) sol	13,000	82,000 (59) sol	13,000	25,000 (59) sol	LQM S4UL
	EC>16-35	2.5%	92,000 (21)	92,000 (21) f, sol	270,000 f	1,700,000 f	250,000 f	480,000 f	LQM S4UL
	EC>35-44	2.5%	92,000 (21)	92,000 (21) f, sol	270,000 f	1,700,000 f	250,000 f	480,000 f	LQM S4UL
	Aliphatic								
	EC 5-6	6%	160	160	3,900	12,000 (1,150) sol	600,000	180,000 (1,150)	LQM S4UL
	EC>6-8	6%	530	530	13,000	40,000 (736) sol	620,000	320,000 (736) sol	LQM S4UL
	EC>8-10	6%	150	150	1,700	11,000 (451) vap	13,000	21,000 (451) vap	LQM S4UL
	EC>10-12	6%	760 (283) vap	760 (283) vap	7,300	47,000 (283) vap	13,000	24,000 (283) vap	LQM S4UL
	EC>12-16	6%	4,300 (142) sol	4,400 (142) sol	13,000	90,000 (142) sol	13,000	26,000 (142) sol	LQM S4UL
	EC>16-35	6%	110,000 f	110,000 f	270,000 f	1,800,000 f	250,000 f	490,000 f	LQM S4UL
	EC>35-44	6%	110,000 f	110,000 f	270,000 f	1,800,000 f	250,000 f	490,000 f	LQM S4UL
	Aromatic								
	EC5-7(benzene as non-	1%	70	370	13	26,000 (1,220) sol	56,000	76,000 (1,220) sol	LQM S4UL
	EC>7-8(toluene)	1%	130	860	22	56,000 (869) vap	56,000	87,000 (869) vap	LQM S4UL
	EC>8-10	1%	34	47	8.6	3,500 (613) vap	5,000	7,200 (613) vap	LQM S4UL
	EC>10-12	1%	74	250	13	16,000 (364) sol	5,000	9,200 (364) sol	LQM S4UL
	EC>12-16	1%	140	1,800	23	36,000 (169) sol	5,100	10,000	LQM S4UL
	EC>16-21	1%	260 f	1,900 f	46 f	28,000 f	3,800 f	7,600 f	LQM S4UL
	EC>21-35	1%	1,100 f	1,900 f	370 f	28,000 f	3,800 f	7,800 f	LQM S4UL
	EC>35-44	1%	1,100 f	1,900 f	370 f	28,000 f	3,800 f	7,800 f	LQM S4UL
	Aromatic								
	EC5-7(benzene as non-	2.5%	140	690	27	46,000 (2,260) sol	56,000	84,000 (2,260) sol	LQM S4UL
	EC>7-8(toluene)	2.5%	290	1,800	51	110,000 (1,920) sol	56,000	95,000 (1,920) sol	LQM S4UL
	EC>8-10	2.5%	83	110	21	8,100 (1,500) vap	5,000	8,500 (1,500) vap	LQM S4UL
	EC>10-12	2.5%	180	590	31	28,000 (899) sol	5,000	9,700 (899) sol	LQM S4UL
	EC>12-16	2.5%	330	2,300 (419) sol	57	37,000	5,100	10,000	LQM S4UL
	EC>16-21	2.5%	540 f	1,900 f	110 f	28,000 f	3,800 f	7,700 f	LQM S4UL
	EC>21-35	2.5%	1,500 f	1,900 f	820 f	28,000 f	3,800 f	7,800 f	LQM S4UL
	EC>35-44	2.5%	1,500 f	1,900 f	820 f	28,000 f	3,800 f	7,800 f	LQM S4UL
	Aromatic								
	EC5-7(benzene as non-	6%	300	1,400	57	86,000 (4,710) sol	56,000	92,000 (4,710) sol	LQM S4UL
	EC>7-8(toluene)	6%	660	3,900	120	180,000 (4,360) vap	56,000	100,000 (4,360)	LQM S4UL
	EC>8-10	6%	190	270	51	17,000 (3,580) vap	5,000	9,300 (3,580) vap	LQM S4UL
	EC>10-12	6%	380	1,200	4	34,000 (2,150) sol	5,000	10,000	LQM S4UL
	EC>12-16	6%	660	2,500	130	38,000	5,100	10,000	LQM S4UL
	EC>16-21	6%	930 f	1,900 f	260 f	28,000 f	3,800 f	7,800 f	LQM S4UL
	EC>21-35	6%	1,700 f	1,900 f	1,600 f	28,000 f	3,800 f	7,900 f	LQM S4UL
	EC>35-44	6%	1,700 f	1,900 f	1,600 f	28,000 f	3,800 f	7,900 f	LQM S4UL
	Aliphatic +Aromatic >EC44	1%	1,600 f	1,900 f	1,200 f	28,000 f	3,800 f	7,800 f	LQM S4UL
		2.5%	1,800 f	1,900 f	2,100 f	28,000 f	3,800 f	7,800 f	LQM S4UL
		6%	1,900 f	1,900 f	3,000 f	28,000 f	3,800 f	7,900 f	LQM S4UL

Generic Assessment Criteria Values

Contaminant		SOM	Res +	Res -	Allot.	Comm.	POS ^{res} i	POS ^{park}	Source
Chloroalkanes and Alkenes & Explosives	1,2 Dichloroethane (DCA)	1%	0.0071	0.0092	0.0046	0.67	29	21	LQM S4UL
		2.5%	0.0110	0.0130	0.0083	0.97	29	24	LQM S4UL
		6%	0.0190	0.0230	0.0160	1.7	29	28	LQM S4UL
	1,1,1 Trichloroethane (TCA)	1%	8.8	9.0	48	660	140,000	57,000 (1,425) ^{vap}	LQM S4UL
		2.5%	18	18	110	1,300	140,000	76,000 (2,915) ^{vap}	LQM S4UL
		6%	39	40	240	3,000	140,000	100,000 (6,392)	LQM S4UL
	1,1,2,2-Tetrachloroethanes (PCA)	1%	1.6	3.9	0.41	270	1,400	1,800	LQM S4UL
		2.5%	3.4	8.0	0.89	550	1,400	2,100	LQM S4UL
		6%	7.5	17	2.0	1,100	1,400	2,300	LQM S4UL
	1,1,1,2-Tetrachloroethanes (PCA)	1%	1.2	1.5	0.79	110	1,400	1,500	LQM S4UL
		2.5%	2.8	3.5	1.9	250	1,400	1,800	LQM S4UL
		6%	6.4	8.2	4.4	560	1,400	2,100	LQM S4UL
	Tetrachloroethene (PCE)	1%	0.31	0.32	2.00	24	3,200	1400	DEFRA C4SL
		2.5%	0.70	0.71	4.8	55	3,300	1900	DEFRA C4SL
		6%	1.60	1.60	11.0	130	3,400	2,500	DEFRA C4SL
	Tetrachloromethane (carbon tetrachloride)	1%	0.03	0.03	0.45	2.9	890	190	LQM S4UL
		2.5%	0.06	0.06	1.0	6.3	920	270	LQM S4UL
		6%	0.13	0.13	2.4	14	950	400	LQM S4UL
	Trichloroethene (TCE)	1%	0.009	0.010	0.032	0.7	76.0	41.0	DEFRA C4SL
		2.5%	0.020	0.020	0.072	1.5	78.0	51.0	DEFRA C4SL
		6%	0.043	0.045	0.160	3.4	79.0	69.0	DEFRA C4SL
	cis 1,2-dichloroethene	1%	0.46	0.50	0.890	38	3,800	2,000	DEFRA C4SL
		2.5%	0.78	0.84	1.70	64	3,800	2,400	DEFRA C4SL
		6%	1.50	1.60	3.60	120	3,900	3,100	DEFRA C4SL
	Trichloromethane (chloroform)	1%	0.91	1.2	0.42	99	2,500	2,600	LQM S4UL
		2.5%	1.7	2.1	0.83	170	2,500	2,800	LQM S4UL
		6%	3.4	4.2	1.7	350	2,500	3,100	LQM S4UL
	Trans-1,2 Dichloroethene	1%	0.9	0.9	3.7	69	13,000	5,600	DEFRA C4SL
		2.5%	1.6	1.7	7.5	120	13,000	7,000	DEFRA C4SL
		6%	3.3	3.4	16.0	260	13,000	9,100	DEFRA C4SL
	Chloroethene (vinyl chloride)	1%	0.006	0.015	0.0017	1.1E+00	7.8	18.0	DEFRA C4SL
		2.5%	0.010	0.019	0.0031	1.4E+00	7.8	19.0	DEFRA C4SL
		6%	0.017	0.029	0.0058	2.20	7.8	19.0	DEFRA C4SL
	2,4,6-Trinitrotoluene (TNT)	1%	1.6	65	0.24	1,000	130	260	LQM S4UL
		2.5%	3.7	66	0.58	1,000	130	270	LQM S4UL
		6%	8.1	66	1.4	1,000	130	270	LQM S4UL
	RDX	1%	120	13,000	17	210,000	26,000	49,000 (18.7) ^{sol}	LQM S4UL
		2.5%	250	13,000	38	210,000	26,000	51,000	LQM S4UL
		6%	540	13,000	85	210,000	27,000	53,000	LQM S4UL
	HMX	1%	5.7	6,700	0.86	110,000	13,000	23,000 (0.35) ^{vap}	LQM S4UL
		2.5%	13	6,700	1.9	110,000	13,000	23,000 (0.39) ^{vap}	LQM S4UL
		6%	26	6,700	3.9	110,000	13,000	24,000 (0.48) ^{vap}	LQM S4UL
Pesticides	Aldrin	1%	5.7	7.3	3.2	170	18	30	LQM S4UL
		2.5%	6.6	7.4	6.1	170	18	31	LQM S4UL
		6%	7.1	7.5	9.8	170	18	31	LQM S4UL
	Dieldrin	1%	0.97	7.0	0.17	170	18	30	LQM S4UL
		2.5%	2.0	7.3	0.41	170	18	30	LQM S4UL
		6%	3.5	7.4	0.96	170	18	31	LQM S4UL
	Atrazine	1%	3.3	610	0.5	9,300	1,200	2,300	LQM S4UL
		2.5%	7.8	620	1.2	9,400	1,200	2,400	LQM S4UL
		6%	17.4	620	2.7	9,400	1,200	2,400	LQM S4UL
	Dichlorvos	1%	3.2E-02	6.4	4.9E-03	140	16	26	LQM S4UL
		2.5%	6.6E-02	6.5	1.0E-02	140	16	26	LQM S4UL
		6%	0.14	6.6	2.2E-02	140	16	27	LQM S4UL
	Endosulfans (2 isomers)	1%	7.4	160 (3.0E-03) ^{vap}	1.2	5,600 (3.0E-03) ^{vap}	1,200	2,300	LQM S4UL
		2.5%	18	280 (7.0E-03) ^{vap}	2.9	7,400 (7.0E-03) ^{vap}	1,200	2,400	LQM S4UL
		6%	41	410 (1.6E-02) ^{vap}	6.8	8,400 (1.6E-02) ^{vap}	1,200	2,500	LQM S4UL
	Hexachlorocyclohexane (3 isomers), inc Lindane	1%	8.5E-02	3.7	1.3E-02	65	8.1	15	LQM S4UL
		2.5%	0.2	3.8	3.2E-02	65	8.1	15	LQM S4UL
		6%	0.46	3.8	7.7E-02	65	8.1	16	LQM S4UL
Chlorobenzenes	Chlorobenzene	1%	0.46	0.46	5.9	56	11,000	1,300 (675) ^{sol}	LQM S4UL
		2.5%	1.0	1.0	14	130	13,000	2,000 (1,520) ^{sol}	LQM S4UL
		6%	2.4	2.4	32	290	14,000	2,900	LQM S4UL
	Dichlorobenzenes (3 isomers)	1%	23	24	94	2,000 (571) ^{sol}	90,000	24,000 (571) ^{sol}	LQM S4UL
		2.5%	55	57	230	4,800 (1,370) ^{sol}	95,000	36,000 (1,370) ^{sol}	LQM S4UL
		6%	130	130	540	11,000 (3,240) ^{sol}	98,000	51,000 (3,270) ^{sol}	LQM S4UL
	Trichlorobenzenes (3 isomers)	1%	2.6	2.6	55	220	15,000	1,700 (318) ^{vap}	LQM S4UL
		2.5%	6.4	6.4	140	530	17,000	2,600 (786) ^{vap}	LQM S4UL
		6%	15	15	320	1,300	19,000	4,000 (1,880) ^{vap}	LQM S4UL
	Tetrachlorobenzenes (3 isomers)	1%	0.66	0.75	0.38	49 (39.4) ^{vap}	78	110 (39) ^{vap}	LQM S4UL
		2.5%	1.6	1.9	0.90	120 (98.1) ^{vap}	79	120	LQM S4UL
		6%	3.7	4.3	2.2	240 (235) ^{vap}	79	130	LQM S4UL
	Pentachlorobenzene	1%	5.8	19	1.2	640 (43.0) ^{sol}	100	190	LQM S4UL
		2.5%	12	30	3.1	770 (107) ^{sol}	100	190	LQM S4UL
		6%	22	38	7.0	830	100	190	LQM S4UL
	Hexachlorobenzene	1%	1.8 (0.20) ^{vap}	4.1 (0.20) ^{vap}	0.47	110 (0.20) ^{vap}	16	30	LQM S4UL
		2.5%	3.3 (0.50) ^{vap}	5.7 (0.50) ^{vap}	1.1	120	16	30	LQM S4UL
		6%	4.9	6.7 (1.2) ^{vap}	2.5	120	16	30	LQM S4UL

Generic Assessment Criteria Values

Contaminant		SOM	Res +	Res -	Allot.	Comm.	POSresi	POSpark	Source
Chlorophenol	Chlorophenols (4 congeners)	1%	0.87 ^g	94	0.13 ^g	3,500	620	1,100	LQM S4UL
		2.5%	2.0	150	0.30	4,000	620	1,100	LQM S4UL
		6%	4.5	210	0.70	4,300	620	1,100	LQM S4UL
	Pentachlorophenol	1%	0.22	27 (16.4) ^{vap}	3.0E-02	400	60	110	LQM S4UL
		2.5%	0.52	29	8.0E-02	400	60	120	LQM S4UL
		6%	1.2	31	0.19	400	60	120	LQM S4UL
Others	Carbon Disulphide	1%	0.14	0.14	4.8	11	11,000	1,300	LQM S4UL
		2.5%	0.29	0.29	10	22	11,000	1,900	LQM S4UL
		6%	0.62	0.62	23	47	11,000	2,700	LQM S4UL
	Hexachlorobutadiene	1%	0.29	0.32	0.25	31	25	48	LQM S4UL
		2.5%	0.7	0.78	0.61	66	25	50	LQM S4UL
		6%	1.6	1.8	1.4	120	25	51	LQM S4UL
	Phenol	1%	120	440 (460)	23	440 ^{dir} (26,000)	440 ^{dir} (10,000)	440 ^{dir} (7,600)	LQM S4UL
		2.5%	200	690	42	690 ^{dir} (30,000)	690 ^{dir} (10,000)	690 ^{dir} (8,300)	LQM S4UL
		6%	380	1,200	83	1,300 ^{dir} (34,000)	1,300 ^{dir} (10,000)	1,300 ^{dir} (9,300)	LQM S4UL
sol/vap = solubility/vapour limit (potentially use if free product identified, although highly conservative)									
* = naphthalene C4SL exceeds the CLEA calculated soil saturation concentration (76 mg kg-1 for 1% SOM, 183 mg kg-1 for 2.5% SOM and 432 mg kg-1 for 6% SOM)									
f = oral, dermal and inhalation exposures compared to oral HCV									
dir = S4ULs based on threshold protective of direct skin contact with phenol)brackets long term exposure for illustration purposes)									
g = derived based on 2,3,4-tetrachlorophenol									

SOIL VERIFICATION REPORT

Subsoil Suitability

Site Name	Levenshulme Road, Gorton		
Developer	Watson Construction Ltd	Report Reference	LKC 23 1665-E02-SSR
Material Source	Ledsham Garden Village, CH66 4DF	Test Location	Tested at site
Material Volume	Approx. 287m ³	Inspection Date	23/01/2025 10/04/2025
No. Samples Tested	7	Inspected By	FP / LGD

Rationale

Sampling rates and sampling suites were specified in Section 9.2 in the Updated Phase 2 Geo-Environmental Investigation, Risk Assessment and Remediation Strategy by LKC (ref: LKC 22 1031-B1-GI R1, dated July 2023) The table below details the sampling requirements:

Material Type	Source	Suite of Analysis	Sampling Rate (min. 3 per source) *		
			Garden	Landscape	Other **
Topsoil / subsoil / Fill material	Proven Greenfield	Suite A	200m ³	200m ³	200m ³
	Remediated	Suite A / B dependent upon original SI	100m ³	150m ³	200m ³
	Brownfield / Unknown	Suite B	50m ³	150m ³	200m ³

Notes:

Suite A - Arsenic, cadmium, total chromium, hexavalent chromium, copper, lead, zinc, selenium, nickel, mercury, boron, USEPA PAH 16, asbestos identification, pH, water soluble sulphate and Soil Organic Matter (SOM).

Suite B - Arsenic, cadmium, total chromium, hexavalent chromium, copper, lead, zinc, selenium, nickel, mercury, boron, USEPA PAH 16, asbestos identification, pH, water soluble sulphate, Soil Organic Matter (SOM), TPHCWG, BTEX Compounds, MTBE, phenols, and cyanide suite.

** Other assumed to be stone / 6F2 / mass fill etc.

It was unknown if the subsoil that was imported was from a greenfield source, therefore a 'Suite B' and 1 sample per 50m³ was undertaken as a conservative measure.

Methodology

Composite samples were taken from the garden areas by hand digging following methodology presented in ISO 10381-8:2006 and collected in plastic tubs and amber jars and stored in ice packed coolboxes for same day collection by DETS. Soil results are enclosed.

Risk Assessment – Human Health

Remedial targets followed rationale described in the Updated Phase 2 Geo-Environmental Investigation, Risk Assessment and Remediation Strategy. Imported material to be used in gardens have been compared against residential with plant uptake criteria. Appropriate criteria are enclosed.

LKC has inspected the soil, tested the appropriate number and risk assessed the data. With regards to human health, LKC can confirm that the soil is 'suitable for use'.

Report Prepared By:	Fraser Peers	Report Reviewed By	Rachel Peart
----------------------------	--------------	---------------------------	--------------

DISCLAIMER

This report has been prepared by LKC who have exercised such professional skill, care and diligence as may reasonably be expected of a properly qualified and competent consultant experienced in preparing reports of a similar scope. However, to the extent that the report is based on or relies upon information contained in records, reports or other materials provided to LKC which have not been independently produced or verified, LKC gives no warranty, representation, or assurance as to the accuracy or completeness of such information.

This report is issued on the condition that LKC will not be held liable for any loss arising from ground conditions between sampling points (i.e., boreholes/trial pits/hand augers/surface samples) which have not been shown by the sampling points or related testing carried out during the validation investigation, nor for any loss arising from conditions below the maximum depth of the validation investigation, or for any works done to the garden areas following the date of inspection. Opinions on such conditions, where given, are for general guidance only.

Other works including inter alia hotspot removal, drainage, soil texture, nutrients, permitting, invasive species management and geotechnical requirements are out with this scope and should be dealt with by others.

This report is prepared solely for the benefit of the client named above. It may not be relied upon by, or submitted to a third party for their reliance for the purposes of valuation, mortgage, insurance and regulatory approval, until all invoices have been settled in full. Those using this information in subsequent assessments or evaluations do so at their own risk.

Enclosed:

Laboratory Results, Generic Assessment Criteria



Rachel Peart
LK Consult Limited
Unit 29 Eton Business Park
Eton Hill Road
Manchester
M26 2ZS

Normec DETS Limited
Unit 1
Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Kent
ME17 2JN
t: 01622 850410

DETS Report No: 25-00780

Site Reference: Levenshulme Road, Gorton

Project / Job Ref: LKC231665

Order No: PO-C000837

Sample Receipt Date: 28/01/2025

Sample Scheduled Date: 28/01/2025

Report Issue Number: 1

Reporting Date: 05/02/2025

Authorised by:

Steve Knight
Customer Support Manager

Dates of laboratory activities for each tested analyte are available upon request.

Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate						
DETS Report No: 25-00780	~Date Sampled	23/01/25	23/01/25	23/01/25		
LK Consult Limited	~Time Sampled	None Supplied	None Supplied	None Supplied		
~Site Reference: Levenshulme Road, Gorton	~TP / BH No	SS1b	SS2b	SS3b		
~Project / Job Ref: LKC231665	~Additional Refs	None Supplied	None Supplied	None Supplied		
~Order No: PO-C000837	~Depth (m)	None Supplied	None Supplied	None Supplied		
Reporting Date: 05/02/2025	DETS Sample No	761397	761398	761399		

Determinand	Unit	RL	Accreditation	(n)	(n)	(n)		
Asbestos Screen ^(S)	N/a	N/a	ISO17025	Not Detected	Not Detected	Not Detected		
pH	pH Units	N/a	ISO17025	8.2	8.3	8.4		
Total Cyanide	mg/kg	< 1	NONE	< 1	< 1	< 1		
Free Cyanide	mg/kg	< 1	NONE	< 1	< 1	< 1		
W/S Sulphate as SO ₄ (2:1)	mg/l	< 10	ISO17025	< 10	24	24		
W/S Sulphate as SO ₄ (2:1)	g/l	< 0.01	ISO17025	< 0.01	0.02	0.02		
Organic Matter (SOM)	%	< 0.1	ISO17025	1	0.6	0.7		
Arsenic (As)	mg/kg	< 2	ISO17025	5	< 2	< 2		
W/S Boron	mg/kg	< 1	NONE	< 1	< 1	< 1		
Cadmium (Cd)	mg/kg	< 0.2	ISO17025	< 0.2	< 0.2	< 0.2		
Chromium (Cr)	mg/kg	< 2	ISO17025	6	3	4		
Chromium (hexavalent)	mg/kg	< 2	NONE	< 2	< 2	< 2		
Copper (Cu)	mg/kg	< 4	ISO17025	10	7	8		
Lead (Pb)	mg/kg	< 3	ISO17025	18	6	8		
Mercury (Hg)	mg/kg	< 1	ISO17025	< 1	< 1	< 1		
Nickel (Ni)	mg/kg	< 3	ISO17025	6	4	6		
Selenium (Se)	mg/kg	< 2	ISO17025	< 2	< 2	< 2		
Vanadium (V)	mg/kg	< 1	ISO17025	8	3	3		
Zinc (Zn)	mg/kg	< 3	ISO17025	22	11	13		
Total Phenols (monohydric)	mg/kg	< 2	NONE	< 2	< 2	< 2		

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Method Description page describes if the test is performed on the dried or as-received portion
Subcontracted analysis (S)

~Sample details provided by customer and can affect the validity of results

(n) Please note we are only MCERTS accredited (UK soils only) for sand, loam and clay and any other matrix is outside our scope of accreditation

Subcontracted analysis (S)



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - Speciated PAHs						
DETS Report No: 25-00780	~Date Sampled	23/01/25	23/01/25	23/01/25		
LK Consult Limited	~Time Sampled	None Supplied	None Supplied	None Supplied		
~Site Reference: Levenshulme Road, Gorton	~TP / BH No	SS1b	SS2b	SS3b		
~Project / Job Ref: LKC231665	~Additional Refs	None Supplied	None Supplied	None Supplied		
~Order No: PO-C000837	~Depth (m)	None Supplied	None Supplied	None Supplied		
Reporting Date: 05/02/2025	DETS Sample No	761397	761398	761399		

Determinand	Unit	RL	Accreditation	(n)	(n)	(n)		
Naphthalene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Acenaphthylene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Acenaphthene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Fluorene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Phenanthrene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Anthracene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Fluoranthene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Pyrene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Benzo(a)anthracene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Chrysene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Benzo(b)fluoranthene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Benzo(k)fluoranthene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Benzo(a)pyrene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Indeno(1,2,3-cd)pyrene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Dibenz(a,h)anthracene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Benzo(ghi)perylene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Total EPA-16 PAHs	mg/kg	< 1.6	ISO17025	< 1.6	< 1.6	< 1.6		

~Sample details provided by customer and can affect the validity of results

(n) Please note we are only MCERTS accredited (UK soils only) for sand, loam and clay and any other matrix is outside our scope of accreditation



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - TPH CWG Banded

DETS Report No: 25-00780	~Date Sampled	23/01/25	23/01/25	23/01/25		
LK Consult Limited	~Time Sampled	None Supplied	None Supplied	None Supplied		
~Site Reference: Levenshulme Road, Gorton	~TP / BH No	SS1b	SS2b	SS3b		
~Project / Job Ref: LKC231665	~Additional Refs	None Supplied	None Supplied	None Supplied		
~Order No: PO-C000837	~Depth (m)	None Supplied	None Supplied	None Supplied		
Reporting Date: 05/02/2025	DETS Sample No	761397	761398	761399		

Determinand	Unit	RL	Accreditation	(n)	(n)	(n)		
Aliphatic >C5 - C6 : HS_1D_MS_AL	mg/kg	< 0.01	NONE	< 0.01	< 0.01	< 0.01		
Aliphatic >C6 - C8 : HS_1D_MS_AL	mg/kg	< 0.05	NONE	< 0.05	< 0.05	< 0.05		
Aliphatic >C8 - C10 : EH_CU_1D_AL	mg/kg	< 2	ISO17025	< 2	< 2	< 2		
Aliphatic >C10 - C12 : EH_CU_1D_AL	mg/kg	< 2	ISO17025	< 2	< 2	< 2		
Aliphatic >C12 - C16 : EH_CU_1D_AL	mg/kg	< 3	ISO17025	< 3	< 3	< 3		
Aliphatic >C16 - C21 : EH_CU_1D_AL	mg/kg	< 3	ISO17025	< 3	< 3	< 3		
Aliphatic >C21 - C34 : EH_CU_1D_AL	mg/kg	< 10	ISO17025	< 10	< 10	< 10		
Aliphatic >C34 - C44 : EH_CU_1D_AL	mg/kg	< 10	NONE	< 10	< 10	< 10		
Aliphatic (C5 - C44) : HS_1D_MS+EH_CU_1D_AL	mg/kg	< 21	NONE	< 21	< 21	< 21		
Aromatic >C5 - C7 : HS_1D_MS_AR	mg/kg	< 0.01	NONE	< 0.01	< 0.01	< 0.01		
Aromatic >C7 - C8 : HS_1D_MS_AR	mg/kg	< 0.05	NONE	< 0.05	< 0.05	< 0.05		
Aromatic >C8 - C10 : EH_CU_1D_AR	mg/kg	< 2	ISO17025	< 2	< 2	< 2		
Aromatic >C10 - C12 : EH_CU_1D_AR	mg/kg	< 2	ISO17025	< 2	< 2	< 2		
Aromatic >C12 - C16 : EH_CU_1D_AR	mg/kg	< 2	ISO17025	< 2	< 2	< 2		
Aromatic >C16 - C21 : EH_CU_1D_AR	mg/kg	< 3	ISO17025	< 3	< 3	< 3		
Aromatic >C21 - C35 : EH_CU_1D_AR	mg/kg	< 10	ISO17025	< 10	< 10	< 10		
Aromatic >C35 - C44 : EH_CU_1D_AR	mg/kg	< 10	NONE	< 10	< 10	< 10		
Aromatic (C5 - C44) : HS_1D_MS+EH_CU_1D_AR	mg/kg	< 21	NONE	< 21	< 21	< 21		
Total >C5 - C44 : HS_1D_MS+EH_CU_1D_Tot al	mg/kg	< 42	NONE	< 42	< 42	< 42		

~Sample details provided by customer and can affect the validity of results

(n) Please note we are only MCERTS accredited (UK soils only) for sand, loam and clay and any other matrix is outside our scope of accreditation



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - BTEX / MTBE						
DETS Report No: 25-00780	~Date Sampled	23/01/25	23/01/25	23/01/25		
LK Consult Limited	~Time Sampled	None Supplied	None Supplied	None Supplied		
~Site Reference: Levenshulme Road, Gorton	~TP / BH No	SS1b	SS2b	SS3b		
~Project / Job Ref: LKC231665	~Additional Refs	None Supplied	None Supplied	None Supplied		
~Order No: PO-C000837	~Depth (m)	None Supplied	None Supplied	None Supplied		
Reporting Date: 05/02/2025	DETS Sample No	761397	761398	761399		

Determinand	Unit	RL	Accreditation	(n)	(n)	(n)		
Benzene : HS_1D_MS	µg/kg	< 2	ISO17025	< 2	< 2	< 2		
Toluene : HS_1D_MS	µg/kg	< 5	ISO17025	< 5	< 5	< 5		
Ethylbenzene : HS_1D_MS	µg/kg	< 2	ISO17025	< 2	< 2	< 2		
p & m-xylene : HS_1D_MS	µg/kg	< 2	ISO17025	< 2	< 2	< 2		
o-xylene : HS_1D_MS	µg/kg	< 2	ISO17025	< 2	< 2	< 2		
MTBE : HS_1D_MS	µg/kg	< 5	ISO17025	< 5	< 5	< 5		

~Sample details provided by customer and can affect the validity of results

(n) Please note we are only MCERTS accredited (UK soils only) for sand, loam and clay and any other matrix is outside our scope of accreditation



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - Sample Descriptions	
DETS Report No: 25-00780	
LK Consult Limited	
~Site Reference: Levenshulme Road, Gorton	
~Project / Job Ref: LKC231665	
~Order No: PO-C000837	
Reporting Date: 05/02/2025	

DETS Sample No	~TP / BH No	~Additional Refs	~Depth (m)	Moisture Content (%)	Sample Matrix Description
761397	SS1b	None Supplied	None Supplied	10.8	Brown sand with stones
761398	SS2b	None Supplied	None Supplied	10.4	Brown sand with stones
761399	SS3b	None Supplied	None Supplied	11.7	Brown sand with stones

Moisture content is part of procedure E003 & is not an accredited test

Insufficient Sample ^{1/5}

Unsuitable Sample ^{U/S}

~Sample details provided by customer and can affect the validity of results



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - Methodology & Miscellaneous Information

DETS Report No: 25-00780

LK Consult Limited

~Site Reference: Levenshulme Road, Gorton

~Project / Job Ref: LKC231665

~Order No: PO-C000837

Reporting Date: 05/02/2025

Matrix	Analysed On	Determinand	Brief Method Description	Method No
Soil	D	Boron - Water Soluble	Determination of water soluble boron in soil by 2:1 hot water extract followed by ICP-OES	E012
Soil	AR	BTEX	Determination of BTEX by headspace GC-MS	E001
Soil	D	Cations	Determination of cations in soil by aqua-regia digestion followed by ICP-OES	E002
Soil	D	Chloride - Water Soluble (2:1)	Determination of chloride by extraction with water & analysed by ion chromatography	E009
Soil	AR	Chromium - Hexavalent	Determination of hexavalent chromium in soil by extraction in water then by acidification, addition of 1,5 diphenylcarbazide followed by colorimetry	E016
Soil	AR	Cyanide - Complex	Determination of complex cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Free	Determination of free cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Total	Determination of total cyanide by distillation followed by colorimetry	E015
Soil	D	Cyclohexane Extractable Matter (CEM)	Gravimetrically determined through extraction with cyclohexane	E011
Soil	AR	Diesel Range Organics (C10 - C24)	Determination of hexane/acetone extractable hydrocarbons by GC-FID	E004
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of saturated calcium sulphate followed by electrometric measurement	E022
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of water followed by electrometric measurement	E023
Soil	D	Elemental Sulphur	Determination of elemental sulphur by solvent extraction followed by GC-MS	E020
Soil	AR	EPH (C10 - C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH Product ID	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH TEXAS (C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID for C8 to C40. C6 to C8 by headspace GC-MS	E004
Soil	D	Fluoride - Water Soluble	Determination of Fluoride by extraction with water & analysed by ion chromatography	E009
Soil	D	Fraction Organic Carbon (FOC)	Determination of TOC by combustion analyser.	E027
Soil	D	Organic Matter (SOM)	Determination of TOC by combustion analyser.	E027
Soil	D	TOC (Total Organic Carbon)	Determination of TOC by combustion analyser.	E027
Soil	AR	Exchangeable Ammonium	Determination of ammonium by discrete analyser.	E029
Soil	D	FOC (Fraction Organic Carbon)	Determination of fraction of organic carbon by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	D	Loss on Ignition @ 450oC	Determination of loss on ignition in soil by gravimetrically with the sample being ignited in a muffle furnace	E019
Soil	D	Magnesium - Water Soluble	Determination of water soluble magnesium by extraction with water followed by ICP-OES	E025
Soil	D	Metals	Determination of metals by aqua-regia digestion followed by ICP-OES	E002
Soil	AR	Mineral Oil (C10 - C40)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge	E004
Soil	AR	Moisture Content	Moisture content; determined gravimetrically	E003
Soil	D	Nitrate - Water Soluble (2:1)	Determination of nitrate by extraction with water & analysed by ion chromatography	E009
Soil	D	Organic Matter	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	PAH - Speciated (EPA 16)	Determination of PAH compounds by extraction in acetone and hexane followed by GC-MS with the use of surrogate and internal standards	E005
Soil	AR	PCB - 7 Congeners	Determination of PCB by extraction with acetone and hexane followed by GC-MS	E008
Soil	D	Petroleum Ether Extract (PEE)	Gravimetrically determined through extraction with petroleum ether	E011
Soil	AR	pH	Determination of pH by addition of water followed by electrometric measurement	E007
Soil	AR	Phenols - Total (monohydric)	Determination of phenols by distillation followed by colorimetry	E021
Soil	D	Phosphate - Water Soluble (2:1)	Determination of phosphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Total	Determination of total sulphate by extraction with 10% HCl followed by ICP-OES	E013
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of sulphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of water soluble sulphate by extraction with water followed by ICP-OES	E014
Soil	AR	Sulphide	Determination of sulphide by distillation followed by colorimetry	E018
Soil	D	Sulphur - Total	Determination of total sulphur by extraction with aqua-regia followed by ICP-OES	E024
Soil	AR	SVOC	Determination of semi-volatile organic compounds by extraction in acetone and hexane followed by GC-MS	E006
Soil	AR	Thiocyanate (as SCN)	Determination of thiocyanate by extraction in caustic soda followed by acidification followed by addition of ferric nitrate followed by colorimetry	E017
Soil	D	Toluene Extractable Matter (TEM)	Gravimetrically determined through extraction with toluene	E011
Soil	D	Total Organic Carbon (TOC)	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	TPH CWG (ali: C5- C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C34, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C35. C5 to C8 by headspace GC-MS	E004
Soil	AR	TPH LQM (ali: C5-C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C35, C35-C44, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35, C35-C44)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C44. C5 to C8 by headspace GC-MS	E004
Soil	AR	VOCs	Determination of volatile organic compounds by headspace GC-MS	E001
Soil	AR	VPH (C6-C8 & C8-C10)	Determination of hydrocarbons C6-C8 by headspace GC-MS & C8-C10 by GC-FID	E001

D Dried
AR As Received

~Sample details provided by customer and can affect the validity of results



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



4480

List of HWOL Acronyms and Operators

DETS Report No: 25-00780

LK Consult Limited

~Site Reference: Levenshulme Road, Gorton

~Project / Job Ref: LKC231665

~Order No: PO-C000837

Reporting Date: 05/02/2025

Acronym	Description
HS	Headspace analysis
EH	Extractable Hydrocarbons - i.e. everything extracted by the solvent
CU	Clean-up - e.g. by florisil, silica gel
1D	GC - Single coil gas chromatography
2D	GC-GC - Double coil gas chromatography
Total	Aliphatics & Aromatics
AL	Aliphatics only
AR	Aromatics only
#1	EH_2D_Total but with humics mathematically subtracted
#2	EH_2D_Total but with fatty acids mathematically subtracted
	Operator - underscore to separate acronyms (exception for +)
+	Operator to indicate cumulative eg. EH+HS_Total or EH_CU+HS_Total
~	Sample details provided by customer and can affect the validity of results

Benzene - HS_1D_MS
Ethylbenzene - HS_1D_MS
MTBE - HS_1D_MS
TPH - Aliphatic >C34 - C44 - raw data - EH_CU_1D_AL
TPH CWG - Aliphatic >C10 - C12 - EH_CU_1D_AL
TPH CWG - Aliphatic >C12 - C16 - EH_CU_1D_AL
TPH CWG - Aliphatic >C16 - C21 - EH_CU_1D_AL
TPH CWG - Aliphatic >C21 - C34 - EH_CU_1D_AL
TPH CWG - Aliphatic >C34 - C44 - EH_CU_1D_AL
TPH CWG - Aliphatic >C5 - C44 - HS_1D_MS+EH_CU_1D_AL
TPH CWG - Aliphatic >C5 - C6 - HS_1D_MS_AL
TPH CWG - Aliphatic >C6 - C8 - HS_1D_MS_AL
TPH CWG - Aliphatic >C8 - C10 - EH_CU_1D_AL
TPH CWG - Aromatic >C10 - C12 - EH_CU_1D_AR
TPH CWG - Aromatic >C12 - C16 - EH_CU_1D_AR
TPH CWG - Aromatic >C16 - C21 - EH_CU_1D_AR
TPH CWG - Aromatic >C21 - C35 - EH_CU_1D_AR
TPH CWG - Aromatic >C35 - C44 - EH_CU_1D_AR
TPH CWG - Aromatic >C5 - C44 - HS_1D_MS+EH_CU_1D_AR
TPH CWG - Aromatic >C5 - C7 - HS_1D_MS_AR
TPH CWG - Aromatic >C7 - C8 - HS_1D_MS_AR
TPH CWG - Aromatic >C8 - C10 - EH_CU_1D_AR
TPH CWG - Total >C5 - C44 - HS_1D_MS+EH_CU_1D_Total
Toluene - HS_1D_MS
m & p-xylene - HS_1D_MS
o-Xylene - HS_1D_MS

Certificate of Analysis

Certificate Number 25-08326

Issued: 28-Apr-25

Client LK Consult Limited
Unit 29
Eton Business Park
Eton Hill Road
Radcliffe
Manchester
M26 2ZS

Our Reference 25-08326

Client Reference ~ LKC231665

Order No ~ PO-C001206

Contract Title ~ Levenshulme Road, Gorton

Description 1 Soil sample.

Date Received 14-Mar-25

Date Started 14-Apr-25

Date Completed 28-Apr-25

Test Procedures Identified by prefix DETSn (details on request).

Notes Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.

Approved By

A handwritten signature in black ink, appearing to read "R. Irfan".

Reyhan Irfan
Operations Manager



Summary of Chemical Analysis

Soil Samples

Our Ref 25-08326

Client Ref ~ LKC231665

Contract Title ~ Levenshulme Road, Gorton

Lab No	2494690
Sample ID ~	SS201
Depth ~	
Other ID ~	
Sample Type ~	SOIL
Sampling Date ~	10/04/2025
Sampling Time ~	n/s

Test	Method	LOD	Units	
Metals				
Arsenic	DETSC 2301#	0.2	mg/kg	4.9
Boron, Water Soluble (2.5:1)	DETSC 2311#	0.2	mg/kg	2.7
Cadmium	DETSC 2301#	0.1	mg/kg	0.2
Chromium	DETSC 2301#	0.15	mg/kg	11
Chromium, Hexavalent	DETSC 2204*	1	mg/kg	< 1.0
Copper	DETSC 2301#	0.2	mg/kg	50
Lead	DETSC 2301#	0.3	mg/kg	27
Mercury	DETSC 2325#	0.05	mg/kg	0.06
Nickel	DETSC 2301#	1	mg/kg	13
Selenium	DETSC 2301#	0.5	mg/kg	< 0.5
Vanadium	DETSC 2301#	0.8	mg/kg	14
Zinc	DETSC 2301#	1	mg/kg	64
Inorganics				
pH	DETSC 2008#		pH	10.1
Cyanide, Total	DETSC 2130#	0.1	mg/kg	0.1
Cyanide, Free	DETSC 2130#	0.1	mg/kg	< 0.1
Organic matter	DETSC 2002#	0.1	%	0.6
Sulphate Aqueous Extract as SO4 (2:1)	DETSC 2076*	0.001	%	0.066
Petroleum Hydrocarbons				
Aliphatic C5-C6: HS_1D_AL	DETSC 3321*	0.01	mg/kg	< 0.01
Aliphatic C6-C8: HS_1D_AL	DETSC 3321*	0.01	mg/kg	< 0.01
Aliphatic C8-C10: HS_1D_AL	DETSC 3321*	0.01	mg/kg	< 0.01
Aliphatic >EC10-EC12: EH_2D_AL	DETSC 3521#	1.5	mg/kg	< 1.50
Aliphatic >EC12-EC16: EH_2D_AL	DETSC 3521#	1.2	mg/kg	< 1.20
Aliphatic >EC16-EC21: EH_2D_AL	DETSC 3521#	1.5	mg/kg	< 1.50
Aliphatic >EC21-EC35: EH_2D_AL	DETSC 3521#	3.4	mg/kg	< 3.40
Aliphatic >EC35-EC40: EH_2D_AL	DETSC 3521*	3.4	mg/kg	< 3.40
Aliphatic >EC40-EC44: EH_2D_AL	DETSC 3521*	3.4	mg/kg	< 3.40
Aliphatic C5-C44: EH_2D+HS_1D_AL	DETSC 3521*	10	mg/kg	< 10.00
Aromatic C5-C7: HS_1D_AR	DETSC 3321*	0.01	mg/kg	< 0.01
Aromatic C7-C8: HS_1D_AR	DETSC 3321*	0.01	mg/kg	< 0.01
Aromatic C8-C10: HS_1D_AR	DETSC 3321*	0.01	mg/kg	< 0.01
Aromatic >EC10-EC12: EH_2D_AR	DETSC 3521#	0.9	mg/kg	< 0.90
Aromatic >EC12-EC16: EH_2D_AR	DETSC 3521#	0.5	mg/kg	< 0.50
Aromatic >EC16-EC21: EH_2D_AR	DETSC 3521#	0.6	mg/kg	< 0.60
Aromatic >EC21-EC35: EH_2D_AR	DETSC 3521#	1.4	mg/kg	< 1.40
Aromatic >EC35-EC40: EH_2D_AR	DETSC 3521*	1.4	mg/kg	< 1.40
Aromatic >EC40-EC44: EH_2D_AR	DETSC 3521*	1.4	mg/kg	< 1.40
Aromatic C5-C44: EH_2D+HS_1D_AR	DETSC 3521*	10	mg/kg	< 10.00
TPH Ali/Aro C5-C44: EH_2D+HS_1D_Total	DETSC 3521*	10	mg/kg	< 10.00
Benzene	DETSC 3321#	0.01	mg/kg	< 0.01

Summary of Chemical Analysis

Soil Samples

Our Ref 25-08326

Client Ref ~ LKC231665

Contract Title ~ Levenshulme Road, Gorton

Lab No	2494690
Sample ID ~	SS201
Depth ~	
Other ID ~	
Sample Type ~	SOIL
Sampling Date ~	10/04/2025
Sampling Time ~	n/s

Test	Method	LOD	Units	
Ethylbenzene	DETSC 3321#	0.01	mg/kg	< 0.01
Toluene	DETSC 3321#	0.01	mg/kg	< 0.01
Xylene	DETSC 3321#	0.01	mg/kg	< 0.01
m+p Xylene	DETSC 3321#	0.01	mg/kg	< 0.01
o Xylene	DETSC 3321#	0.01	mg/kg	< 0.01
MTBE	DETSC 3321	0.01	mg/kg	< 0.01
PAHs				
Naphthalene	DETSC 3301	0.1	mg/kg	< 0.1
Acenaphthylene	DETSC 3301	0.1	mg/kg	< 0.1
Acenaphthene	DETSC 3301	0.1	mg/kg	< 0.1
Fluorene	DETSC 3301	0.1	mg/kg	< 0.1
Phenanthrene	DETSC 3301	0.1	mg/kg	0.4
Anthracene	DETSC 3301	0.1	mg/kg	0.1
Fluoranthene	DETSC 3301	0.1	mg/kg	1.0
Pyrene	DETSC 3301	0.1	mg/kg	0.8
Benzo(a)anthracene	DETSC 3301	0.1	mg/kg	0.4
Chrysene	DETSC 3301	0.1	mg/kg	0.4
Benzo(b)fluoranthene	DETSC 3301	0.1	mg/kg	0.3
Benzo(k)fluoranthene	DETSC 3301	0.1	mg/kg	0.3
Benzo(a)pyrene	DETSC 3301	0.1	mg/kg	0.3
Indeno(1,2,3-c,d)pyrene	DETSC 3301	0.1	mg/kg	0.3
Dibenzo(a,h)anthracene	DETSC 3301	0.1	mg/kg	< 0.1
Benzo(g,h,i)perylene	DETSC 3301	0.1	mg/kg	0.2
PAH 16 Total	DETSC 3301	1.6	mg/kg	4.7
Phenols				
Phenol - Monohydric	DETSC 2130#	0.3	mg/kg	< 0.3

Summary of Asbestos Analysis Soil Samples

Our Ref 25-08326

Client Ref ~ LKC231665

Contract Title ~ Levenshulme Road, Gorton

Lab No	Sample ID	Material Type	Result	Comment*	Analyst
2494690	SS201	SOIL	NAD	none	Lee Kerridge

Crocidolite = Blue Asbestos, Amosite = Brown Asbestos, Chrysotile = White Asbestos. Anthophyllite, Actinolite and Tremolite are other forms of Asbestos. Samples are analysed by DETSC 1101 using polarised light microscopy in accordance with HSG248 and documented in-house methods. NAD = No Asbestos Detected. Where a sample is NAD, the result is based on analysis of at least 2 sub-samples and should be taken to mean 'no asbestos detected in sample'. Key: * -not included in laboratory scope of accreditation.

Information in Support of the Analytical Results

Our Ref 25-08326
 Client Ref ~ LKC231665
 Contract ~ Levenshulme Road, Gorton

Containers Received & Deviating Samples

Lab No	Sample ID ~	Date	Containers Received	Holding time	Incorrect
		Sampled ~		exceeded for tests	container for tests
2494690	SS201 SOIL	10/04/25	GJ 250ml, GJ 60ml, PT 1L		
Key: G-Glass P-Plastic J-Jar T-Tub Normec DETS cannot be held responsible for the integrity of samples received whereby the laboratory did not undertake the sampling. In this instance samples received may be deviating. Deviating Sample criteria are based on British and International standards and laboratory trials in conjunction with the UKAS note 'Guidance on Deviating Samples'. All samples received are listed above. However, those samples that have additional comments in relation to hold time, inappropriate containers etc are deviating due to the reasons stated. This means that the analysis is accredited where applicable, but results may be compromised due to sample deviations. If no sampled date (soils) or date+time (waters) has been supplied then samples are deviating. However, if you are able to supply a sampled date (and time for waters) this will prevent samples being reported as deviating where specific hold times are not exceeded and where the container supplied is suitable.					

Soil Analysis Notes

Inorganic soil analysis was carried out on a dried sample, crushed to pass a 250µm sieve Organic soil analysis was carried out on an 'as received' sample. Organics results are corrected for moisture and expressed on a dry weight basis. The Loss on Drying, used to express organics analysis on an air dried basis, is carried out at a temperature of 28°C +/-2°C.
--

Disposal

From the issue date of this test certificate, samples will be held for the following times prior to disposal :- Soils - 1 month, Liquids - 2 weeks, Asbestos (test portion) - 6 months

Information in Support of the Analytical Results

List of HWOL Acronyms and Operators

Acronym	Description
HS	Headspace analysis
EH	Extractable Hydrocarbons - i.e. everything extracted by the solvent
CU	Clean-up - e.g. by florisil, silica gel
1D	GC - Single coil gas chromatography
2D	GC-GC - Double coil gas chromatography
Total	Aliphatics & Aromatics
AL	Aliphatics only
AR	Aromatics only
#1	EH_2D_Total but with humics mathematically subtracted
#2	EH_2D_Total but with fatty acids mathematically subtracted
_	Operator - underscore to separate acronyms (exception for +)
+	Operator to indicate cumulative eg. EH+HS_Total or EH_CU+HS_Total

Det	Acronym
Aliphatic C5-C6	HS_1D_AL
Aliphatic C6-C8	HS_1D_AL
Aliphatic C8-C10	HS_1D_AL
Aliphatic >EC10-EC12	EH_2D_AL
Aliphatic >EC12-EC16	EH_2D_AL
Aliphatic >EC16-EC21	EH_2D_AL
Aliphatic >EC21-EC35	EH_2D_AL
Aliphatic >EC35-EC40	EH_2D_AL
Aliphatic >EC40-EC44	EH_2D_AL
Aliphatic C5-C44	EH_2D+HS_1D_AL
Aromatic C5-C7	HS_1D_AR
Aromatic C7-C8	HS_1D_AR
Aromatic C8-C10	HS_1D_AR
Aromatic >EC10-EC12	EH_2D_AR
Aromatic >EC12-EC16	EH_2D_AR
Aromatic >EC16-EC21	EH_2D_AR
Aromatic >EC21-EC35	EH_2D_AR
Aromatic >EC35-EC40	EH_2D_AR
Aromatic >EC40-EC44	EH_2D_AR
Aromatic C5-C44	EH_2D+HS_1D_AR
TPH Ali/Aro C5-C44	EH_2D+HS_1D_Total

Key:

~ Sample details are provided by the client and can affect the validity of the results

* -not accredited.

-MCERTS (accreditation only applies if report carries the MCERTS logo).

\$ -subcontracted.

n/s -not supplied.

I/S -insufficient sample.

U/S -unsuitable sample.

t/f -to follow.

nd -not detected.

End of Report



Rachel Peart
LK Consult Limited
Unit 29 Eton Business Park
Eton Hill Road
Manchester
M26 2ZS

Normec DETS Limited
Unit 1
Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Kent
ME17 2JN
t: 01622 850410

DETS Report No: 25-00779

Site Reference: Levenshulme Road, Gorton

Project / Job Ref: LKC231665

Order No: PO-C000837

Sample Receipt Date: 28/01/2025

Sample Scheduled Date: 28/01/2025

Report Issue Number: 1

Reporting Date: 05/02/2025

Authorised by:

Steve Knight
Customer Support Manager

Dates of laboratory activities for each tested analyte are available upon request.

Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



4480

Soil Analysis Certificate						
DETS Report No: 25-00779	~Date Sampled	23/01/25	23/01/25	23/01/25		
LK Consult Limited	~Time Sampled	None Supplied	None Supplied	None Supplied		
~Site Reference: Levenshulme Road, Gorton	~TP / BH No	SS1a	SS2a	SS3a		
~Project / Job Ref: LKC231665	~Additional Refs	None Supplied	None Supplied	None Supplied		
~Order No: PO-C000837	~Depth (m)	None Supplied	None Supplied	None Supplied		
Reporting Date: 05/02/2025	DETS Sample No	761394	761395	761396		

Determinand	Unit	RL	Accreditation	(n)	(n)	(n)		
Asbestos Screen ^(S)	N/a	N/a	ISO17025	Not Detected	Not Detected	Not Detected		
pH	pH Units	N/a	ISO17025	8.1	8.2	8.0		
Total Cyanide	mg/kg	< 1	NONE	< 1	< 1	< 1		
Free Cyanide	mg/kg	< 1	NONE	< 1	< 1	< 1		
W/S Sulphate as SO ₄ (2:1)	mg/l	< 10	ISO17025	< 10	< 10	< 10		
W/S Sulphate as SO ₄ (2:1)	g/l	< 0.01	ISO17025	< 0.01	< 0.01	< 0.01		
Organic Matter (SOM)	%	< 0.1	ISO17025	1	1	1.1		
Arsenic (As)	mg/kg	< 2	ISO17025	5	5	6		
W/S Boron	mg/kg	< 1	NONE	< 1	< 1	< 1		
Cadmium (Cd)	mg/kg	< 0.2	ISO17025	< 0.2	< 0.2	< 0.2		
Chromium (Cr)	mg/kg	< 2	ISO17025	7	6	7		
Chromium (hexavalent)	mg/kg	< 2	NONE	< 2	< 2	< 2		
Copper (Cu)	mg/kg	< 4	ISO17025	12	10	13		
Lead (Pb)	mg/kg	< 3	ISO17025	18	14	21		
Mercury (Hg)	mg/kg	< 1	ISO17025	< 1	< 1	< 1		
Nickel (Ni)	mg/kg	< 3	ISO17025	7	6	7		
Selenium (Se)	mg/kg	< 2	ISO17025	< 2	< 2	< 2		
Vanadium (V)	mg/kg	< 1	ISO17025	9	8	11		
Zinc (Zn)	mg/kg	< 3	ISO17025	25	21	27		
Total Phenols (monohydric)	mg/kg	< 2	NONE	< 2	< 2	< 2		

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Method Description page describes if the test is performed on the dried or as-received portion

Subcontracted analysis (S)

~Sample details provided by customer and can affect the validity of results

(n) Please note we are only MCERTS accredited (UK soils only) for sand, loam and clay and any other matrix is outside our scope of accreditation

Subcontracted analysis (S)



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - Speciated PAHs						
DETS Report No: 25-00779	~Date Sampled	23/01/25	23/01/25	23/01/25		
LK Consult Limited	~Time Sampled	None Supplied	None Supplied	None Supplied		
~Site Reference: Levenshulme Road, Gorton	~TP / BH No	SS1a	SS2a	SS3a		
~Project / Job Ref: LKC231665	~Additional Refs	None Supplied	None Supplied	None Supplied		
~Order No: PO-C000837	~Depth (m)	None Supplied	None Supplied	None Supplied		
Reporting Date: 05/02/2025	DETS Sample No	761394	761395	761396		

Determinand	Unit	RL	Accreditation	(n)	(n)	(n)		
Naphthalene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Acenaphthylene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Acenaphthene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Fluorene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Phenanthrene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Anthracene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Fluoranthene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Pyrene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Benzo(a)anthracene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Chrysene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Benzo(b)fluoranthene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Benzo(k)fluoranthene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Benzo(a)pyrene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Indeno(1,2,3-cd)pyrene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Dibenz(a,h)anthracene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Benzo(ghi)perylene	mg/kg	< 0.1	ISO17025	< 0.1	< 0.1	< 0.1		
Total EPA-16 PAHs	mg/kg	< 1.6	ISO17025	< 1.6	< 1.6	< 1.6		

~Sample details provided by customer and can affect the validity of results

(n) Please note we are only MCERTS accredited (UK soils only) for sand, loam and clay and any other matrix is outside our scope of accreditation



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - TPH CWG Banded

DETS Report No: 25-00779	~Date Sampled	23/01/25	23/01/25	23/01/25		
LK Consult Limited	~Time Sampled	None Supplied	None Supplied	None Supplied		
~Site Reference: Levenshulme Road, Gorton	~TP / BH No	SS1a	SS2a	SS3a		
~Project / Job Ref: LKC231665	~Additional Refs	None Supplied	None Supplied	None Supplied		
~Order No: PO-C000837	~Depth (m)	None Supplied	None Supplied	None Supplied		
Reporting Date: 05/02/2025	DETS Sample No	761394	761395	761396		

Determinand	Unit	RL	Accreditation	(n)	(n)	(n)		
Aliphatic >C5 - C6 : HS_1D_MS_AL	mg/kg	< 0.01	NONE	< 0.01	< 0.01	< 0.01		
Aliphatic >C6 - C8 : HS_1D_MS_AL	mg/kg	< 0.05	NONE	< 0.05	< 0.05	< 0.05		
Aliphatic >C8 - C10 : EH_CU_1D_AL	mg/kg	< 2	ISO17025	< 2	< 2	< 2		
Aliphatic >C10 - C12 : EH_CU_1D_AL	mg/kg	< 2	ISO17025	< 2	< 2	< 2		
Aliphatic >C12 - C16 : EH_CU_1D_AL	mg/kg	< 3	ISO17025	< 3	< 3	< 3		
Aliphatic >C16 - C21 : EH_CU_1D_AL	mg/kg	< 3	ISO17025	< 3	< 3	< 3		
Aliphatic >C21 - C34 : EH_CU_1D_AL	mg/kg	< 10	ISO17025	< 10	< 10	< 10		
Aliphatic >C34 - C44 : EH_CU_1D_AL	mg/kg	< 10	NONE	< 10	< 10	< 10		
Aliphatic (C5 - C44) : HS_1D_MS+EH_CU_1D_AL	mg/kg	< 21	NONE	< 21	< 21	< 21		
Aromatic >C5 - C7 : HS_1D_MS_AR	mg/kg	< 0.01	NONE	< 0.01	< 0.01	< 0.01		
Aromatic >C7 - C8 : HS_1D_MS_AR	mg/kg	< 0.05	NONE	< 0.05	< 0.05	< 0.05		
Aromatic >C8 - C10 : EH_CU_1D_AR	mg/kg	< 2	ISO17025	< 2	< 2	< 2		
Aromatic >C10 - C12 : EH_CU_1D_AR	mg/kg	< 2	ISO17025	< 2	< 2	< 2		
Aromatic >C12 - C16 : EH_CU_1D_AR	mg/kg	< 2	ISO17025	< 2	< 2	< 2		
Aromatic >C16 - C21 : EH_CU_1D_AR	mg/kg	< 3	ISO17025	< 3	< 3	< 3		
Aromatic >C21 - C35 : EH_CU_1D_AR	mg/kg	< 10	ISO17025	< 10	< 10	< 10		
Aromatic >C35 - C44 : EH_CU_1D_AR	mg/kg	< 10	NONE	< 10	< 10	< 10		
Aromatic (C5 - C44) : HS_1D_MS+EH_CU_1D_AR	mg/kg	< 21	NONE	< 21	< 21	< 21		
Total >C5 - C44 : HS_1D_MS+EH_CU_1D_Tot al	mg/kg	< 42	NONE	< 42	< 42	< 42		

~Sample details provided by customer and can affect the validity of results

(n) Please note we are only MCERTS accredited (UK soils only) for sand, loam and clay and any other matrix is outside our scope of accreditation



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - BTEX / MTBE						
DETS Report No: 25-00779	~Date Sampled	23/01/25	23/01/25	23/01/25		
LK Consult Limited	~Time Sampled	None Supplied	None Supplied	None Supplied		
~Site Reference: Levenshulme Road, Gorton	~TP / BH No	SS1a	SS2a	SS3a		
~Project / Job Ref: LKC231665	~Additional Refs	None Supplied	None Supplied	None Supplied		
~Order No: PO-C000837	~Depth (m)	None Supplied	None Supplied	None Supplied		
Reporting Date: 05/02/2025	DETS Sample No	761394	761395	761396		

Determinand	Unit	RL	Accreditation	(n)	(n)	(n)		
Benzene : HS_1D_MS	µg/kg	< 2	ISO17025	< 2	< 2	< 2		
Toluene : HS_1D_MS	µg/kg	< 5	ISO17025	< 5	< 5	< 5		
Ethylbenzene : HS_1D_MS	µg/kg	< 2	ISO17025	< 2	< 2	< 2		
p & m-xylene : HS_1D_MS	µg/kg	< 2	ISO17025	< 2	< 2	< 2		
o-xylene : HS_1D_MS	µg/kg	< 2	ISO17025	< 2	< 2	< 2		
MTBE : HS_1D_MS	µg/kg	< 5	ISO17025	< 5	< 5	< 5		

~Sample details provided by customer and can affect the validity of results

(n) Please note we are only MCERTS accredited (UK soils only) for sand, loam and clay and any other matrix is outside our scope of accreditation



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - Sample Descriptions

DETS Report No: 25-00779

LK Consult Limited

~Site Reference: Levenshulme Road, Gorton

~Project / Job Ref: LKC231665

~Order No: PO-C000837

Reporting Date: 05/02/2025

DETS Sample No	~TP / BH No	~Additional Refs	~Depth (m)	Moisture Content (%)	Sample Matrix Description
761394	SS1a	None Supplied	None Supplied	10.4	Light brown sand with stones
761395	SS2a	None Supplied	None Supplied	9.9	Light brown sand with stones
761396	SS3a	None Supplied	None Supplied	9.4	Light brown sand with stones

Moisture content is part of procedure E003 & is not an accredited test

Insufficient Sample ^{U/S}

Unsuitable Sample ^{U/S}

~Sample details provided by customer and can affect the validity of results



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - Methodology & Miscellaneous Information

DETS Report No: 25-00779

LK Consult Limited

~Site Reference: Levenshulme Road, Gorton

~Project / Job Ref: LKC231665

~Order No: PO-C000837

Reporting Date: 05/02/2025

Matrix	Analysed On	Determinand	Brief Method Description	Method No
Soil	D	Boron - Water Soluble	Determination of water soluble boron in soil by 2:1 hot water extract followed by ICP-OES	E012
Soil	AR	BTEX	Determination of BTEX by headspace GC-MS	E001
Soil	D	Cations	Determination of cations in soil by aqua-regia digestion followed by ICP-OES	E002
Soil	D	Chloride - Water Soluble (2:1)	Determination of chloride by extraction with water & analysed by ion chromatography	E009
Soil	AR	Chromium - Hexavalent	Determination of hexavalent chromium in soil by extraction in water then by acidification, addition of 1,5 diphenylcarbazide followed by colorimetry	E016
Soil	AR	Cyanide - Complex	Determination of complex cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Free	Determination of free cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Total	Determination of total cyanide by distillation followed by colorimetry	E015
Soil	D	Cyclohexane Extractable Matter (CEM)	Gravimetrically determined through extraction with cyclohexane	E011
Soil	AR	Diesel Range Organics (C10 - C24)	Determination of hexane/acetone extractable hydrocarbons by GC-FID	E004
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of saturated calcium sulphate followed by electrometric measurement	E022
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of water followed by electrometric measurement	E023
Soil	D	Elemental Sulphur	Determination of elemental sulphur by solvent extraction followed by GC-MS	E020
Soil	AR	EPH (C10 - C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH Product ID	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH TEXAS (C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID for C8 to C40. C6 to C8 by headspace GC-MS	E004
Soil	D	Fluoride - Water Soluble	Determination of Fluoride by extraction with water & analysed by ion chromatography	E009
Soil	D	Fraction Organic Carbon (FOC)	Determination of TOC by combustion analyser.	E027
Soil	D	Organic Matter (SOM)	Determination of TOC by combustion analyser.	E027
Soil	D	TOC (Total Organic Carbon)	Determination of TOC by combustion analyser.	E027
Soil	AR	Exchangeable Ammonium	Determination of ammonium by discrete analyser.	E029
Soil	D	FOC (Fraction Organic Carbon)	Determination of fraction of organic carbon by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	D	Loss on Ignition @ 450oC	Determination of loss on ignition in soil by gravimetrically with the sample being ignited in a muffle furnace	E019
Soil	D	Magnesium - Water Soluble	Determination of water soluble magnesium by extraction with water followed by ICP-OES	E025
Soil	D	Metals	Determination of metals by aqua-regia digestion followed by ICP-OES	E002
Soil	AR	Mineral Oil (C10 - C40)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge	E004
Soil	AR	Moisture Content	Moisture content; determined gravimetrically	E003
Soil	D	Nitrate - Water Soluble (2:1)	Determination of nitrate by extraction with water & analysed by ion chromatography	E009
Soil	D	Organic Matter	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	PAH - Speciated (EPA 16)	Determination of PAH compounds by extraction in acetone and hexane followed by GC-MS with the use of surrogate and internal standards	E005
Soil	AR	PCB - 7 Congeners	Determination of PCB by extraction with acetone and hexane followed by GC-MS	E008
Soil	D	Petroleum Ether Extract (PEE)	Gravimetrically determined through extraction with petroleum ether	E011
Soil	AR	pH	Determination of pH by addition of water followed by electrometric measurement	E007
Soil	AR	Phenols - Total (monohydric)	Determination of phenols by distillation followed by colorimetry	E021
Soil	D	Phosphate - Water Soluble (2:1)	Determination of phosphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Total	Determination of total sulphate by extraction with 10% HCl followed by ICP-OES	E013
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of sulphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of water soluble sulphate by extraction with water followed by ICP-OES	E014
Soil	AR	Sulphide	Determination of sulphide by distillation followed by colorimetry	E018
Soil	D	Sulphur - Total	Determination of total sulphur by extraction with aqua-regia followed by ICP-OES	E024
Soil	AR	SVOC	Determination of semi-volatile organic compounds by extraction in acetone and hexane followed by GC-MS	E006
Soil	AR	Thiocyanate (as SCN)	Determination of thiocyanate by extraction in caustic soda followed by acidification followed by addition of ferric nitrate followed by colorimetry	E017
Soil	D	Toluene Extractable Matter (TEM)	Gravimetrically determined through extraction with toluene	E011
Soil	D	Total Organic Carbon (TOC)	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	TPH CWG (ali: C5- C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C34, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C35. C5 to C8 by headspace GC-MS	E004
Soil	AR	TPH LQM (ali: C5-C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C35, C35-C44, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35, C35-C44)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C44. C5 to C8 by headspace GC-MS	E004
Soil	AR	VOCs	Determination of volatile organic compounds by headspace GC-MS	E001
Soil	AR	VPH (C6-C8 & C8-C10)	Determination of hydrocarbons C6-C8 by headspace GC-MS & C8-C10 by GC-FID	E001

D Dried
AR As Received

~Sample details provided by customer and can affect the validity of results



Normec DETS Limited
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



4480

List of HWOL Acronyms and Operators

DETS Report No: 25-00779

LK Consult Limited

~Site Reference: Levenshulme Road, Gorton

~Project / Job Ref: LKC231665

~Order No: PO-C000837

Reporting Date: 05/02/2025

Acronym	Description
HS	Headspace analysis
EH	Extractable Hydrocarbons - i.e. everything extracted by the solvent
CU	Clean-up - e.g. by florisil, silica gel
1D	GC - Single coil gas chromatography
2D	GC-GC - Double coil gas chromatography
Total	Aliphatics & Aromatics
AL	Aliphatics only
AR	Aromatics only
#1	EH_2D_Total but with humics mathematically subtracted
#2	EH_2D_Total but with fatty acids mathematically subtracted
	Operator - underscore to separate acronyms (exception for +)
+	Operator to indicate cumulative eg. EH+HS_Total or EH_CU+HS_Total
~	Sample details provided by customer and can affect the validity of results

Benzene - HS_1D_MS
Ethylbenzene - HS_1D_MS
MTBE - HS_1D_MS
TPH - Aliphatic >C34 - C44 - raw data - EH_CU_1D_AL
TPH CWG - Aliphatic >C10 - C12 - EH_CU_1D_AL
TPH CWG - Aliphatic >C12 - C16 - EH_CU_1D_AL
TPH CWG - Aliphatic >C16 - C21 - EH_CU_1D_AL
TPH CWG - Aliphatic >C21 - C34 - EH_CU_1D_AL
TPH CWG - Aliphatic >C34 - C44 - EH_CU_1D_AL
TPH CWG - Aliphatic >C5 - C44 - HS_1D_MS+EH_CU_1D_AL
TPH CWG - Aliphatic >C5 - C6 - HS_1D_MS_AL
TPH CWG - Aliphatic >C6 - C8 - HS_1D_MS_AL
TPH CWG - Aliphatic >C8 - C10 - EH_CU_1D_AL
TPH CWG - Aromatic >C10 - C12 - EH_CU_1D_AR
TPH CWG - Aromatic >C12 - C16 - EH_CU_1D_AR
TPH CWG - Aromatic >C16 - C21 - EH_CU_1D_AR
TPH CWG - Aromatic >C21 - C35 - EH_CU_1D_AR
TPH CWG - Aromatic >C35 - C44 - EH_CU_1D_AR
TPH CWG - Aromatic >C5 - C44 - HS_1D_MS+EH_CU_1D_AR
TPH CWG - Aromatic >C5 - C7 - HS_1D_MS_AR
TPH CWG - Aromatic >C7 - C8 - HS_1D_MS_AR
TPH CWG - Aromatic >C8 - C10 - EH_CU_1D_AR
TPH CWG - Total >C5 - C44 - HS_1D_MS+EH_CU_1D_Total
Toluene - HS_1D_MS
m & p-xylene - HS_1D_MS
o-Xylene - HS_1D_MS

Generic Assessment Criteria Values

Contaminant		SOM	Res +	Res -	Allot.	Comm.	POS ^{resi}	POS ^{park}	Source
Metals	Inorganic Arsenic	N/A	37	40	49	640	79	168	DEFRA C4SL
	Beryllium	N/A	1.7	1.7	35	12	2.2	63	LQM S4UL
	Boron	N/A	290	11,000	45	240,000	21,000	46,000	LQM S4UL
	Cadmium	N/A	26	149	4.9	410	220	880	DEFRA C4SL
	Chromium (III)	N/A	910	910	18,000	8,600	1,500	33,000	LQM S4UL
	Chromium (VI)	N/A	21.0	21.0	170.0	49	23.0	250	DEFRA C4SL
	Copper	N/A	2,400	7,100	520	68,000	12,000	44,000	LQM S4UL
	Lead	N/A	200	310	80	2,330	630	1,300	DEFRA C4SL
	Elemental Mercury	N/A	1.2	1.2	21	58 (25.8) ^{vap}	16	30 (25.8) ^{vap}	LQM S4UL
	Inorganic Mercury	N/A	40	56	19	1,100	120	240	LQM S4UL
	Methylmercury	N/A	11	15	6.0	320	40	68	LQM S4UL
	Nickel (2015 update)	N/A	130	180	53	980	230	800	LQM S4UL
	Selenium	N/A	250	430	88	12,000	1,100	1,800	LQM S4UL
	Vanadium	N/A	410	1,200	91	9,000	2,000	5,000	LQM S4UL
Zinc	N/A	3,700	40,000	620	730,000	81,000	170,000	LQM S4UL	
Polycyclic Aromatic Hydrocarbons (PAHs)	Acenaphthene	1%	210	3,000 (57.1) ^{sol}	34	84,000 (57.0) ^{sol}	15,000	29,000	LQM S4UL
		2.5%	510	4,700 (141) ^{sol}	85	97,000 (141) ^{sol}	15,000	30,000	LQM S4UL
		6%	1,100	6,000 (336) ^{sol}	200	100,000	15,000	30,000	LQM S4UL
	Acenaphthylene	1%	170	2,900 (86.1) ^{sol}	28	83,000 (86.1) ^{sol}	15,000	29,000	LQM S4UL
		2.5%	420	4,600 (212) ^{sol}	69	97,000 (212) ^{sol}	15,000	30,000	LQM S4UL
		6%	920	6,000 (506) ^{sol}	160	100,000	15,000	30,000	LQM S4UL
	Anthracene	1%	2,400	31,000 (1.17) ^{vap}	380	520,000	74,000	150,000	LQM S4UL
		2.5%	5,400	35,000	950	540,000	74,000	150,000	LQM S4UL
		6%	11,000	37,000	2,200	540,000	74,000	150,000	LQM S4UL
	Benz(a)anthracene	1%	7.2	11	2.9	170	29	49	LQM S4UL
		2.5%	11	14	6.5	170	29	56	LQM S4UL
		6%	13	15	13	180	29	62	LQM S4UL
	Benzo(a)pyrene (only)	1%	5.0	5.3	5.70	77	10.0	21	DEFRA C4SL
		2.5%	5.0	5.3	5.70	77	10.0	21	DEFRA C4SL
		6%	5.0	5.3	5.70	77	10.0	21	DEFRA C4SL
	Benzo(a)pyrene (surrogate marker Coal Tar)	1%	0.8	1.2	0.32	15	2.2	4	LQM S4UL
		2.5%	1.0	1.2	0.67	15	2.2	5	LQM S4UL
		6%	1.1	1.2	1.20	15	2.2	5	LQM S4UL
	Benzo(b)fluoranthene	1%	2.6	3.9	0.99	44	7.1	13	LQM S4UL
		2.5%	3.3	4.0	2.1	44	7.2	15	LQM S4UL
		6%	3.7	4.0	3.9	45	7.2	16	LQM S4UL
	Benzo(ghi)perylene	1%	320	360	290	3,900	640	1,400	LQM S4UL
		2.5%	340	360	470	4,000	640	1,500	LQM S4UL
		6%	350	360	640	4,000	640	1,600	LQM S4UL
	Benzo(k)fluoranthene	1%	77	110	37	1,200	190	370	LQM S4UL
		2.5%	93	110	75	1,200	190	410	LQM S4UL
		6%	100	110	130	1,200	190	440	LQM S4UL
	Chrysene	1%	15	30	4.1	350	57	93	LQM S4UL
		2.5%	22	31	9.4	350	57	110	LQM S4UL
		6%	27	32	19	350	57	120	LQM S4UL
	Dibenzo(ah)anthracene	1%	0.24	0.31	0.14	3.5	0.57	1.1	LQM S4UL
		2.5%	0.28	0.32	0.27	3.6	0.58	1.3	LQM S4UL
		6%	0.3	0.32	0.43	3.6	0.58	1.4	LQM S4UL
	Fluoranthene	1%	280	1,500	52	23,000	3,100	6,300	LQM S4UL
		2.5%	560	1,600	130	23,000	3,100	6,300	LQM S4UL
		6%	890	1,600	290	23,000	3,100	6,400	LQM S4UL
	Fluorene	1%	170	2,800 (36.0) ^{sol}	27	63,000 (30.9) ^{sol}	9,900	20,000	LQM S4UL
		2.5%	400	3,800 (76.5) ^{sol}	67	68,000	9,900	20,000	LQM S4UL
		6%	860	4,500 (183) ^{sol}	160	71,000	9,900	20,000	LQM S4UL
	Indeno(123-cd)pyrene	1%	27	45	9.5	500	82	150	LQM S4UL
		2.5%	36	46	21	510	82	170	LQM S4UL
		6%	41	46	39	510	82	180	LQM S4UL
	Naphthalene	1%	15	15	65	1,600*	11,000*	8,400*	DEFRA C4SL
		2.5%	36	36	130	3,700*	15,000*	17,00*	DEFRA C4SL
		6%	85	85	200	8,400*	1,200*	1,900*	DEFRA C4SL
	Phenanthrene	1%	95	1,300 (36.0) ^{sol}	15	22,000	3,100	6,200	LQM S4UL
		2.5%	220	1,500	38	22,000	3,100	6,200	LQM S4UL
		6%	440	1,500	90	22,000	3,100	6,300	LQM S4UL
	Pyrene	1%	620	3,700	110	54,000	7,400	15,000	LQM S4UL
		2.5%	1,200	3,800	270	54,000	7,400	15,000	LQM S4UL
		6%	2,000	3,800	620	54,000	7,400	15,000	LQM S4UL
	Coal Tar (B(a)P as surrogate marker)	1%	0.79	1.2	0.32	15	2.2	4.4	LQM S4UL
		2.5%	0.98	1.2	0.67	15	2.2	4.7	LQM S4UL
		6%	1.1	1.2	1.2	15	2.2	4.8	LQM S4UL

Generic Assessment Criteria Values

Contaminant		SOM	Res +	Res -	Allot.	Comm.	POS ^{resi}	POS ^{park}	Source
BTEX Compounds	Benzene	1%	0.87	0.38	0.017	27	72	90	LQM S4UL
		2.5%	0.17	0.70	0.034	47	72	100	LQM S4UL
		6%	0.37	1.4	0.075	90	73	110	LQM S4UL
	Toluene	1%	130	880 (869) ^{vap}	22	56,000 (869) ^{vap}	56,000	87,000 (869) ^{vap}	LQM S4UL
		2.5%	290	1,900	51	110,000 (1,920) ^{vap}	56,000	95,000 (1,920) ^{vap}	LQM S4UL
		6%	660	3,900	120	180,000 (4,360) ^{vap}	56,000	100,000 (4,360)	LQM S4UL
	Ethylbenzene	1%	47	83	16	5,700 (518) ^{vap}	24,000	17,000 (518) ^{vap}	LQM S4UL
		2.5%	110	190	39	13,000 (1,220) ^{vap}	24,000	22,000 (1,220) ^{vap}	LQM S4UL
		6%	260	440	91	27,000 (2,840) ^{vap}	25,000	27,000 (2,840) ^{vap}	LQM S4UL
	o-xylene	1%	60	88	28	6,600 (478) ^{sol}	41,000	17,000 (478) ^{sol}	LQM S4UL
		2.5%	140	210	67	15,000 (1,120) ^{sol}	42,000	24,000 (1,120) ^{sol}	LQM S4UL
		6%	330	480	160	33,000 (2,620) ^{sol}	43,000	33,000 (2,620) ^{sol}	LQM S4UL
	m-xylene	1%	59	82	31	6,200 (625) ^{vap}	41,000	17,000 (625) ^{vap}	LQM S4UL
		2.5%	140	190	74	14,000 (1,470) ^{vap}	42,000	24,000 (1,470) ^{vap}	LQM S4UL
		6%	320	450	170	31,000 (3,460) ^{vap}	43,000	32,000 (3,460) ^{vap}	LQM S4UL
	p-xylene	1%	56	79	29	5,900 (576) ^{sol}	41,000	17,000 (576) ^{sol}	LQM S4UL
		2.5%	130	180	69	14,000 (1,350) ^{sol}	42,000	23,000 (1,350) ^{sol}	LQM S4UL
		6%	310	430	160	30,000 (3,170) ^{sol}	43,000	31,000 (3,170) ^{sol}	LQM S4UL
Aliphatic									
EC 5-6	1%	42	42	730	3,200 (304) ^{sol}	570,000(304) ^{sol}	95,000 (304) ^{sol}	LQM S4UL	
EC>6-8	1%	100	100	2,300	7,800 (144) ^{sol}	600,000	150,000 (144) ^{sol}	LQM S4UL	
EC>8-10	1%	27	27	320	2,000 (78) ^{sol}	13,000	14,000 (78) ^{vap}	LQM S4UL	
EC>10-12	1%	130 (48) ^{vap}	130 (48) ^{vap}	2,200	9,700 (48) ^{sol}	13,000	21,000 (48) ^{vap}	LQM S4UL	
EC>12-16	1%	1,100 (24) ^{sol}	1,100 (24) ^{sol}	11,000	59,000 (24) ^{sol}	13,000	25,000 (24) ^{sol}	LQM S4UL	
EC>16-35	1%	65,000 (8.48)	65,000 (8.48) ^{f, sol}	260,000 ^f	160,000 ^f	250,000 ^f	450,000 ^f	LQM S4UL	
EC>35-44	1%	65,000 (8.48)	65,000 (8.48) ^{f, sol}	260,000 ^f	160,000 ^f	250,000 ^f	450,000 ^f	LQM S4UL	
Aliphatic									
EC 5-6	2.5%	78	78	1,700	5,900 (558) ^{sol}	590,000	130,000 (558) ^{sol}	LQM S4UL	
EC>6-8	2.5%	230	230	5,600	17,000 (322) ^{sol}	610,000	220,000 (322) ^{sol}	LQM S4UL	
EC>8-10	2.5%	65	65	770	4,800 (190) ^{vap}	13,000	18,000 (190) ^{vap}	LQM S4UL	
EC>10-12	2.5%	330 (118) ^{vap}	330 (118) ^{vap}	4,400	23,000 (118) ^{vap}	13,000	23,000 (118) ^{vap}	LQM S4UL	
EC>12-16	2.5%	2,400 (59) ^{sol}	2,400 (59) ^{sol}	13,000	82,000 (59) ^{sol}	13,000	25,000 (59) ^{sol}	LQM S4UL	
EC>16-35	2.5%	92,000 (21)	92,000 (21) ^{f, sol}	270,000 ^f	1,700,000 ^f	250,000 ^f	480,000 ^f	LQM S4UL	
EC>35-44	2.5%	92,000 (21)	92,000 (21) ^{f, sol}	270,000 ^f	1,700,000 ^f	250,000 ^f	480,000 ^f	LQM S4UL	
Aliphatic									
EC 5-6	6%	160	160	3,900	12,000 (1,150) ^{sol}	600,000	180,000 (1,150)	LQM S4UL	
EC>6-8	6%	530	530	13,000	40,000 (736) ^{sol}	620,000	320,000 (736) ^{sol}	LQM S4UL	
EC>8-10	6%	150	150	1,700	11,000 (451) ^{vap}	13,000	21,000 (451) ^{vap}	LQM S4UL	
EC>10-12	6%	760 (283) ^{vap}	760 (283) ^{vap}	7,300	47,000 (283) ^{vap}	13,000	24,000 (283) ^{vap}	LQM S4UL	
EC>12-16	6%	4,300 (142) ^{sol}	4,400 (142) ^{sol}	13,000	90,000 (142) ^{sol}	13,000	26,000 (142) ^{sol}	LQM S4UL	
EC>16-35	6%	110,000 ^f	110,000 ^f	270,000 ^f	1,800,000 ^f	250,000 ^f	490,000 ^f	LQM S4UL	
EC>35-44	6%	110,000 ^f	110,000 ^f	270,000 ^f	1,800,000 ^f	250,000 ^f	490,000 ^f	LQM S4UL	
Aromatic									
EC5-7(benzene as non-	1%	70	370	13	26,000 (1,220) ^{sol}	56,000	76,000 (1,220) ^{sol}	LQM S4UL	
EC>7-8(toluene)	1%	130	860	22	56,000 (869) ^{vap}	56,000	87,000 (869) ^{vap}	LQM S4UL	
EC>8-10	1%	34	47	8.6	3,500 (613) ^{vap}	5,000	7,200 (613) ^{vap}	LQM S4UL	
EC>10-12	1%	74	250	13	16,000 (364) ^{sol}	5,000	9,200 (364) ^{sol}	LQM S4UL	
EC>12-16	1%	140	1,800	23	36,000 (169) ^{sol}	5,100	10,000	LQM S4UL	
EC>16-21	1%	260 ^f	1,900 ^f	46 ^f	28,000 ^f	3,800 ^f	7,600 ^f	LQM S4UL	
EC>21-35	1%	1,100 ^f	1,900 ^f	370 ^f	28,000 ^f	3,800 ^f	7,800 ^f	LQM S4UL	
EC>35-44	1%	1,100 ^f	1,900 ^f	370 ^f	28,000 ^f	3,800 ^f	7,800 ^f	LQM S4UL	
Aromatic									
EC5-7(benzene as non-	2.5%	140	690	27	46,000 (2,260) ^{sol}	56,000	84,000 (2,260) ^{sol}	LQM S4UL	
EC>7-8(toluene)	2.5%	290	1,800	51	110,000 (1,920) ^{sol}	56,000	95,000 (1,920) ^{sol}	LQM S4UL	
EC>8-10	2.5%	83	110	21	8,100 (1,500) ^{vap}	5,000	8,500 (1,500) ^{vap}	LQM S4UL	
EC>10-12	2.5%	180	590	31	28,000 (899) ^{sol}	5,000	9,700 (899) ^{sol}	LQM S4UL	
EC>12-16	2.5%	330	2,300 (419) ^{sol}	57	37,000	5,100	10,000	LQM S4UL	
EC>16-21	2.5%	540 ^f	1,900 ^f	110 ^f	28,000 ^f	3,800 ^f	7,700 ^f	LQM S4UL	
EC>21-35	2.5%	1,500 ^f	1,900 ^f	820 ^f	28,000 ^f	3,800 ^f	7,800 ^f	LQM S4UL	
EC>35-44	2.5%	1,500 ^f	1,900 ^f	820 ^f	28,000 ^f	3,800 ^f	7,800 ^f	LQM S4UL	
Aromatic									
EC5-7(benzene as non-	6%	300	1,400	57	86,000 (4,710) ^{sol}	56,000	92,000 (4,710) ^{sol}	LQM S4UL	
EC>7-8(toluene)	6%	660	3,900	120	180,000 (4,360) ^{vap}	56,000	100,000 (4,360)	LQM S4UL	
EC>8-10	6%	190	270	51	17,000 (3,580) ^{vap}	5,000	9,300 (3,580) ^{vap}	LQM S4UL	
EC>10-12	6%	380	1,200	4	34,000 (2,150) ^{sol}	5,000	10,000	LQM S4UL	
EC>12-16	6%	660	2,500	130	38,000	5,100	10,000	LQM S4UL	
EC>16-21	6%	930 ^f	1,900 ^f	260 ^f	28,000 ^f	3,800 ^f	7,800 ^f	LQM S4UL	
EC>21-35	6%	1,700 ^f	1,900 ^f	1,600 ^f	28,000 ^f	3,800 ^f	7,900 ^f	LQM S4UL	
EC>35-44	6%	1,700 ^f	1,900 ^f	1,600 ^f	28,000 ^f	3,800 ^f	7,900 ^f	LQM S4UL	
Aliphatic +Aromatic >EC44	1%	1,600 ^f	1,900 ^f	1,200 ^f	28,000 ^f	3,800 ^f	7,800 ^f	LQM S4UL	
	2.5%	1,800 ^f	1,900 ^f	2,100 ^f	28,000 ^f	3,800 ^f	7,800 ^f	LQM S4UL	
	6%	1,900 ^f	1,900 ^f	3,000 ^f	28,000 ^f	3,800 ^f	7,900 ^f	LQM S4UL	

Generic Assessment Criteria Values

Contaminant		SOM	Res +	Res -	Allot.	Comm.	POS ^{res} i	POS ^{park}	Source
Chloroalkanes and Alkenes & Explosives	1,2 Dichloroethane (DCA)	1%	0.0071	0.0092	0.0046	0.67	29	21	LQM S4UL
		2.5%	0.0110	0.0130	0.0083	0.97	29	24	LQM S4UL
		6%	0.0190	0.0230	0.0160	1.7	29	28	LQM S4UL
	1,1,1 Trichloroethane (TCA)	1%	8.8	9.0	48	660	140,000	57,000 (1,425) ^{vap}	LQM S4UL
		2.5%	18	18	110	1,300	140,000	76,000 (2,915) ^{vap}	LQM S4UL
		6%	39	40	240	3,000	140,000	100,000 (6,392)	LQM S4UL
	1,1,2,2-Tetrachloroethanes (PCA)	1%	1.6	3.9	0.41	270	1,400	1,800	LQM S4UL
		2.5%	3.4	8.0	0.89	550	1,400	2,100	LQM S4UL
		6%	7.5	17	2.0	1,100	1,400	2,300	LQM S4UL
	1,1,1,2-Tetrachloroethanes (PCA)	1%	1.2	1.5	0.79	110	1,400	1,500	LQM S4UL
		2.5%	2.8	3.5	1.9	250	1,400	1,800	LQM S4UL
		6%	6.4	8.2	4.4	560	1,400	2,100	LQM S4UL
	Tetrachloroethene (PCE)	1%	0.31	0.32	2.00	24	3,200	1400	DEFRA C4SL
		2.5%	0.70	0.71	4.8	55	3,300	1900	DEFRA C4SL
		6%	1.60	1.60	11.0	130	3,400	2,500	DEFRA C4SL
	Tetrachloromethane (carbon tetrachloride)	1%	0.03	0.03	0.45	2.9	890	190	LQM S4UL
		2.5%	0.06	0.06	1.0	6.3	920	270	LQM S4UL
		6%	0.13	0.13	2.4	14	950	400	LQM S4UL
	Trichloroethene (TCE)	1%	0.009	0.010	0.032	0.7	76.0	41.0	DEFRA C4SL
		2.5%	0.020	0.020	0.072	1.5	78.0	51.0	DEFRA C4SL
		6%	0.043	0.045	0.160	3.4	79.0	69.0	DEFRA C4SL
	cis 1,2-dichloroethene	1%	0.46	0.50	0.890	38	3,800	2,000	DEFRA C4SL
		2.5%	0.78	0.84	1.70	64	3,800	2,400	DEFRA C4SL
		6%	1.50	1.60	3.60	120	3,900	3,100	DEFRA C4SL
	Trichloromethane (chloroform)	1%	0.91	1.2	0.42	99	2,500	2,600	LQM S4UL
		2.5%	1.7	2.1	0.83	170	2,500	2,800	LQM S4UL
		6%	3.4	4.2	1.7	350	2,500	3,100	LQM S4UL
	Trans-1,2 Dichloroethene	1%	0.9	0.9	3.7	69	13,000	5,600	DEFRA C4SL
		2.5%	1.6	1.7	7.5	120	13,000	7,000	DEFRA C4SL
		6%	3.3	3.4	16.0	260	13,000	9,100	DEFRA C4SL
	Chloroethene (vinyl chloride)	1%	0.006	0.015	0.0017	1.1E+00	7.8	18.0	DEFRA C4SL
		2.5%	0.010	0.019	0.0031	1.4E+00	7.8	19.0	DEFRA C4SL
		6%	0.017	0.029	0.0058	2.20	7.8	19.0	DEFRA C4SL
	2,4,6-Trinitrotoluene (TNT)	1%	1.6	65	0.24	1,000	130	260	LQM S4UL
		2.5%	3.7	66	0.58	1,000	130	270	LQM S4UL
		6%	8.1	66	1.4	1,000	130	270	LQM S4UL
	RDX	1%	120	13,000	17	210,000	26,000	49,000 (18.7) ^{sol}	LQM S4UL
		2.5%	250	13,000	38	210,000	26,000	51,000	LQM S4UL
		6%	540	13,000	85	210,000	27,000	53,000	LQM S4UL
	HMX	1%	5.7	6,700	0.86	110,000	13,000	23,000 (0.35) ^{vap}	LQM S4UL
		2.5%	13	6,700	1.9	110,000	13,000	23,000 (0.39) ^{vap}	LQM S4UL
		6%	26	6,700	3.9	110,000	13,000	24,000 (0.48) ^{vap}	LQM S4UL
Pesticides	Aldrin	1%	5.7	7.3	3.2	170	18	30	LQM S4UL
		2.5%	6.6	7.4	6.1	170	18	31	LQM S4UL
		6%	7.1	7.5	9.8	170	18	31	LQM S4UL
	Dieldrin	1%	0.97	7.0	0.17	170	18	30	LQM S4UL
		2.5%	2.0	7.3	0.41	170	18	30	LQM S4UL
		6%	3.5	7.4	0.96	170	18	31	LQM S4UL
	Atrazine	1%	3.3	610	0.5	9,300	1,200	2,300	LQM S4UL
		2.5%	7.8	620	1.2	9,400	1,200	2,400	LQM S4UL
		6%	17.4	620	2.7	9,400	1,200	2,400	LQM S4UL
	Dichlorvos	1%	3.2E-02	6.4	4.9E-03	140	16	26	LQM S4UL
		2.5%	6.6E-02	6.5	1.0E-02	140	16	26	LQM S4UL
		6%	0.14	6.6	2.2E-02	140	16	27	LQM S4UL
	Endosulfans (2 isomers)	1%	7.4	160 (3.0E-03) ^{vap}	1.2	5,600 (3.0E-03) ^{vap}	1,200	2,300	LQM S4UL
		2.5%	18	280 (7.0E-03) ^{vap}	2.9	7,400 (7.0E-03) ^{vap}	1,200	2,400	LQM S4UL
		6%	41	410 (1.6E-02) ^{vap}	6.8	8,400 (1.6E-02) ^{vap}	1,200	2,500	LQM S4UL
	Hexachlorocyclohexane (3 isomers), inc Lindane	1%	8.5E-02	3.7	1.3E-02	65	8.1	15	LQM S4UL
		2.5%	0.2	3.8	3.2E-02	65	8.1	15	LQM S4UL
		6%	0.46	3.8	7.7E-02	65	8.1	16	LQM S4UL
Chlorobenzenes	Chlorobenzene	1%	0.46	0.46	5.9	56	11,000	1,300 (675) ^{sol}	LQM S4UL
		2.5%	1.0	1.0	14	130	13,000	2,000 (1,520) ^{sol}	LQM S4UL
		6%	2.4	2.4	32	290	14,000	2,900	LQM S4UL
	Dichlorobenzenes (3 isomers)	1%	23	24	94	2,000 (571) ^{sol}	90,000	24,000 (571) ^{sol}	LQM S4UL
		2.5%	55	57	230	4,800 (1,370) ^{sol}	95,000	36,000 (1,370) ^{sol}	LQM S4UL
		6%	130	130	540	11,000 (3,240) ^{sol}	98,000	51,000 (3,270) ^{sol}	LQM S4UL
	Trichlorobenzenes (3 isomers)	1%	2.6	2.6	55	220	15,000	1,700 (318) ^{vap}	LQM S4UL
		2.5%	6.4	6.4	140	530	17,000	2,600 (786) ^{vap}	LQM S4UL
		6%	15	15	320	1,300	19,000	4,000 (1,880) ^{vap}	LQM S4UL
	Tetrachlorobenzenes (3 isomers)	1%	0.66	0.75	0.38	49 (39.4) ^{vap}	78	110 (39) ^{vap}	LQM S4UL
		2.5%	1.6	1.9	0.90	120 (98.1) ^{vap}	79	120	LQM S4UL
		6%	3.7	4.3	2.2	240 (235) ^{vap}	79	130	LQM S4UL
	Pentachlorobenzene	1%	5.8	19	1.2	640 (43.0) ^{sol}	100	190	LQM S4UL
		2.5%	12	30	3.1	770 (107) ^{sol}	100	190	LQM S4UL
		6%	22	38	7.0	830	100	190	LQM S4UL
	Hexachlorobenzene	1%	1.8 (0.20) ^{vap}	4.1 (0.20) ^{vap}	0.47	110 (0.20) ^{vap}	16	30	LQM S4UL
		2.5%	3.3 (0.50) ^{vap}	5.7 (0.50) ^{vap}	1.1	120	16	30	LQM S4UL
		6%	4.9	6.7 (1.2) ^{vap}	2.5	120	16	30	LQM S4UL

Generic Assessment Criteria Values

Contaminant		SOM	Res +	Res -	Allot.	Comm.	POSresi	POSpark	Source
Chlorophenol	Chlorophenols (4 congeners)	1%	0.87 ^g	94	0.13 ^g	3,500	620	1,100	LQM S4UL
		2.5%	2.0	150	0.30	4,000	620	1,100	LQM S4UL
		6%	4.5	210	0.70	4,300	620	1,100	LQM S4UL
	Pentachlorophenol	1%	0.22	27 (16.4) ^{vap}	3.0E-02	400	60	110	LQM S4UL
		2.5%	0.52	29	8.0E-02	400	60	120	LQM S4UL
		6%	1.2	31	0.19	400	60	120	LQM S4UL
Others	Carbon Disulphide	1%	0.14	0.14	4.8	11	11,000	1,300	LQM S4UL
		2.5%	0.29	0.29	10	22	11,000	1,900	LQM S4UL
		6%	0.62	0.62	23	47	11,000	2,700	LQM S4UL
	Hexachlorobutadiene	1%	0.29	0.32	0.25	31	25	48	LQM S4UL
		2.5%	0.7	0.78	0.61	66	25	50	LQM S4UL
		6%	1.6	1.8	1.4	120	25	51	LQM S4UL
	Phenol	1%	120	440 (460)	23	440 ^{dir} (26,000)	440 ^{dir} (10,000)	440 ^{dir} (7,600)	LQM S4UL
		2.5%	200	690	42	690 ^{dir} (30,000)	690 ^{dir} (10,000)	690 ^{dir} (8,300)	LQM S4UL
		6%	380	1,200	83	1,300 ^{dir} (34,000)	1,300 ^{dir} (10,000)	1,300 ^{dir} (9,300)	LQM S4UL
sol/vap = solubility/vapour limit (potentially use if free product identified, although highly conservative)									
* = naphthalene C4SL exceeds the CLEA calculated soil saturation concentration (76 mg kg-1 for 1% SOM, 183 mg kg-1 for 2.5% SOM and 432 mg kg-1 for 6% SOM)									
f = oral, dermal and inhalation exposures compared to oral HCV									
dir = S4ULs based on threshold protective of direct skin contact with phenol)brackets long term exposure for illustration purposes)									
g = derived based on 2,3,4-tetrachlorophenol									