



Plant Schedule

QTY	UNIT	CODE	PLANTNAME	STOCK	FORM	GIRTH/HEIGHT
Trees						
2 No.	ALN	GLU hs	Alnus glutinosa	FB	STD	12-14cm
3 No.	BET	PEN hs12	Betula pendula	FB	STD	12-14cm
2 No.	Pop	Tre hs	Populus tremula	B	STD	12-14cm
2 No.	SORA	Chs	Sorbus aucuparia	FB	STD	12-14cm

PERCENT	QTY	UNIT	PLANTNAME	STOCK	SIZE
---------	-----	------	-----------	-------	------

Plant Mixes

519m2 NATIVE SCRUB MIX 2 planted @ 2/m2						
15%	156	No.	Corylus avellana	B Trans	60-80cm	
15%	156	No.	Crataegus monogyna	B Trans	60-80cm	
15%	156	No.	Prunus spinosa	B Trans	60-80cm	
15%	156	No.	Sambucus nigra	B Trans	60-80cm	
10%	104	No.	Rhamnus cathartica	B Trans	60-80cm	
10%	104	No.	Rosa canina	B Trans	60-80cm	
10%	104	No.	Salix lanтана	C2L	20-30cm	
5%	52	No.	Lonicera periclymenum	C2L	20-30cm	
5%	52	No.	Rubus fruticosus	C2L	20-30cm	

Individual varieties to be planted in groups of approximately 3-5.

Notes and Abbreviations

- B = Bare root (bagged).
- C = Container (or pot) grown, followed by size of the container (or pot).
- FORM = Shape of tree as supplied by the nursery.
- QTY = Quantity
- FB = Rootballed (balled and wrapped).
- Std = (clear stem) Standard.
- STOCK = Root condition/protection method eg Bare root.
- Trans = Transplant (or undercut seedling).
- Refer to specification for further information.
- All plants to be completely hardened off
- Substitutions to be agreed with Landscape Architect.

Do not scale this drawing (printed or electronic version).
Contractors must check all dimensions from site.
This drawing is copyright and is for use on this site only. This drawing should be read in conjunction with all relevant consultants drawings and specialist subcontractors / supply chain drawings and specifications.
All works to be carried out in accordance with the latest British Standards / Codes of Practice unless specifically directed otherwise in the specification.
Responsibility for the reproduction of this drawing in paper form, or issued in electronic format, lies with the recipient to check that all information has been replicated in full and is correct when compared to the original paper or electronic image.
Graphical representations of equipment on this drawing have been co-ordinated, but are approximations only. Please refer to the specifications and / or details for actual sizes and / or specific contractor construction information.

Notes:-

KEY

Hard Works

- Service Yard Mesh Reinforced Concrete**
Light brush finish.
To engineer specification & recommendation
- Vehicular Tarmac**
Black colour.
To engineer specification & recommendation
- Pedestrian Tarmac**
Black colour.
To engineer specification & recommendation
- Pedestrian Concrete Block Pavers**
Light grey colour.
To engineer specification & recommendation
- Car Park Concrete Block Pavers**
Charcoal colour.
To engineer specification & recommendation
- Proposed 2.4m Paladin Fence**
Including matching gates as required
Colour: Black
- Proposed 2.4m Paladin Fence**
Including matching gates as required
Colour: RAL 5002
- Retaining Wall**
To engineer specification & recommendation
- Existing 2.4m Palisade Fence**
Including matching gates as required

Soft Works

- Proposed Tree**
Refer to planting schedule.
- Existing Native Shrub Mix**
To be retained and improve.
- Proposed Native Shrub Planting**
- Easement**

P12	29/04/25	UPDATED	IG	SA
P11	15/10/24	UPDATED	RS	SA
P10	10/10/24	UPDATED	RS	SA
P09	10/10/24	UPDATED	RS	SA
P08	07/10/24	UPDATED	IG	SA
P07	13/09/24	UPDATED	IG	SA
P06	03/04/24	UPDATED	TH	SA
P05	19/12/23	UPDATED	TH	SA
P04	14/12/23	UPDATED	TH	SA
P03	11/12/23	UPDATED	TH	SA
REV.	DATE	DESCRIPTION	DRAWN	CHK'D



A: Ground Floor, The Tower,
Deva City Office Park, Trinity Way,
Manchester M3 7BF
T: +44 (0) 161 312 3131
weareurbangreen.co.uk

Client:	Chancery Gate		
Project:	Former Walkers Site,Crabtree Lane		
Title:	GENERAL ARRANGEMENT PLAN		
Issue:	PLANNING		
Drawn:	TH	Checked:	SA
Approved:	MT		
Project:	UG2066	Scale @ A1:	1:250
Date:	29/11/23		
Dwg No:	UG_2066_LAN_GA_DRW_01	Revision:	P12