



EXTERNAL


WALLS




- 1NO. LAYER 12.5MM GYPSUM PLASTERBOARD WITH 10MM DOT AND DAB LAYER
  - 100MM BLOCKWORK MEDIUM DENSITY (K-VALUE=0.42 W/MK) - EXACT SPECIFICATION TO BE AGREED WITH ALL PARTIES AT STAGE 4
  - 175MM ROCKWOOL INSULATION FULL FILL
  - BLOCKWORK MEDIUM DENSITY (K-VALUE=0.42 W/MK) - EXACT SPECIFICATION TO BE AGREED WITH ALL PARTIES AT STAGE 4
  - CLAD-LINE CL4 FRAMING SYSTEM (25MM RANGE) (70 SPECIALIST DESIGN AND DETAILS)
  - W-1540 15MM WELTEC GROUP W CORRUGATED PROFILE SHEETS PPC
- NOTE**
- BUILD UP CALCULATED USING ROCKWOOL U-VALUE CALCULATOR TO ACHIEVE 0.18W/M2K (MIN). BRICKWORK SUBSTITUTED WITH 100MM BLOCKWORK - ELEMENT SUSTAINABILITY CONFIRMED ACCEPTANCE OF APPROACH AT STAGE 3
  - TFQM CONFIRMED INCREASED WALL DEPTH FACILITATED BY REDUCING 3M ZONE IN CORRESPONDENCE 01/03/23
  - LOW LEVEL OF WALL TO BE BLACK BRICK WITH BLACK MORTAR (FINISH TBC)




- 1NO. LAYER 12.5MM GYPSUM PLASTERBOARD WITH 10MM DOT AND DAB LAYER GYPSUM BASED BOARD MINIMUM 8 kg/m2
- 100MM INNERLEAF BLOCKWORK DENSITY 1350 TO 1600 kg/m3
- WALL TIES TO FOLLOW APPROVED DOCUMENT E
- 75MM COVER TO PARTY WALL ROLL
- 100MM INNERLEAF BLOCKWORK DENSITY 1350 TO 1600 kg/m3
- 1NO. LAYER 12.5MM GYPSUM PLASTERBOARD WITH 10MM DOT AND DAB LAYER GYPSUM BASED BOARD MINIMUM 8 kg/m2



- W-1540 15MM WELTEC GROUP W CORRUGATED PROFILE SHEETS PPC
- CLAD-LINE CL4 FRAMING SYSTEM (25MM RANGE)
- 100MM INNERLEAF BLOCKWORK
- 127.5MM AIR GAP
- 100MM INNERLEAF BLOCKWORK
- CLAD-LINE CL4 FRAMING SYSTEM (25MM RANGE)
- W-1540 15MM WELTEC GROUP W CORRUGATED PROFILE SHEETS PPC



- STANDARD PARTITION**
- BRITISH GYSPUM A206003 (EN) 206003 & MR1 (EN) - ALL WET AREAS (BATHROOMS AND LAUNDRY ROOMS)
- 2 LAYERS 12.5MM GYPSUM WALL BOARD
  - 48 S 50 °C GYPFRAME STUDS
  - 1 LAYERS 12.5MM GYPSUM WALL BOARD
- NB: ADDITIONAL ACOUSTIC INSULATION TO BATHROOMS AND SENSITIVE AREAS TO BE CONFIRMED BY ACOUSTICIAN
- FIRE RATING: 30EI  
SOUND INSULATION: (AIRBORNE) (dB): 42  
DUTY RATING: MEDIUM  
PARTITION THICKNESS: 100mm  
MAXIMUM HEIGHT 3.4m




- SHAFT WALL (ACCOMMODATION PODS)**
- BRITISH GYSPUM A306002 (B/MR1) (EN)
- 2 LAYERS 12.5MM GYPSUM FIRELINE PLASTERBOARD - MR TO OUTER FACE
  - 60MM 170 ° STUDS
  - 19MM GYPROC COREBOARD
- SERVICING STRATEGY REQUIRES CONFIRMATION TO DETERMINE PERFORMANCE REQUIREMENTS - MEP / FIRE ENGINEER COMMENT REQUIRED**
- FIRE RATING: 60EI  
SOUND INSULATION: (AIRBORNE) (dB): 40  
DUTY RATING: SEVERE  
PARTITION THICKNESS: 87  
MAXIMUM HEIGHT 4.4m

PARTY

NIB WALLS

PARTITIONS


FLOORS



- SINGLE PLY MEMBRANE LAYER
  - 220MM ROCKWOOL INSULATION (TO GIVE NOTED U VALUE)
  - VAPOUR CONTROL LAYER LAID ON TOP 18MM WBP PLY
  - TIMBER FIRRING LAYER TO ACCOMMODATE ROOF SLOPE @ 1:10 (25MM)
  - 50X175 C24 TIMBER JOISTS @ 6000C
  - 80MM MF CEILING FRAME
  - 50 MM ISOVER INSULATION ROLL LAID ON TOP OF CEILING BOARD
  - TWO LAYERS 15 MM GYPROC SOUNDBLOC BOARD
- ACOUSTICS REPORT BY CUNDALL TO BE REVIEWED
- ALLOWANCE TO BE MADE FOR ALUMINIUM LAY IN GRID PANELS TO VILLAGE HALL KITCHEN AREAS TO FACILITATE ACCESS TO MVHR
- MOISTURE RESISTANT PLASTERBOARD TO BE USED IN ALL WET AREAS (KITCHENS / LAUNDRY / WC)
- ROOF CONSTRUCTION TO ALLOW ACCESS - NO PLANT CURRENTLY UNDERSTOOD TO BE LOCATED AT ROOF LEVEL

ROOF


PARTY



- 18MM T&G FLOORING BOARD
  - 12.5MM GYPSUM BASED BOARD
  - 80MM ACOUSTIC BATTEN JCW 80T
  - MINERAL WOOL QUILT LAID BETWEEN BATTENS 13MM (MIN) 33-36KG/M3 OR 25MM (MIN) 10-36 KG/M3
  - 19MM THICK (11MM MIN) WOOD BASED BOARD, DENSITY 600 KG/M3 (MIN) OR WALKER TIMBER PERFORATED DECK SYSTEM
  - 50X175 C24 TIMBER JOISTS @ 6000C TO SE DESIGN
  - 100MM MINERAL WOOL QUILT INSULATION (OR CELLECTA MICRO 50)
  - 16MM (MIN) METAL RESILIENT CEILING BARS MOUNTED AT RIGHT ANGLES TO THE JOISTS AT 400MM CENTRES
  - 2NO LAYERS OF 15MM GYPSUM-BASED BOARD, COMPOSED
  - MINIMUM 145MM SERVICE VOID CONFIRMED BY CWC
  - 80MM MF CEILING FRAMES
  - TWO LAYERS 15 MM GYPROC FIRELINE BOARD
- ACOUSTICS REPORT BY CUNDALL TO BE REVIEWED
- STRUCTURAL SIZES CONFIRMED BY CURTINS ON 08/12/22

175mm JOIST ZONE SUBJECT TO AGREEMENT WITH BUILDING CONTROL

GROUND



- 75MM SAND CEMENT SCREED
- POLYTHENE SEPARATION LAYER (DASHED PURPLE)
- 150mm CELOTEX INSULATION OR EQUAL APPROVED
- DPM (DASHED GREEN)
- 150MM SUSPENDED GROUND FLOOR SLAB

SUB STRUCTURE TO STRUCTURAL ENGINEER'S DESIGN AND DETAIL

NOTES

- All dimensions and levels are to be checked on site.
- Any discrepancies are to be reported to the architect before any work commences
- This drawing shall not be reproduced without express written permission from AEW.
- Title overlay drawings and ownership boundaries are produced using all reasonable endeavors. AEW cannot be responsible for the accuracy or scale discrepancy of base plans supplied to them.
- All works are to be undertaken in accordance with Building Regulations and the latest British Standards.
- All proprietary materials and products are to be used strictly in accordance with the manufacturers recommendations.

This drawing contains the following model files: -

13095-AEW-XX-XX-M3-A-0002

CDM 2015

Client notified of duties: 06/09/22

Principal Designer: C-CDM Services

Unless noted below, all known hazards have been highlighted on the drawing:

GENERAL NOTES

- SIGNAGE STRATEGY TBA WITH EMBASSY
- RWP'S SHOWN INDICATIVELY - FINAL POSITION AND QUANTITY SUBJECT TO DETAILED REVIEW AND SUB-CONTRACTOR INPUT

TARGET U-VALUES CONFIRMED BY ELEMENT

0.14W/MPK FLOORS  
0.18W/MPK WALLS  
0.16W/MPK ROOF - VERMONT TARGET 0.11W/MPK  
1.4W/MPK WINDOWS  
1.0W/MPK DOORS  
AIR TIGHTNESS 3

ALL VALUES ARE SUBJECT TO REVIEW AND AGREEMENT  
ALL U-VALUES FOLLOW 2021 EDITION OF APPROVED  
DOCUMENT PART L AND TO BE CONFIRMED BY ELEMENT

KEY:

- TILED WALL - FINISH TBC
- PATRESSING
- MANIFESTATION (FINAL SIZE AND STYLE TBC)
- DRAINAGE ROUTES

LEGEND

- WATERPROOF LINE
- AIRTIGHTNESS LINE
- DPM
- POLYTHENE SEPARATION LAYER
- VAPOUR CONTROL LAYER

ALL DETAILS REPRESENT DESIGN INTENT  
TO BE FULLY DETAILED AND COORDINATED WITH SPECIALIST  
SUBCONTRACTOR INPUT

GAS MEMBRANE REQUIREMENT TO BE CONFIRMED BY SE

|     |          |                                                          |          |            |
|-----|----------|----------------------------------------------------------|----------|------------|
| P10 | 28/03/25 | Updates to Party Floor build up                          | JL       | BS         |
| P09 | 07/03/25 | Amendments made to drawings following RFI's received     | JL       | BS         |
| P08 | 29/01/25 | General updates and SVP details amended for buildability | JL       | BS         |
| P07 | 12/12/24 | Updates made to stage 5 following comments               | JL       | BR         |
| P06 | 05/05/24 | Updated Partition Notes added                            | RB       | BR         |
| P05 | 21/09/23 | Stair layout and details updated                         | JL       | BS         |
| P04 | 21/07/23 | Stage 4 Issue                                            | AG       | BS         |
| P03 | 15/03/23 | Stage 3 Issue - External Wall Types Updated              | BS       | BR         |
| P02 | 16/02/23 | Stage 3 Issue - Updated with minor comments              | CM       | BS         |
| P01 | 10/02/23 | Issued for Stage 3                                       | BR       | BS         |
| Rev | Date     | Description                                              | Drawn by | Checked By |

Status Purpose of Issue  
S2 For Information

drawing stage STAGE 5

client

Embassy Village

project

Embassy Village

drawing title

Typical Build-ups

date 10/10/22 drawn BS  
scale @ A1 As indicated checked BR

Rev P10

Dwg No 13095-AEW-B1-XX-DR-A-6001

aew architects  
0161 214 4370  
www.aewarchitects.com  
aew