Trees moved into adopted northern offsite patch



NOTE:

Proposed trees within the RLB
97 clear stem trees
+ **10** multi stems (not counted as acceptable replacements for trees removed)

Proposed trees offsite
Boundary path: **2** clear stem trees Ancoats
Green: **4** trees offsite

Total new trees proposed - **113**

Substitution ratios
Cm, C p 'P', S a 18-20 girth substituted with 25-30 girth at a ratio of 3:1

P av 'P' and B p 20-25 girth substituted with 35-40 girth at a ratio of 3:1

NOTES:
1. DO NOT SCALE FROM THIS DRAWING. ALWAYS WORK TO NOTED DIMENSIONS.
2. ALL SETTING OUT, LEVELS AND DIMENSIONS TO BE CHECKED ON SITE PRIOR TO THE INSTALLATION OF MATERIALS AND ANY DISCREPANCIES ARE TO BE BROUGHT TO THE ATTENTION OF THE CONTRACT ADMINISTRATOR IMMEDIATELY.
3. THIS DRAWING MUST BE READ WITH THE RELEVANT SPECIFICATION DOCUMENTS AND DETAIL DRAWINGS. ANY DISCREPANCIES MUST BROUGHT TO THE ATTENTION OF THE CONTRACT ADMINISTRATOR IMMEDIATELY.
4. THIS DRAWING IS COPYRIGHT PROTECTED AND MAY NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN AUTHORITY.
5. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE STATED.

THIS DRAWING WAS PLOTTED ON:
06/11/2024

REVISION HISTORY

DATE	REV	ZONE	DESCRIPTION	CHK
16/08/2024	P09		Comments from Wates	AD
16/09/2024	P10		Issued for stage approval	AD
05/11/2024	C04		CONSTRUCTION ISSUE	OK

GENERAL INFORMATION

Application Site Boundary

SOFTWORKS

Clear-stem Tree Planting

Multi-stem Tree Planting

ROOT PROTECTION BARRIER
To Gas Main
GreenBlue Urban ReRoot (OAE)
Refer to sheet RODSTA-LYR-XX-ZZ-D-L-6007

Refer to planting schedule
Page: XX-ZZ-DWG-L-3003

	TREES
Abr.	**Species**
B p	Betula pendula
B p 35-40	Betula pendula
B u j	Betula utilis jacquemontii
C b	Carpinus betulus
C m	Crategeus monogyna
C m 25-30	Crategeus monogyna
C p 'P'	Crategeus persimilis 'Prunifolia'
C p 'P' 25-30	Crategeus persimilis 'Prunifolia'
P av 'P'	Prunus avium 'Plena
P av 'P' 35-40	Prunus avium 'Plena
P c 'C'	Pyrus calleryana 'Chanticleer'
S a	Sorbus aucuparia
S a 25-30	Sorbus aucuparia
	MULTI-STEM TREES
Abr.	**Species**
A lam	Amelanchier lamarckii
C k	Cornus kousa

ORIGINATOR
Layer. studio
W layer.studio
T 01625 523 157
E manchester or newcastle@layer.studio
MANCHESTER
The Barn
One Hollin Lane
Styal
Cheshire
SK9 4JH
NEWCASTLE
Flintlab
1 Salters Road
Gosforth
Newcastle upon Tyne
NE3 1DH

Client
Wates Construction

Project
Rodney St
Ancoats

Drawing Title
Softworks Tree Planting

Created By	Checked By	Scale	Sheet Size
OK	ST	1:200	A1

Project Number	Originator	Volume	Level	File Type	Discipline	Number
RODSTA	LYR	XX	ZZ	D	L	3002

Work Stage	Status	Revision
Stage 4	A5- Issued for Construction	C04