

ARUP	Job No.		Sheet No.		Rev.		
	276353		23135-ARP-ZZ-XX-SH-E-00004		P01		
	Member/Location						
Job Title		North Manchester General Hospital Work Package 06					
Substation 14 Compound Luminaire Schedule		Made by	MG	Date	22/11/24	Chd.	PH

Notes
3 hour back up battery shall be included on the light fittings when used as emergency lighting.
Contractor to use below or equally approved products for the installation of the lighting fixtures
Contractor shall install the lighting fixture in line with the manufacturer guidelines
Contractor shall install the lighting fixture in co-ordination with the architects

Luminaire Family	Ref	Luminaire Image	Typical Manufacturer	Typical Product Range	Protection Rating	Mounting	Optical Distribution	Light Source Colour	Rated luminous flux (lumens)	Connected Load (Watts)	Dimensions (LxWxH) / ø	Area for use	Other
A	A1		Whitecroft	ACL Industry ACH44K	IP66	Surface	Standard	4000K	4628	32.1	1282 x 140 x 100mm	Transformer Room	
A	A2		Whitecroft	ACL Industry ACH94K	IP66	Surface	Standard	4000K	9518	62.8	1282 x 140 x 100mm	LV Switchroom	
B	B1		Whitecroft	Spectre WX SPXAH24KG	IP65 IK07	Wall	Standard	4000K	1526	17	224 x 375 x 329	Substation 14 Compound - External	
E	EX		Whitecroft	Convex Low Profile Emergency Bulkhead	IP65	Surface	Standard	-	120	2	240 x 130 x 100mm	Exit doors	