Existing tactile crossing to remain

Butler Street

Butler Street

Rodney Street

Rodney Street

Jersey Street

Jersey Street

Proposed development

Wadeford Close

0 10 20

SCALE IN METRES

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION

IN ADDITION TO THE HAZARDS/RISKS NORMALLY ASSOCIATED WITH THE TYPES OF WORK DETAILED ON THIS DRAWING, NOTE THE FOLLOWING

CONSTRUCTION

MAINTENANCE / CLEANING

DECOMMISSIONING / DEMOLITION

IT IS ASSUMED THAT ALL WORKS WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WORKING, WHERE APPROPRIATE, TO AN APPROVED METHOD STATEMENT

Key

PROPOSED CAR PARK ACCESS
40mm AC10 CLOSESURF 100/150
60mm AC20 DENSE BIN 100/150
150mm AC32 DENSE BIN 100/150
225mm TYPE 1 SUB BASE
350mm 6FS CAPPING LAYER (BASED ON 5% CBR)

PROPOSED FOOTWAY
20mm AC6 SURFACE COURSE 100/150
60mm AC20 BINDER COURSE 100/150
150mm TYPE 1 SUB BASE

HIGHWAY VERGE
150mm TOPSOIL AND SEED

TACTILE PAVING
60mm THICK 400mm x 400mm TACTILE PAVING (BUFF)
TO MCC STANDARD DETAIL F10
40mm 4:1 SAND : CEMENT MORTAR (12 HOUR RETARD) BED
150mm TYPE 1 SUB BASE

VEHICULAR CROSSING CONSTRUCTION
20mm AC6 CLOSE SURFACE 100/150
60mm AC20 BINDER COURSE 100/150
150mm WET LEAN CONCRETE TYPE ST2
75mm TYPE 1 SUB BASE

PROPOSED SUB STATION ACCESS (PRIVATE)

SITE BOUNDARY

Rev	Date	Description	By	Ckd
P5	16.08.24	Updated in line with comments	JM	MB
P4	17.07.24	Footway and verge updated	JM	MB
P3	28.05.24	Butler Street access updated	JM	MB
P2	28.02.24	Revised in accordance with clients comments	JM	MB
P1	31.01.24	First Issue	SJ	MB

Architect :

Hydrock

Hydrock Consultants Ltd
St Baldred's Hall
239 Ashley Road
Hale, Cheshire
WA15 9NE
T +44 (0)161 233 0746
manchester@hydrock.com
www.hydrock.com

Client :

Project Title:
RODNEY STREET
MANCHESTER

Drawing Title:
PAVEMENT AND VERGE

Drawing Status:
PRELIMINARY ISSUE

Hydrock Job No:
C18321

Drawn	Checked	Scale @ A1	Date	Issue Date
SJ	MB	1:200	31.01.2024	31.01.2024

Drawing Number:
18321-HYD-XX-XX-DR-D-0700

Revision:
P5

This drawing is the copyright of Hydrock Consultants Ltd