

CLIENT	Great Places Housing Group	SCHEDULE REF		106240-PEF-FD-XX-SH-S-10010		REVISION		C01	STATUS		B1
PROJECT		PREPARED BY		NRS		DATE			10/01/25		
		DATE PREPARED		10-01-25		PAGE			1 of 2		
		CHECKED BY		AM		DRAWING REF		106240-PEF-FD-XX-DR-S-10010			

Member	Bar Mark	Type and size	No. of Mbrs	No.of bars in each	Total No	Length of each bar (mm)	Shape code	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F (mm)	R (mm)	Weight (kg)	Rev
Base edge (Section 4-4)	12	H12	2	36	72	1350	21	700	185	(490)					86.314	
Retaining Wall (Section 1-1)	01	H16	1	580	580	2825	00								2588.830	
	02	H12	1	1160	1160	1475	21	750	215	(540)					1519.368	
	03	H16	1	580	580	1875	11	1190	(710)						1718.250	
	04	H12	1	580	580	3000	00								1545.120	
	05	H12	1	290	290	1400	21	600	225	(600)					360.528	
	06	H12	1	580	580	2200	00								1133.088	
	08	H12	1	58	58	1150	11	550	(600)						59.230	
	17	H12	1	580	580	1150	00								592.296	
Retaining Wall (Section 2-2)	01	H16	2	116	232	2825	00								1035.532	
	02	H12	2	232	464	1475	21	750	215	(540)					607.747	
	03	H16	2	116	232	1875	11	1190	(710)						687.300	
	05	H12	2	58	116	1400	21	600	225	(600)					144.211	
	06	H12	2	116	232	2200	00								453.235	
	07	H12	2	116	232	3375	00								695.304	
	08	H12	2	58	116	1150	11	550	(600)						118.459	
	09	H12	2	58	116	1400	21	600	240	(600)					144.211	
	17	H12	2	116	232	1150	00								236.918	
Slab fold (Detail B)	16	H12	4	2	8	1150	21	500	190	(500)					8.170	
Page Total															13734.111 kg	

This schedule conforms to BS8666:2020

* Specified in multiples of 5 mm.

+ Specified in multiples of 25 mm.

Status:

P Preliminary

T Tender

B1 Construction

