	TREES				
Abr.	**Species**	**Height (cm)**	**Girth (cm)**	**Density/m2**	**Quantity**
B p	Betula pendula	500-550	20-25	as shown	7
B p 35-40	Betula pendula	600-700	35-40	as shown	3
B u j	Betula utilis jacquemontii	500-550	20-25	as shown	7
C b	Carpinus betulus	600-650	30-35	as shown	3
C m	Crategeus monogyna	450-500	18-20	as shown	21
C m 25-30	Crategeus monogyna		25-30	as shown	7
C p 'P'	Crategeus persimilis 'Prunifolia'	450-500	18-20	as shown	10
C p 'P' 25-30	Crategeus persimilis 'Prunifolia'		25-30	as shown	3
P av 'P'	Prunus avium 'Plena	550-600	20-25	as shown	3
P av 'P' 35-40	Prunus avium 'Plena	600-700	35-40	as shown	2
P c 'C'	Pyrus calleryana 'Chanticleer'	550-600	20-25	as shown	4
S a	Sorbus aucuparia	450-500	18-20	as shown	25
S a 25-30	Sorbus aucuparia	min 450	25-30	as shown	2
	MULTI-STEM TREES				
Abr.	**Species**	**Height (cm)**	**Girth (cm)**	**Density/m2**	
A lam	Amelanchier lamarckii	250-300	-	as shown	5
C k	Cornus kousa	250-300	-	as shown	5
	HEDGES				
	Species	**Height (cm)**		**Specification**	
Pl	Prunus lusitanica	120	-	3y/o Root ball	
	WILDFLOWER				
	EW1 Woodland Mixture (Emorsgate Seeds)			Sowing rate- 4 g/m2	
	EL1 Flowering Lawn Mixture (Emorsgate Seeds)			Sowing rate- 4 g/m2	
	RAIN GARDEN SHRUB AND GRASS PLANTING				**Quantity**
	Species	**Size**	**Density/m2**	**Percentage mix**	**Area: 168m2**
A h	Acanthus hungaricus	3L	3	5	24
B m 'J F'	Brunnera macrophylla 'Jack Frost'	3L	3	10	51
C g	Campanula glomerata	3L	3	5	24
D c 'Go'	Deschampsia cespitosa 'Goldtau'	3L	3	10	51
D er	Dryopteris erythrosora	3L	2	10	33
H	Hemerocallis	3L	3	5	24
I si	Iris sibirica	3L	4	10	68
K	Kniphofias	3L	2	5	17
P v	Pennisetum villosum	3L	3	10	51
R f d	Rudbeckia fulgida deamii	3L	4	10	68
S o 'RT'	Sanguisorba officinalis 'Red Thund	3L	5	10	84
S ten	Stipa tenuissima	3L	4	10	68
	ORNAMENTAL SHRUB AND GRASS PLANTING MIX				
	Species	**Size**	**Density/m2**		**Quantity**
	1				**Area: 138m2**
A 'F'	Astilbe 'Fanal'	5L	4	15	84
A sco	Asplenium scolopendrium	3L	5	30	209
H r	Hebe rakaiensis	5L	5	10	71
L m 'RP'	Liriope muscari 'Royal Purple'	5L	7	15	144
P al 'H'	Pennisetum alopecuroides 'Hamel	5L	6	10	84
R f d	Rudbeckia fulgida deamii	3L	4	20	
	2				**Area: 180m2**
B co 'P'	Bergenia cordifolia 'Purpurea'	2L	7	30	352
C m 'I D'	Carex morowii 'Ice dance'	5L	4	15	101
D c 'Go'	Deschampsia cespitosa 'Goldtau'	3L	3	15	81
L an 'H'	Lavandula angustifolia 'Hidcote'	3L	3	10	51
P a 'S'	Persicaria affinis 'Superba'	2L	5	20	167
S x s	Salvia x superba	2L	4	10	65
	NATIVE AND ORNAMENTAL PLANTING MIX (PRIVATE)				
	Species	**Size**	**Density/m2**		**Quantity**
					Area: 93m2
	1				
Aq v	Aquilegia vulgaris	2L	5	10	46
B m 'J F'	Brunnera macrophylla 'Jack Frost'	3L	6	15	84
G od	Galium odoratum	3L	4	10	37
H m	Hakonechloa macra	3L	3	20	57
P vu	Polypodium vulgare	3L	5	30	140
S of	Sanguisorba officinalis	3L	3	15	42
	2				**Area: 84m2**
A mi	Achillea millefolium	3L	5	15	71
C san 'M F'	Cornus sanguinea 'Midwinter Fire'	3L	3	15	42
D f-m	Dryopteris filix-mas	3L	3	10	29
H 'Cc'	Heuchera 'Can-can'	5L	5	15	71
L v	Leucanthemum vulgare	3L	5	15	71
L sy	Luzula sylvatica	3L	5	30	144

NOTES:

1. DO NOT SCALE FROM THIS DRAWING. ALWAYS WORK TO NOTED DIMENSIONS.
2. ALL SETTING OUT, LEVELS AND DIMENSIONS TO BE CHECKED ON SITE PRIOR TO THE INSTALLATION OF MATERIALS AND ANY DISCREPANCIES ARE TO BE BROUGHT TO THE ATTENTION OF THE CONTRACT ADMINISTRATOR IMMEDIATELY.
3. THIS DRAWING MUST BE READ WITH THE RELEVANT SPECIFICATION DOCUMENTS AND DETAIL DRAWINGS. ANY DISCREPANCIES MUST BROUGHT TO THE ATTENTION OF THE CONTRACT ADMINISTRATOR IMMEDIATELY.
4. THIS DRAWING IS COPYRIGHT PROTECTED AND MAY NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN AUTHORITY.
5. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE STATED.

THIS DRAWING WAS PLOTTED ON:
06/11/2024

REVISION HISTORY

DATE	REV	ZONE	DESCRIPTION	CHK
26/07/2024	P04		Design changes CRF003	AD
16/09/2024	P05		Issued for stage approval	AD
05/11/2024	C03		CONSTRUCTION ISSUE	OK

NOTE:

Trees in revsion cloud have been updated/ added since last issue

ORIGINATOR

Layer. studio

W layer.studio
T 01625 523 157
E manchester or newcastle@layer.studio

MANCHESTER
The Barn
One Hollin Lane
Styal
Cheshire
SK9 4JH

NEWCASTLE
Flintlab
1 Salters Road
Gosforth
Newcastle upon Tyne
NE3 1DH

Client
Wates Construction

Project
Rodney St
Ancoats

Drawing Title
Softworks Planting Schedule

Created By	Checked By	Scale	Sheet Size
OK	ST	1:200	A1

Project Number	Originator	Volume	Level	File Type	Discipline	Number
RODSTA	LYR	XX	ZZ	D	L	3003

Work Stage	Status	Revision
Stage 4	A5- Issued for Construction	C03