

Baptist Church Rochdale Rd, Manchester

Noise Impact Assessment Report

Client:

City Point Developments Limited
c/o Zerum, South Central, Suite 4E
11 Peter Street, Manchester, M2 5QR

Date:

6 January 2025

Our Ref:

22144-RP-1-R5



**JAMESON
ACOUSTICS**

Consultants in acoustics,
noise and vibration

Document Control

Revision	Date	Author	Description
0	27-07-2024	AJ	First issue
1	18-09-2024	AJ	To consider updated architectural design
2	15-10-2024	AJ	To capture revisions to fenestration design
3	16-10-2024	AJ	To capture comments from the team
4	04-12-2024	AJ	Minor amendment to project description
5	06-01-2025	AJ	Amendment to capture Level 01 terrace

This report has been prepared with all reasonable skill, care and diligence for the sole benefit, use and information of the aforementioned Client in accordance with the purposes and terms agreed between ourselves and the Client. The liability of Jameson Acoustics Limited in respect of the information contained within this report will not extend to any third party.

Author	Andrew Jameson (AJ)
Position	Director
Qualifications	BSc(Hons) Acoustics, MIOA, MIET
Experience	20+ years
Signature	
Date	06-01-2025

Executive Summary

Planning permission is sought for a new-build residential development on Rochdale Road in Manchester. The development will see the partial demolition of rear of existing building and erection of a 23 storey residential building comprising 133 units with ground floor commercial unit (Use Class E), amenities and associated works.

The site is subject to traffic noise from surrounding road network.

Jameson Acoustics Limited has been commissioned to undertake a noise impact assessment to supplement the planning application. The assessment seeks to demonstrate that [A] noise impacts can be sufficiently mitigated to achieve acceptable acoustic conditions within new dwellings, and [B] noise generated from the operation of the development (plant and amenity operations) can be mitigated to prevent adverse noise impacts on the locality and structurally connected dwellings.

The assessment finds that acceptable internal noise levels within new dwellings can be achieved through the appropriate specification of façade elements and appropriate ventilation and overheating mitigation solutions that removes or restricts reliance on openable purge doors, particularly for dwellings overlooking Rochdale Road. Preliminary guidance on suitable specifications and solutions for framed external window/door systems has been provided. Acoustically-enhanced double glazed windows will be required for façades facing Rochdale Road, reducing to more conventional double glazing to the rear elevation. Purge doors may require additional mass layers to maintain the acoustic performance of the completed frame system.

Outdoor living spaces are to be provided in the form of roof terraces at L01 and L20 and our calculations demonstrate that acceptable noise levels are expected to be achieved, in line with BS 8233.

Plant noise emission limits have been proposed so that future plant installations do not adversely impact on the locality.

Noise impacts from the operation of the ground floor commercial unit and residential amenity spaces within the converted church building have been considered and suitable noise criteria have been proposed to mitigate the risk of adverse noise impacts.

For the commercial unit, the approach should be to provide shell only constructions achieving Building Regulations Part E sound insulation requirements. This will allow future tenants to introduce acoustic enhancements to suit their operation, and the Local Authority may wish to secure this through a suitably worded condition of planning.

For the amenity spaces, provisions exist to enhance building fabric constructions as required to mitigate noise and vibration impact risks to nearby dwellings. However, the exact usage of these amenity spaces is yet to be decided and, again, it may therefore be prudent for the Local Authority to secure this through a suitably worded condition of planning.

Contents

1.0 Introduction 4

2.0 Objectives 4

3.0 Site Description 5

4.0 Planning Policy, Legislation & Assessment Guides 7

5.0 Baseline Noise Survey 9

6.0 Incident Noise Levels 14

7.0 Achieving Internal Noise Levels 16

8.0 Outdoor Living Space 20

9.0 Development-Generating Noise Impacts 21

10.0 Conclusions 22

Appendix A – Acoustic Terminology 24

Appendix B – Planning Policy & Assessment Guides 25

Appendix C – Noise Survey Time History Graphs..... 31

1.0 Introduction

Planning permission is sought for a new-build residential development on Rochdale Road in Manchester. The development will see the partial demolition of rear of existing building and erection of a 23 storey residential building comprising 133 units with ground floor commercial unit (Use Class E), amenities and associated works.

The site is subject to traffic noise from surrounding road network.

Jameson Acoustics Limited has been commissioned to undertake a noise impact assessment to supplement the planning application. The assessment seeks to demonstrate that [A] noise impacts can be sufficiently mitigated to achieve acceptable acoustic conditions within new dwellings, and [B] noise generated from the operation of the development (plant and amenity operations) can be mitigated to prevent adverse noise impacts on the locality and structurally connected dwellings.

For a description of the acoustic terminology used herein, please see Appendix A.


2.0 Objectives

- To review the latest national and local planning policies/requirements and relevant design standards and good practice guides that will inform the noise impact assessments.
- To carry out a detailed noise survey at the site, capturing daytime and night-time traffic noise levels at selected positions in accordance with BS 7445.
- Based on the survey data, to undertake a noise assessment for the suitability of the site for residential use in accordance with the Noise Policy Statement for England (NPSE), National Planning Policy Framework (NPPF), statutory legislation, Planning Practice Guidance (ProPG), British Standard BS8233:2014 and Local Authority guidance/requirements.
- To subsequently provide guidance on noise mitigation and façade sound insulation solutions to achieve acceptable acoustic conditions within the completed scheme.
- To set noise emission limits for the development in line with BS 4142 with the aim of minimising the risk of the operation of new plant causing a noise nuisance to neighbours.
- To advise on sound insulation provisions to adequately control commercial/amenity noise transfer externally and to adjoining residential spaces.

3.0 Site Description

3.1 Location

The site is located on Rochdale Road in Manchester and falls under the jurisdiction of Manchester City Council. See Location Plan below.



Location Plan (© maps.google.co.uk)

3.2 Description

The site, occupied by the Baptist church (not in use), is bounded by Rochdale Road to the south east, Sharp Street to the north east, Dyche Street to the north west and an open air car park to the south west. Existing residential use buildings surround the site on all sides.

There are no notable commercial/industrial/entertainment premises nearby, other than the Angel Pub to the south west approximately 75 metres from the site. This pub has a function room but does not, however, host any live or amplified music events.


The noise climate on site was noted to be dominated by road traffic, particularly Rochdale Road. The remaining roads surrounding the site are minor access roads with relatively low traffic flows.


See site plan below.



Site Plan (© maps.google.co.uk)

The proposed development is for the conversion of the Baptist church and a new build 20-storey new-build extension. The church will accommodate residential amenities, including co-working spaces, lounges and a gym. The new-build tower will accommodate BOH plant, a ground floor commercial unit and residential apartments from Level 1 to Level 20. External amenity space (terraces) will be provided at Level 01 and 20, both facing onto Dyche Street. See below the proposed plans at ground, mezzanine, L01 and a typical upper floor plan.





4.0 Planning Policy, Legislation & Assessment Guides

4.1 National Planning Policy

National planning policies are set out in the following:

- Noise Policy Statement for England [NPSE], 2010;
- National Planning Policy Framework [NPPF], 2023;
- National Planning Practice Guidance – Noise [PPGN], 2019.

These documents provide a qualitative approach to noise assessments. See Appendix B for a detailed description of each.

4.2 Local Planning Requirements

4.2.1 Local Authority Development Plan

Manchester City Council's [MCC] Core Strategy was adopted on the 11 July 2012 and is the key document in the Manchester Local Plan. It sets out the long-term strategic policies for Manchester's future development and will form the framework that planning applications will be assessed against.

The Core Strategy requests that all new developments follow the 'Development Principles' and accord with the design guidance set out in the Supplementary Planning Documents. In accordance with Policy DM1, this includes the effects on amenity due to noise generated by a new development and, conversely for noise sensitive uses (e.g. residential), the effects of environmental noise onto the new development.

MCC's Supplementary Planning Document relating to noise is their 'Planning & Noise, Technical Guidance' published in October 2022 by their Environmental Protection Team. This document provides guidance to applicants and consultants concerning the assessment and prediction of environmental noise associated with a particular development. The key elements relevant to this development are summarised below.

4.2.2 Specific Guidance on Noise

In relation to noise affecting newly proposed residential properties, the council has adopted the following noise limits for sites affected only by environmental noise (e.g. road traffic):

- **Bedrooms (night time – 23.00 – 07.00) 30 dB L_{Aeq} (individual noise events should not normally exceed 45 dB $L_{Amax,F}$ by more than 10 times)**
- **Living Rooms (daytime – 07.00 – 23.00) 35 dB L_{Aeq}**
- **Gardens and terraces (daytime) 55 dB L_{Aeq}**

In relation to commercial noise, MCC's guidance advises that *"BS 4142 should be used to assess the likely impact of noise from industrial and commercial sources at noise sensitive premises"*. The Council consider that new developments should contribute and enhance the area in which they are located and where possible, i.e. prevent 'noise creep', contribute to the improvement of people's health and quality of life as per the NPSE. For fixed plant, the Council advises a BS 4142 assessment that demonstrates that:

'Externally mounted ancillary plant, equipment and servicing shall be selected and/or acoustically treated in accordance with a scheme designed so as to achieve a rating level of 5dB (L_{Aeq}) below the typical background (L_{A90}) level at the nearest noise sensitive location'.

4.3 Legislation (Building Regulations)

The development will need to be built in such a way that it conforms to the Building Regulations 2010. In relation to noise and acoustics, the key documents to consider are:

- Approved Document E: 2003 Edition (incorporating amendments to 2015) – Resistance to the Passage of Sound [ADE];
- Approved Document F: 2021 Edition – Ventilation [ADF];
- Approved Document O: 2021 Edition – Overheating [ADO].

ADE relates to the design of the building's internal building fabric and primarily considers the control sound transfer between adjacent spaces. In planning terms, this development will contain a party floor separating new apartments from the ground floor commercial unit which will need to be designed in such a way that they achieve, as a minimum, the below ADE on-site sound insulation performance.

Description	Required Performance
Minimum airborne sound level difference <i>Party Walls/Floors separating dwellings from other parts of the building</i>	45 dB $D_{nT,w} + C_{tr}$

ADF includes a section on controlling noise from ventilation systems. It states that “*account should be taken of outside noise when considering whether openable windows are appropriate for purge ventilation*” and that noise from mechanical ventilation systems operating under normal conditions (not boost rates) should not exceed 30 dB $L_{Aeq,T}$ for noise sensitive rooms (e.g. bedrooms) and 45 dB $L_{Aeq,T}$ in less sensitive rooms.

ADO took effect on 15 June 2022 and does not apply to work subject to a building notice, full plans application or initial notice submitted before that date, provided the building work is started before 15 June 2023. It requires noise to be considered as part of the development’s overheating strategy in locations where external noise may be an issue. It states that the overheating strategy should take account of the likelihood that windows will be closed during sleeping hours if noise within bedrooms exceeds the following limits.

- 40 dB $L_{Aeq,T}$, averaged over 8 hours (between 11pm and 7am).
- 55 dB L_{AFmax} , more than 10 times a night (between 11pm and 7am).

4.4 Assessment Guides

For planning and noise, the following industry standards and assessment guides shall be considered.

- ProPG: Planning & Noise, 2017;
- BS 8233: 2014 ‘*Guidance on sound insulation and noise reduction for buildings*’;
- World Health Organisation [WHO] Environmental Noise Guidelines, 2018;
- Acoustics, Ventilation & Overheating [AVO] Residential Design Guide, 2020;
- BS 4142: 2014 ‘*Methods for Rating and Assessing Industrial and Commercial Sound*’.


See Appendix B for a detailed description of each.

5.0 Baseline Noise Survey

5.1 Procedure

Automated noise level measurements were taken from 12:00 hours on Thursday 23 May 2024 to 11:00 hours on Wednesday 29 May 2024 at 2nr on-site positions as described below. Both positions were selected to establish the typical prevailing daytime and night-time ambient, maximum and background noise levels on the front and rear facing elevations of the existing Baptist church building.

Position	Type	Description
1	Automated	Microphone protruding 1m from the south east elevation of the Baptist Church, overlooking Rochdale Road (Level 1). Façade measurement.
2	Automated	Microphone protruding 1m from the north west elevation of the Baptist Church, overlooking Dyche Street (Level 1). Façade measurement.



Site Plan showing measurement positions (© maps.google.co.uk)

The equipment was programmed to continuously log all relevant A-weighted broadband (dBA) and linear spectral noise level indices, including L_{eq} , L_{90} , L_{10} and L_{max} , over intervals of 5-minutes, 15-minutes and 1-hour intervals.

All measurements were taken in general accordance with BS 7445-1: 2003 '*Description and Measurement of Environmental Noise*'.

5.2 Instrumentation

The instrumentation used for the survey is summarised below. The sound level meters were hand-calibrated at the beginning and end of the survey periods. No significant deviations in calibration level were noted.

Description	Equipment	Serial Nr	Lab Calibration Expiry	Lab Calibration Certificate Nr
Class 1 sound level meter	Svantek 971A (with Type 7152 microphone)	131642 (85571)	9 Nov 2024	10 Nov 2022
Class 1 sound level meter	Svantek 971A (with Type 7152 microphone)	127647 (84398)	12 Mar 2025	13 Mar 2023
Class 1 sound calibrator	Cirrus CR:515	57570	28 Nov 2024	1153776

5.3 Weather Conditions

Due to the nature of the survey, i.e. unmanned, it is not possible to describe the weather conditions throughout the duration of the survey period. However, on install and collection, weather conditions were considered suitable for obtaining representative readings. The sky was overcast, road surfaces were damp/dry and wind speeds were low (below 4 m/s).

Based on internet weather reports for the full duration of the survey, conditions generally remain commensurate with those described, although there was periods of high wind speeds and rainfall recorded on Thursday 23 May (00:00-00:00).

5.4 Observed Noise Climate

Due to the nature of the automated survey, i.e. unmanned, it is not possible to describe the noise climate throughout the duration of the survey period. However, on install and collection the noise climate was noted to be dominated by road traffic on Rochdale Road.

5.5 Results & Analysis

5.5.1 Automated Noise Survey A

The uncorrected results of the automated survey have been plotted on Time History Graph 22144-1-G1 to G2 enclosed in Appendix C. The graph presents the 15-minute A-weighted (dBA) L_{90} , L_{eq} and L_{max} levels throughout the duration of the survey.

A summary of the results, as used to inform subsequent assessments against current guidelines, is presented in the following tables. Note, the values below have been corrected to 'free-field'.

L_{Aeq} Ambient Noise Levels

The logarithmically averaged 16-hour daytime and 8-hour night-time L_{Aeq} ambient noise levels

Position 1 Period Commencement (Day/Night of...)	Free-Field Ambient Noise Level (dB)	
	Daytime L _{Aeq,16hr} (07:00-23:00)	Night-time L _{Aeq,8hr} (23:00-07:00)
Thursday 23 May 2024	68 ¹	64
Friday 24 May 2024	68	64
Saturday 25 May 2024	67	64
Sunday 26 May 2024	67	63
Monday 27 May 2024	66	61
Tuesday 28 May 2024	67	62
Wednesday 29 May 2024	68 ¹	-
Taken for Assessment	68	64

¹ incomplete 16-hour period

Position 2 Period Commencement (Day/Night of...)	Free-Field Ambient Noise Level (dB)	
	Daytime L _{Aeq,16hr} (07:00-23:00)	Night-time L _{Aeq,8hr} (23:00-07:00)
Thursday 23 May 2024	59 ¹	55
Friday 24 May 2024	58	53
Saturday 25 May 2024	57	54
Sunday 26 May 2024	57	53
Monday 27 May 2024	56	53
Tuesday 28 May 2024	58	53
Wednesday 29 May 2024	58 ¹	-
Taken for Assessment	58	53

¹ incomplete 16-hour period

L_{Afmax} Maximum Noise Levels at Night

The 10-15th highest 5-minute L_{Afmax} maximum noise level 'event' at night


Position	Free-Field Maximum Noise Level (dB) At Night-time L _{Amax,5min} (23:00-07:00)
1	78
2	68

L_{A90} Background Noise Levels


The representative background determined through statistical analysis to BS 4142

Position	Free-Field Background Noise Level (dB)	
	Daytime L _{A90,1hr} (07:00-23:00)	Night-time L _{A90,15min} (23:00-07:00)
1	55	47
2	50	42


See below graphs showing the % distribution of background noise levels at each position throughout the duration of the survey.




Daytime – Position 1



Night-time – Position 1



Daytime – Position 2




Night-time – Position 2

6.0 Incident Noise Levels


6.1 Road Traffic Noise

Incident road traffic noise levels onto each building façade have been analysed using 3D noise modelling software. The following plan illustrates the spread of daytime $L_{Aeq,16hr}$ traffic noise levels across the existing site.




Noise Map of Existing Site – Daytime $L_{Aeq,16hr}$ traffic noise levels (5 m above ground – first floor level)

The following Figures illustrate the incident daytime $L_{Aeq,16hr}$ traffic noise levels across the proposed façades of the development. Note, night-time $L_{Aeq,8hr}$ noise levels will be consistently circa 4-5 dB lower than these values.



Looking North



Looking South

Incident night-time L_{Amax} noise levels are calculated to be ≤ 78 dB on the Rochdale Road elevation (lower levels), and ≤ 68 dB on the Dyche Street (lower levels).

7.0 Achieving Internal Noise Levels

7.1 Criteria

We would propose the following internal noise levels to be achieved within new dwellings during normal ventilation conditions.

Room	Desirable Internal Noise Level	
	Daytime (07:00-23:00)	Night-time (23:00-07:00)
Living Room	35 dB $L_{Aeq,16hr}$	-
Bedroom	35 dB $L_{Aeq,16hr}$	30 dB $L_{Aeq,8hr}$ 45 dB* L_{Amax}

* Noise events (5-min) - not exceeded more than 10-15 times per night

7.2 Building Envelope Acoustic Design

7.2.1 External Walls & Roofs

The façade design proposes brick (or brick-slip) external walls with insulated external cavity, SFS with outer sheathing board, full fill insulation and double layer plasterboard linings with punched-in double glazed windows and purge vent panels. The external wall construction would be expected to provide a sound reduction performance of not less than 45 dB $R'_w + C_{tr}$. This performance would far surpass what will be required on this site to control noise ingress.

The roof elements will be a solid concrete slab of circa 200-225 mm depth with plasterboard ceilings to top floor apartments. Such a construction would be expected to provide a sound reduction performance of not less than 50 dB $R'_w + C_{tr}$. This performance would far surpass what will be required on this site to control noise ingress.


7.2.2 Framed External Windows/Door Systems

Preliminary sound insulation calculations have been carried out in order to specify the minimum sound insulation performance of the windows. Our calculations follow BS 8233 procedures and consider the apartment room dimensions and window sizes taken from the planning stage drawings.


Our calculations suggest provisions should be made for the following specifications for the complete framed window/door systems to habitable rooms (living rooms and bedrooms). Example configurations are provided for guidance only. The complete framed systems include the frames, spandrels, purge doors (closed), seals, etc.. Not just the glass.

Note, purge panels in the higher performance zones may require additional mass layers to achieve the performance requirements.


Façade Zone (ref. Figures below table)	Min. Required Sound Reduction $R_w + C_{tr}$ (dB)	Example Glass Configuration (for guidance only)
RED	36	10.4 / 16 / 6.4 mm (aco. lam.)
ORANGE	32	8 / 16 / 6.4 mm (lam.)
BLUE	28	6 / 16 / 6 mm




South east elevation



South west elevation



North east elevation



North west elevation

7.2.3 Ventilation

For ventilation (and to assist with overheating), MVHR heat recovery systems will be provided to each apartment. These will remove the need for trickle ventilators and/or openable windows for normal ventilation (in line with Approved Document F). These units will be suitably sized and provided with a manual operable boost and an evening bypass mode that will remove any reliance on opening windows during the night to avoid overheating (in line with Approved Document O) – see Section 7.3.

Our calculations indicate that with conventional MVHR duct sizes, additional in-duct attenuators at façade openings for noise ingress control should not be required.

Note: Noise from mechanical ventilation systems shall be designed to NR 25 in bedrooms at night and NR 30 in bedrooms and living rooms during the day.

7.3 Overheating & Noise

Often the overheating strategy for residential buildings places some reliance on openable windows/purge doors in the summer months. For sites where incident noise levels are high, noise should be taken into account when considering whether openable windows are appropriate for providing this extra purge ventilation to control overheating.

In accordance with the Acoustics, Ventilation and Overheating Guide (AVO), the associated risk of noise levels been deemed unacceptably high with windows open would be when incident external noise levels exceed 65 dB $L_{Aeq,16hr}$ (day) and 55 dB $L_{Aeq,8hr}$ (night). In addition, Building Regulations' Part O advises that the overheating strategy should assume windows will be closed throughout the night where incident façade noise levels exceed circa 49 dB $L_{Aeq,8hr}$ and 64 dB L_{Amax} .


Based on the Part O requirements, **the overheating strategy shall assume bedroom purge doors will be closed throughout the night (23:00-07:00hr) for all apartments.**

For AVO (daytime), the following table sets out the maximum number of hours purge doors can be modelled as open during daytime hours before internal noise levels would exceed the Significant Observed Adverse Effect Level (SOAEL) when averaged over a 16-hr assessment period (to account for embedded mitigation, e.g. upsized MVHRs to minimise open window reliance). A 13 dB external to internal noise level difference has been taken for periods where purge vents are open (50% free-area) in line with Appendix C of AVO (losses for fully opened window).


Façade Zone (ref. Figure in Section 7.2.2)	Maximum number of hours purge doors can be open during the day (07:00-23:00) when assessed over full 16-hr noise exposure period
RED	4 hours
ORANGE	7 hours
BLUE	10 hours

Provided these limits are achieved, internal noise levels would fall below the AVO threshold in all zones, as illustrated on the below Figures.


The x-axis scale is duration for which 'overheating condition' occurs (in hours), the y-axis is the internal ambient noise level (in dB, $L_{Aeq,16hr}$).



Red Zone – AVO Assessment



Orange Zone – AVO Assessment



Blue Zone - AVO Assessment

Based on our experience working on similar schemes with restricted reliance on openable windows for acoustics, TM59 internal temperature targets can be maintained with a combination of suitably specified solar-rated glazing, appropriately sized windows, black-out blinds, and the specification of suitably sized mechanical ventilation systems.

Air conditioning (or additional purge fans) could be considered for red zone apartments with consideration for the fact that the temporary rise in internal noise levels during the period the purge door is open would significantly exceed the AVO SOAEL level. The introduction of such additional mechanical solutions would remove reliance on the purge doors for overheating control, but this should be considered carefully. Not only with regard to additional cost and maintenance, but sustainability and the environment, which are factors that carry more importance for any new development under MCC's jurisdiction. Additional mechanical solutions would increase carbon emissions, which is part of the cause of the issue we are trying to mitigate.


8.0 Outdoor Living Space

The development proposals include large, shared roof terraces at Level 01 and Level 20, as shown in Section 3.2.

For outdoor living spaces, BS 8233 states:

“For traditional external areas that are used for amenity space, such as gardens and patios, it is desirable that the external noise level does not exceed 50 dB $L_{Aeq,T}$, with an upper guideline value of 55 dB $L_{Aeq,T}$ which would be acceptable in noisier environments. However, it is also recognized that these guideline values are not achievable in all circumstances where development might be desirable and a compromise between elevated noise levels and other factors, such as the convenience of living in these locations or making efficient use of land resources to ensure development needs can be met, might be warranted. In such a situation, development should be designed to achieve the lowest practicable levels in these external amenity spaces but should not be prohibited.”

The calculated noise levels on the L20 roof terrace are summarised on the following plan. These levels are calculated at a height of 1.7 m above roof level (approx. head height). The model does not include any solid screening to the perimeter (i.e. perimeter railings assumed to be hit-and-miss) other than a solid parapet assumed to be circa 0.5 m in height.



Noise Model plan showing noise levels on roof terrace

The results illustrate noise levels are expected to achieve the BS 8233 ‘upper’ target of ≤ 55 dB $L_{Aeq,16hr}$ across the terrace.

9.0 Development-Generating Noise Impacts

9.1 Plant Noise Emission Limits

Based on the results of the noise survey and the requirements of the Local Authority, we propose the following plant noise emission limits to be achieved incident at the nearest noise sensitive windows with all plant operating simultaneously. These limits are 5 dB below the prevailing 'representative' background noise levels.

Receptor Location	Plant Noise Rating Limit, $L_{A,T,r}$ ref. BS 4142 (dB)	
	Daytime (07:00-23:00)	Night-time (23:00-07:00)
Receptors over Rochdale Road	50	42
Receptors to north	45	37

Noise shall be assessed in accordance with BS 4142:2014 with corrections applied for any plant emitting noise of a tonal or irregular quality.

The above limits shall be subject to the final approval of the Local Authority.

9.2 Amenity / Commercial Unit Operations

The development will contain residential amenity spaces within the converted Baptist church and a ground floor commercial unit within the new build block. These spaces may have the potential to generate notable activity noise levels depending on the intended usage. Any such noise may have the potential to cause adverse impacts to external noise sensitive receptors (noise breakout through facades) and/or to the structurally connected new dwellings within the building (airborne and/or structure-borne noise transfer).

In the converted church, the exact uses / opening times etc. for the amenity spaces is not known; however, the current intent is for the space to operate as a coworking/lounge with a gym provided at mezzanine level. The church will effectively be a separate building to the new-build, albeit with structural columns for the new-build penetrating through the church structure. Provided these structural columns are de-coupled (isolated) from the church building, structure-borne noise transfer will not be a concern. Airborne noise breakout will need to be assessed.

For the coworking areas, the risk of excessive noise breakout will be low. For the gym, however, additional information may be required to demonstrate compliance to the local authority's requirements. For now, we would advise provisions are made for additional treatment. Treatment may include enhanced acoustic ceilings (double layer plasterboard, mineral wool, and possibly acoustic hangers below the tiled roof structure) and suitably rated glazing to control external noise breakout. The need for specialist acoustic floating floor treatments to mitigate the risk of structure-borne noise and vibration transfer may be required depending on the configuration of the new-build columns and existing structure. Note that, depending on the use of the gym, size of weights, and

ProPG G-curve assigned, it may be necessary to consider a heavy weight concrete floating floor system with additional rubber gym matting of an appropriate thickness.

For the commercial unit, the shell construction shall be designed to achieve Building Regulations ADE standards, with prospective tenants made responsible for acoustic upgrades to suit their operation. For Level 1 amenity spaces (usage unknown at this stage), provisions for appropriately specified ceilings should be made to control noise transfer to apartments directly above.

We would propose the base-build approach aims to achieve the following:

- All separating constructions to neighbouring dwellings to achieve Building Regulations ADE minimum standards;
- Anticipated activity noise transfer from amenity spaces ($L_{Aeq,5min}$) should be controlled to 5dB below the typical background noise level (L_{A90}) in each octave band in neighbouring habitable rooms. NB: If background noise levels closely match MEP services noise limits of NR30 (daytime) and NR25 (night-time), activity noise limits of NR25 (daytime) and NR20 (night-time) may be suitable.
- For 'entertainment' amenity spaces (i.e. with music noise), noise levels in the 63Hz and 125Hz octave centre frequency bands (L_{eq}) should be controlled so as not to exceed (in habitable rooms) absolute noise limits of 47dB and 41dB ($L_{eq,5min}$), respectively.
- For gyms, airborne and structure-borne noise should be controlled in line with ProPG Gym Acoustics design guide (2023), with a suitable G-curve assigned to mitigate risks of structural-impacts caused by the dropping of weights, use of treadmills, etc..

Given the lack of detailed information at this stage, it may be prudent for the local authority to consider a suitably worded condition so further information can be provided as the building design progresses.

10.0 Conclusions

Planning permission is sought for a new-build residential development on Rochdale Road in Manchester. The development will see the partial demolition of rear of existing building and erection of a 23 storey residential building comprising 133 units with ground floor commercial unit (Use Class E), amenities and associated works.

The site is subject to traffic noise from surrounding road network.

Jameson Acoustics Limited has been commissioned to undertake a noise impact assessment to supplement the planning application. The assessment seeks to demonstrate that [A] noise impacts can be sufficiently mitigated to achieve acceptable acoustic conditions within new dwellings, and [B]

noise generated from the operation of the development (plant and amenity operations) can be mitigated to prevent adverse noise impacts on the locality and structurally connected dwellings.

The assessment finds that acceptable internal noise levels within new dwellings can be achieved through the appropriate specification of façade elements and appropriate ventilation and overheating mitigation solutions that removes or restricts reliance on openable purge doors, particularly for dwellings overlooking Rochdale Road. Preliminary guidance on suitable specifications and solutions for framed external window/door systems has been provided. Acoustically-enhanced double glazed windows will be required for façades facing Rochdale Road, reducing to more conventional double glazing to the rear elevation. Purge doors may require additional mass layers to maintain the acoustic performance of the completed frame system.

Outdoor living spaces are to be provided in the form of roof terraces at L01 and L20 and our calculations demonstrate that acceptable noise levels are expected to be achieved, in line with BS 8233.

Plant noise emission limits have been proposed so that future plant installations do not adversely impact on the locality.

Noise impacts from the operation of the ground floor commercial unit and residential amenity spaces within the converted church building have been considered and suitable noise criteria have been proposed to mitigate the risk of adverse noise impacts.

For the commercial unit, the approach should be to provide shell only constructions achieving Building Regulations Part E sound insulation requirements. This will allow future tenants to introduce acoustic enhancements to suit their operation, and the Local Authority may wish to secure this through a suitably worded condition of planning.

For the amenity spaces, provisions exist to enhance building fabric constructions as required to mitigate noise and vibration impact risks to nearby dwellings. However, the exact usage of these amenity spaces is yet to be decided and, again, it may therefore be prudent for the Local Authority to secure this through a suitably worded condition of planning.

Appendix A – Acoustic Terminology

dB	Decibel - Used as a measurement of sound level. Decibels are not an absolute unit of measurement but an expression of ratio between two quantities expressed in logarithmic form.
dB(A)	The human ear is more susceptible to mid-frequency noise than the high and low frequencies. The 'A'-weighting scale approximates this response and allows sound levels to be expressed as an overall single figure value in dBA. The _A subscript is applied to an acoustical parameter to indicate the stated noise level is A-weighted (e.g. $L_{Aeq,T}$ in dB). Noise levels in dBA do not have a linear relationship to each other; for similar noises, a change in noise level of 10dBA represents a doubling or halving of subjective loudness. A change of 3dBA is only just perceptible.
$L_{Aeq,T}$	$L_{Aeq,T}$ is the equivalent continuous sound pressure level. It is an average of the total sound energy measured over a specified time measurement period, T .
$L_{10,T}$	L_{10} is the noise level exceeded for 10% of the measurement period T (i.e. the quietest 10% of the measurement) and has, for many years, been used in the assessment of road traffic noise.
$L_{90,T}$	L_{90} is the noise level exceeded for 90% of the measurement period T (i.e. the quietest 10% of the measurement) and is often used to describe the 'background' noise level.
L_{max}	L_{max} is the maximum sound pressure level recorded over the measurement period, T . L_{max} is often used in assessing scheduled environmental noise 'events' (such as train passbys), particularly at night where such events may cause sleep disturbance.
R_w	The weighted sound reduction index, R_w , is a single figure description of sound reduction as defined in BS EN ISO 717-1. It is single-number quantity which characterizes the airborne sound insulating properties of a material or building element over a range of frequencies. The R_w is calculated from sound insulation measurements taken in an acoustic laboratory. Sound insulation ratings derived from site measurements are invariably lower than the laboratory figures and are referred to as the apparent weighted sound reduction index, R'_w .
$D_{n,e,w}$	The weighted element-normalised level difference, $D_{n,e,w}$, is a single figure description of the sound insulation performance of small building elements, such as a trickle ventilator.
C_{tr}	C_{tr} is correction term applied against the sound insulation single-number values (e.g. R_w) to provide a weighting against low frequency performance. The reference values used within the C_{tr} calculation are based on urban traffic noise.

Appendix B – Planning Policy & Assessment Guides

Planning Policy

- **Noise Policy Statement for England (NPSE)**

The Noise Policy Statement for England (NPSE) launched in March 2010 states the long-term vision of Government noise policy is to *“promote good health and a good quality of life through the effective management of noise within the context of Government policy on sustainable development”*.

The long-term vision is supported by the following aims; through the effective management and control of environmental, neighbour and neighbourhood noise within the context of Government policy on sustainable development:

- Avoid significant adverse impacts on health and quality of life;
- Mitigate and minimise adverse impacts on health and quality of life;
- Where possible, contribute to the improvement of health and quality of life.

The intention is that the NPSE should apply to all types of noise apart from noise in the workplace (occupational noise).

The NPSE introduces a three-tier concept for the assessment of noise impacts onto a receptor:

- **NOEL – No Observed Effect Level:** The level below which no effect can be detected and below which there is no detectable effect on health and quality of life due to noise.
- **LOAEL – Lowest Observable Adverse Effect Level:** The level above which adverse effects on health and quality of life can be detected.
- **SOAEL – Significant Observed Adverse Effect Level:** The level above which significant adverse effects on health and quality of life occur.

There are no numeric thresholds relating to each of the above. The NPSE acknowledges that the severity of noise impacts vary depending upon the type of noise, the type of receptor, the duration (on-time) of the noise, the characteristics of the noise, the time of day, the day of the week, etc.. As a result, the definition of what constitutes an SOAEL is somewhat flexible.

- **National Planning Policy Framework (NPPF)**

The National Planning Policy Framework (NPPF) was first published in 2012 and sets out the government’s planning policies for England and how these are expected to be applied.

The latest revision of the NPPF (2023) states that planning system should **contribute to, and enhance**, the natural and local environment by (amongst others) *“preventing both new and existing development from*

*contributing to or being put at unacceptable risk from, or being adversely affected by unacceptable levels of soil, water or **noise pollution** or land stability.”*

The express inclusion of noise in the NPPF means that it is a material planning consideration for local planning decisions.

Paragraph 123 of the NPPF document states that planning policies and decisions should aim to:

“A. Avoid noise from giving rise to significant adverse impacts on health and quality of life as a result of new development;

B. Mitigate and reduce to a minimum other adverse impacts on health and quality of life arising from noise from new development, including through the use of conditions;

C. Recognise that development will often create some noise and existing businesses wanting to develop in continuance of their business should not have unreasonable restrictions put on them because of changes in nearby land uses since they were established; and

D. Identify and protect areas of tranquillity which have remained relatively undisturbed by noise and are prized for their recreational and amenity value for this reason.”

NPPF advises that decisions relating to planning applications should ensure “...new development is appropriate for its location taking into account the likely effects (including cumulative effects) of pollution on health, living conditions and the natural environment, as well as the potential sensitivity of the site or the wider area to impacts that could arise from the development.”

To achieve this, new developments should “mitigate and reduce to a minimum potential adverse impacts resulting from noise from new development – and avoid noise giving rise to significant adverse impacts on health and the quality of life” and should also “identify and protect tranquil areas which have remained relatively undisturbed by noise and are prized for their recreational and amenity value for this reason.”

The NPPF recognises that “...new development can be integrated effectively with existing businesses and community facilities (such as places of worship, pubs, music venues and sports clubs). Existing businesses and facilities should not have unreasonable restrictions placed on them as a result of development permitted after they were established. Where the operation of an existing business or community facility could have a significant adverse effect on new development (including changes of use) in its vicinity, the applicant (or ‘agent of change’) should be required to provide suitable mitigation before the development has been completed.”

- **Planning Practice Guidance on Noise (PPG)**

The National Planning Practice Guidance (PPG) is a web-based resource, launched by the Department for Communities and Local Government (DCLG) in March 2014 to support the NPPF and make it more accessible. It advises on how planning can manage potential noise impacts in new development. The guidance is regularly reviewed and updated and noise is listed as a specific category. The guidance is for ad hoc developments, as major infrastructure is covered by overarching National Policy Statements.

PPG provides the following tabulated summary of the effects of noise exposure (in terms of health and quality of life) associated with noise generating and sensitive developments.

Response	Examples of Outcomes	Increasing Effect Level	Action
No Observed Effect Level			
Not present	No effect	No Observed Effect	No specific measures required
Present and not intrusive	Noise can be heard, but does not cause any change in behaviour, attitude or other physiological response. Can slightly affect the acoustic character of the area but not such that there is a change in the quality of life.	No Observed Adverse Effect	No specific measures required
Lowest Observed Adverse Effect Level			
Present and intrusive	Noise can be heard and causes small changes in behaviour, attitude or other physiological response, e.g. turning up volume of television; speaking more loudly; where there is no alternative ventilation, having to close windows for some of the time because of the noise. Potential for some reported sleep disturbance. Affects the acoustic character of the area such that there is a small actual or perceived change in the quality of life.	Observed Adverse Effect	Mitigate and reduce to a minimum
Significant Observed Adverse Effect Level			
Present and disruptive	The noise causes a material change in behaviour, attitude or other physiological response, e.g. avoiding certain activities during periods of intrusion; where there is no alternative ventilation, having to keep windows closed most of the time because of the noise. Potential for sleep disturbance resulting in difficulty in getting to sleep, premature awakening and difficulty in getting back to sleep. Quality of life diminished due to change in acoustic character of the area.	Significant Observed Adverse Effect	Avoid
Present and very disruptive	Extensive and regular changes in behaviour, attitude or other physiological response and/or an inability to mitigate effect of noise leading to psychological stress, e.g. regular sleep deprivation/awakening; loss of appetite, significant, medically definable harm, e.g. auditory and non-auditory.	Unacceptable Adverse Effect	Prevent

Assessment Guides

- ProPG: Planning & Noise**

ProPG: Planning & Noise 'Professional Practice Guidance on Planning & Noise' was issued in May 2017 with the primary goal of assisting the delivery of sustainable residential development by promoting good health and well-being through the effective management of noise. It seeks to do that through encouraging a good acoustic design process in and around proposed new residential development having regard to national policy on planning and noise.

It is applicable to noise from existing transport sources (noting that good professional practice should have regard to any reasonably foreseeable changes in existing and/or new sources of noise). The recommended approach is also considered suitable where some industrial or commercial noise contributes to the acoustic environment provided that is “not dominant”.

ProPG advocates a systematic, proportionate, risk based, 2-stage, approach. The approach encourages early consideration of noise issues, facilitates straightforward accelerated decision making for lower risk sites, and assists proper consideration of noise issues where the acoustic environment is challenging.

The two sequential stages of the overall approach are:

Stage 1 – an initial noise risk assessment of the proposed development site; and

Stage 2 – a systematic consideration of four key elements.

- Element 1 – demonstrating a “Good Acoustic Design Process”;
- Element 2 – observing internal “Noise Level Guidelines”;
- Element 3 – undertaking an “External Amenity Area Noise Assessment”; and
- Element 4 – consideration of “Other Relevant Issues”.

The ProPG considers suitable guidance on internal noise levels found in BS 8233 (see below) with the addition of an $L_{Amax,f}$ requirement for bedrooms at night, as below.

“Regular individual noise events (for example, scheduled aircraft or passing trains) can cause sleep disturbance. A guideline value may be set in terms of SEL or $L_{Amax,F}$, depending on the character and number of events per night. Sporadic noise events could require separate values. In most circumstances in noise-sensitive rooms at night (e.g. bedrooms) good acoustic design can be used so that individual noise events do not normally exceed 45 dB $L_{Amax,F}$ more than 10 times a night. However, where it is not reasonably practicable to achieve this guideline then the judgement of acceptability will depend not only on the maximum noise levels but also on factors such as the source, number, distribution, predictability and regularity of noise events.”

- **BS 8233: 2014**

British Standard 8233: 2014 ‘Sound insulation and noise reduction for buildings’ presents the following desirable internal ambient noise levels for dwellings based on steady external noise sources (e.g. road traffic).

Activity	Location	Desirable Internal Ambient Noise Level	
		07:00 – 23:00	23:00 – 07:00
Resting	Living Rooms	35 dB $L_{Aeq,16hour}$	-
Dining	Dining Room/Area	40 dB $L_{Aeq,16hour}$	-
Sleeping (Daytime Resting)	Bedroom	35 dB $L_{Aeq,16hour}$	30 dB $L_{Aeq,8hour}$

BS 8233 states that where development is considered necessary or desirable, despite external noise levels above WHO guidelines, the internal target levels may be relaxed by up to 5 dB and reasonable internal conditions still achieved.

For outdoor living spaces, BS 8233 states:

“For traditional external areas that are used for amenity space, such as gardens and patios, it is desirable that the external noise level does not exceed 50 dB $L_{Aeq,T}$, with an upper guideline value of 55 dB $L_{Aeq,T}$ which would be acceptable in noisier environments. However, it is also recognized that these guideline values are not achievable in all circumstances where development might be desirable and a compromise between elevated noise levels and other factors, such as the convenience of living in these locations or making efficient use of land resources to ensure development needs can be met, might be warranted. In such a situation, development should be designed to achieve the lowest practicable levels in these external amenity spaces but should not be prohibited.

Other locations, such as balconies, roof gardens and terraces, are also important in residential buildings where normal external amenity space might be limited or not available, i.e. in flats, apartment blocks, etc. In these locations, specification of noise limits is not necessarily appropriate. Small balconies may be included for uses such as drying washing or growing pot plants, and noise limits should not be necessary for these uses. However, the general guidance on noise in amenity space is still appropriate for larger balconies, roof gardens and terraces, which might be intended to be used for relaxation. In high-noise areas, consideration should be given to protecting these areas by screening or building design to achieve the lowest practicable levels. Achieving levels of 55 dB $L_{Aeq,T}$ or less might not be possible at the outer edge of these areas, but should be achievable in some areas of the space.”

- **World Health Organisation (WHO)**

The current WHO Environmental Noise Guidelines 2018 for the European Region supersede the 1999 Guidelines for Community Noise, although it does suggest that the 1999 values for indoor noise levels remain valid, as presented below.


Noise Source	CNG guideline indoors all sources	ENG guideline outdoors noise from specific source only
Road traffic	35 dB $L_{Aeq, 16h}$	53 dB L_{den}
	30 dB $L_{Aeq, 8h}$	45 dB L_{night}
Railway	35 dB $L_{Aeq, 16h}$	54 dB L_{den}
	30 dB $L_{Aeq, 8h}$	44 dB L_{night}
Aircraft	35 dB $L_{Aeq, 16h}$	45 dB L_{den}
	30 dB $L_{Aeq, 8h}$	40 dB L_{night}

With regard to night-time noise “events”, WHO states *“In many situations, average noise levels like the L_{den} or L_{night} indicators may not be the best to explain a particular noise effect. Single-event noise indicators – such as the maximum sound pressure level (L_{Amax}) and its frequency distribution – are warranted in specific situations, such as in the context of night-time railway or aircraft noise events that can clearly elicit awakenings and other physiological reactions that are mostly determined by $L_{A,max}$. Nevertheless, the assessment of the relationship between different types of single-event noise indicators and long-term health outcomes at the population level remains tentative. The guidelines therefore make no recommendations for single-event noise indicators.”*

- **Acoustics, Ventilation & Overheating Residential Design Guide**

The Acoustics, Ventilation and Overheating Residential Design Guide (Version 1.1) was issued in January 2020 by the Association of Noise Consultants (ANC) and the Institute of Acoustics (IOA). This document provides guidance on the interdependence between acoustics, ventilation and overheating.

The AVO guide recommends a two-level approach to assess the potential impact of noise ingress through windows that have been opened to mitigate overheating and also noise from any mechanical services used to provide comfort cooling. The level 1 assessment relates to incident environmental noise levels across a proposed site, it is used to define “risk categories” for each building façade based on these levels. These categories are set out below:



At planning stage the level of information required to undertake a level 2 assessment in-line with the AVO guide is often not available and a level 1 assessment, which establishes the risk categories of each proposed façade, would be most suitable.

- **BS 4142:2014**

British Standard BS 4142 looks at the assessment of noise of a commercial / industrial nature. It describes methods for rating and assessing outdoor sound of an industrial and/or commercial nature “on people who might be inside or outside a dwelling or premises used for residential purposes upon which sound is incident”. In relation to this development, this includes sound from fixed installations, comprising M&E plant and equipment.


The assessment method is based on the difference between the measured ‘background sound level’ without the influence of any industrial noise source, and the ‘rating level’ of the industrial source, at the receiver location. A difference of around +10 dB or more is likely to be an indication of a significant adverse impact. A difference of around +5 dB is of marginal significance, and where the rating level does not exceed the background, this is an indication of the specific sound source having a low impact.

Appendix C – Noise Survey Time History Graphs

Rochdale Road, Manchester

Measurement Position 1 (Facade Measurement)
Thursday 23 May 2024 - Wednesday 29 May 2024

22144-1-G1



Rochdale Road, Manchester

Measurement Position 2 (Facade Measurement)

Thursday 23 May 2024 - Wednesday 29 May 2024

22144-1-G2

