# CDA Plasterers

Proposal of Lime plaster work to ground floor (Cut and Craft manchester)

Ground floor existing walls are lime finished plaster and all repair work to these walls would need to be carried out in lime plaster like for like. NHL2 by saintastier is the material proposed to use. It is compliant for solid wall constructions and is a breathable system. This would be applied within manufacturers guidelines as per data sheet.  it will then be finished with a lime putty and sand finishing coat. This consists of 5 minutes dry mixing followed by 15 minutes of wet mixing prior to applying coats. Please see attached data sheet for further information should you need it.

https://limestuff-static.myshopblocks.com/uploads/28d946cc64464abea62805d23b4310d5/Lime-Stuff-Technical-Data-Sheet-Secil-NHL2.pdf