


GENERAL NOTES

- This drawing is the copyright of tpm landscape Ltd and cannot be reproduced in any form without the consent of the company.
- This drawing is to be read in conjunction with detail landscape drawings, details and specification.
- This drawing is to be read in conjunction with all relevant Architects', Engineer's, Specialists, Bills of Quantities and Specifications.
- The insertion of any firm or proprietary brand on this drawing is an indication of the class or quality required and does not exclude the use of alternative materials that are equal in performance, quality and appearance, provided that they have been approved in writing by the Landscape Architect.
- The Contractor is responsible for accurately ascertaining the position of underground services and responding to all relevant service easement requirements.
- All dimensions are in millimetres unless stated otherwise, for the purposes of construction this drawing must not be scaled and only written dimensions used. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. IF IN DOUBT PLEASE ASK.
- All work and materials are to be in accordance with the relevant British Standards and Code of Practice.
- All Proprietary products are to be used strictly in accordance with the manufacturer's instructions and details.



TPM Planting Schedule (continued)										
No	Code	Plant Name	Height/Spread/Grade	Girth	Age	Root	Container	Height	Form	Density/ha
303	16 HED	Fagus sylvatica	100-120cm			C	10L	Bulky		3.00
276	17 H	Prunus laurocerasus	100-120cm			C	10L	Bulky		3.00
Herbaceous										
No	Code	Plant Name	Height/Spread/Grade	Girth	Age	Root	Container	Height	Form	Density/ha
23	AC05	Achillea Millefolium	30-40cm			C	5L			5.00
48	ALV1	Alchemilla vulgaris 'Snowy Jewel'	30-40cm			C	5L			5.00
11	ALR0	Andromeda 'Snowfall'	30-40cm			C	5L			5.00
43	ARM H	Artemisia vulgaris	30-40cm			C	5L			5.00
44	ARM	Artemisia vulgaris	30-40cm			C	5L			5.00
27	CV01	Carex monensis 'Emerald'	30-40cm			C	5L			5.00
84	IS	Isotria medeoloides	30-40cm			C	5L			5.00
76	LSB	Lonicera xylosteum 'Blue'	30-40cm			C	5L			5.00
13	HT	Hebe x exoniensis	30-40cm			C	5L			4.00
44	HEX	Hebe x exoniensis 'Major Award'	30-40cm			C	5L			5.00
36	HRP	Hebe x exoniensis 'Major Award'	30-40cm			C	5L			5.00
38	HRP	Hebe x exoniensis 'Major Award'	30-40cm			C	5L			5.00
34	HRP	Hebe x exoniensis 'Major Award'	30-40cm			C	5L			5.00
72	HRP	Hebe x exoniensis 'Major Award'	30-40cm			C	5L			5.00
83	HRP	Hebe x exoniensis 'Major Award'	30-40cm			C	5L			5.00
23	HRP	Hebe x exoniensis 'Major Award'	30-40cm			C	5L			5.00
13	HRP	Hebe x exoniensis 'Major Award'	30-40cm			C	5L			5.00
14	HRP	Hebe x exoniensis 'Major Award'	30-40cm			C	5L			5.00
Specimen										
No	Code	Plant Name	Height/Spread/Grade	Girth	Age	Root	Container	Height	Form	Density/ha
34	BOGS	Brachyglottis Duvalei Group 'Summer'	30-40cm			C	5L	Branching		4.00
4	CS	Clematis jackmanii	100-120cm			C	5L		Climber	
4	CS	Clematis jackmanii	100-120cm			C	5L		Climber	
17	CS	Clematis jackmanii	100-120cm			C	5L		Climber	
80	ERS	Erythronium albidum 'Gold'	30-40cm			C	5L			4.00
26	ERS	Erythronium albidum 'Gold'	30-40cm			C	5L			4.00
27	ERS	Erythronium albidum 'Gold'	30-40cm			C	5L			4.00
2	HSA	Hydrangea arborescens 'Annabelle'	60-80cm			C	10L	Branching	Specimen	
38	HSA	Hydrangea arborescens 'Annabelle'	60-80cm			C	5L			4.00
36	HSA	Hydrangea arborescens 'Annabelle'	60-80cm			C	5L			4.00
40	HSA	Hydrangea arborescens 'Annabelle'	60-80cm			C	5L			4.00
7	HSA	Hydrangea arborescens 'Annabelle'	60-80cm			C	10L		Specimen	
41	HSA	Hydrangea arborescens 'Annabelle'	60-80cm			C	5L			4.00
24	HSA	Hydrangea arborescens 'Annabelle'	60-80cm			C	5L			4.00
33	HSA	Hydrangea arborescens 'Annabelle'	60-80cm			C	5L			4.00
18	HSA	Hydrangea arborescens 'Annabelle'	60-80cm			C	5L			4.00
8	HSA	Hydrangea arborescens 'Annabelle'	60-80cm			C	5L			4.00
18	HSA	Hydrangea arborescens 'Annabelle'	60-80cm			C	5L			4.00
4	HSA	Hydrangea arborescens 'Annabelle'	60-80cm			C	10L		Specimen	
25	PW	Phlox paniculata 'Blue'	60-80cm			C	10L	Specimen		4.00
39	RHM	Rhododendron 'Red Admiral'	30-40cm			C	5L			4.00
23	RHM	Rhododendron 'Red Admiral'	30-40cm			C	5L			4.00
72	RHM	Rhododendron 'Red Admiral'	30-40cm			C	5L			4.00
18	RHM	Rhododendron 'Red Admiral'	30-40cm			C	5L			4.00
4	RHM	Rhododendron 'Red Admiral'	30-40cm			C	5L			4.00
TPM Native Shrub Mix A										
No	Code	Plant Name	Height/Spread/Grade	Girth	Age	Root	Container	Height	Form	Density/ha
3	AC01	Achillea Millefolium	30-40cm			C	5L		Selected Standard	
4	ALV1	Alchemilla vulgaris 'Snowy Jewel'	30-40cm			C	5L		Selected Standard	
1	CS	Clematis jackmanii	100-120cm			C	5L		Standard (Selected)	
2	CV01	Carex monensis 'Emerald'	30-40cm			C	5L		Standard (Selected)	
3	ERS	Erythronium albidum 'Gold'	30-40cm			C	5L		Selected Standard	
4	HSA	Hydrangea arborescens 'Annabelle'	60-80cm			C	5L		Selected Standard	
TPM Native Shrub Mix B										
No	Code	Plant Name	Height/Spread/Grade	Girth	Age	Root	Container	Height	Form	Density/ha
205	CBP	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
322	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
388	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
400	NTT	Nerium 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
TPM Native Shrub Mix C										
No	Code	Plant Name	Height/Spread/Grade	Girth	Age	Root	Container	Height	Form	Density/ha
80	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
81	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
82	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
83	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
84	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
85	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
86	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
87	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
88	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
89	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
90	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
91	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
92	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
93	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
94	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
95	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
96	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
97	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
98	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
99	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00
100	CSB	Cornus 'Red Pearl'	20-30cm			C	5L		Bulb	11.00

NOTES ON PLANTING

1 Topsoil / Subsoil: Topsoil shall be spread to min 450mm depth over planting beds and 150mm depth over turf areas and graded to fall. Topsoil should be in accordance with BS3882:2015 and where subsoil is required, to be in line with BS8601:2013. It is recommended that samples are tested with Certification and Analysis Reports with a concise analysis. To be provided to the landscape Architect / Client for approval. If the soil doesn't meet the BS standard specialist advise should be received to see if the soil can be improved.

2 Herbicide and Cultivation: Topsoil to be treated with an application of herbicide prior to planting, where necessary, strictly in accordance with the Control of Pesticides Regulations 1986 (or otherwise updated / superceded legislation), and following manufacturers instructions and undertaken by qualified staff. The topsoil shall then be cultivated to 150mm depth)

3 Container Grown Shrubs, Transplants and Whips: Shrubs and transplants shall comply with the National Plant Specification. Shrubs shall be planted in pits 300 x 300 x 200mm depth, and the backfill shall include 3 litres Peat Free Tree and Shrub Compost. Specimen plants to be planted in a pit 400 x 400 x250mm depth with 5 litres Tree and Shrub Compost. BR whips should be notch planted as required and healed into position. All whips to be protected by a spiral bound shrub guard secured into place with a timber cane. When in public locations it may be necessary to have caps to the canes.

4 Herbicide: Spot treat with herbicide throughout the maintenance period in accordance with the manufacturer's instructions.

5 Bark Mulch: All Ornamental Planting beds to receive 75mm depth pulverised ornamental bark mulch.

6 Position of Plants: Final position of trees and shrubs subject to confirmation of service location and approval of statutory undertakers.

7 On excavation of the tree pit a bucket test should be undertaken to review the water infiltration. Certain species of trees will decline if the ground drainage is poor. Monitor the water egress. If water sits for long periods or doesn't drain the pit may require further works to break up the ground. A clean stone drainage layer may assist to ensure that the root ball isn't sat within standing water.

8 TREES - STANDARD: Tree pits to be 600x600x600mm backfilled with good quality topsoil. Stake to be 1 no. 65mm diameter treated softwood driven firmly into the ground, 650mm above ground level and 300mm below the bottom of the pit. Stakes to be fixed to tree with suitable rubber tree tie. Tree stake to be placed on the windward side of the tree to prevent rubbing. Stake to be pointed at one end. Spacing of stakes to avoid rootball. If within lawn tree to be set in circle area of bark mulch 75mm depth at 500mm diameter. Pit backfilled with 1 parts topsoil, 2 parts tree planting compost to depth of 500mm and with a 100mm depth of clean stone to the base.

TREES - EXTRA HEAVY STANDARDS Tree pits to be 900x900x900mm backfilled with sub soil and 450mm topsoil. Stakes to be 65mm diameter treated softwood driven firmly into the ground. Stakes to be 1m above ground level and fixed to tree with suitable rubber tree tie. Add in 100mm depth clean stone gravel at the base of the tree pit to aid with drainage. Trees planted within grass to have 500mm diameter of 75mm depth pulverised ornamental bark mulch around the tree trunk.

TREES - MULTI STEMMED: Tree pits for multi-stemmed trees to be 600x600x600mm backfilled with sub soil and 300mm of topsoil. To be secured with a double stake and crossbar. Stakes to be 65mm diameter treated softwood driven firmly into the ground. Stakes to be 600mm above ground level and fixed to several tree branches with suitable rubber tree ties. Trees planted within grass to have 500mm diameter of 75mm depth pulverised ornamental bark mulch around the tree trunk.

8 Watering: Plant only into moist soil and water thoroughly to the full depth of soil immediately after planting. Water regularly through the establishment period (minimum 3 months) to prevent dehydration. The trees should be watered through the irrigation pipe to ensure that the water gets down to the rootball. These trees should be watered regularly throughout spring-summer during the first 2 years to ensure that the tree root system establish well.


9 Bulb Planting: Plant spring flowering bulbs(e.g. daffodils, tulips, spring flowering crocus) in autumn and autumn flowering (e.g. autumn crocus, cyclamen) bulbs in late summer. Plant bulbs at 8 per m2. Plant bulbs at a depth 2-3 times their height with the shoot facing upwards. Refill the holes and lightly compact soil to avoid damaging bulbs.

10 Grass Seeding: Sow late summer to mid autumn. Prepare ground by removing any existing vegetation, large stones and roughly levelling. An application of non-residual systemic glyphosate containing weedkiller may be required. Grass seed should be spread at 50g per metre squared After sowing, lightly rake over area and water.


11 Turf: Complete ground preparations before turf is delivered to site to avoid turf drying out. Turf should be laid immediately on delivery. Remove all existing vegetation from area to be turfed and spread 150mm depth of top soil. Dig over or rotavate soil before laying turf if soil is compacted. Rake, lightly compact, and water soil. Stagger the joins when laying the turf. Water turf after laying and every day for the next 2-3 weeks, especially in periods of low rainfall.

12 Tree species selected subject to soil conditions and NHBC guidance. Root barriers may be required subject to findings from soil analysis and engineer's details.


LEGEND
SOFT LANDSCAPE




Existing Trees and Hedges to be Retained
Trees to be retained and protected in line with BS5837:2012. Please refer to Keen Consultants Arboricultural Survey for more information.



Existing Trees and Hedges to be Removed
To avoid disturbance to breeding birds, any woody vegetation will be removed prior to the bird-breeding season (March to August inclusive). If this is not possible, the site will be checked prior to removal or other ground works that may disturb breeding species (e.g. dunlocks in hedgerows) by an experienced ecologist. If active nests are found, areas will be left untouched and suitably buffered from works until all birds have fledged. Specific advice will be provided prior to undertaking the clearance.




Proposed Medium Trees
Trees to be planted as 14-16cm girth, Extra Heavy Standard, 5.5-6m high with 2m clear single stem. Trees to be double staked and secured with suitable rubber ties.




Proposed Small Ornamental Tree
To be 3-3.5m high specimen.




Proposed Ornamental Planting
Proposed shrubs and flowering herbaceous to be planted as 3.5L pots at 3-5 per sq.m. and enhanced by feature specimens in 10-20L pots.




Proposed Native Shrub Mix
Bare root stock, 60-80cm, planted at 2p/m2 and planted in groups of 3-5. Plants to be protected with spiral guards where necessary.




Proposed Evergreen Hedge
Evergreen hedge, 100-120cm high, to be planted at 3 plants per lin.m.



Proposed Native Hedge
Native hedge, 100-120cm high, to be planted at 3 plants per lin.m. Species: Fagus sylvatica



Proposed Grass
To be turf.



Proposed Woodland Bulbs
To provide seasonal interest.

REVISION NOTES

Rev	By	Description	Date
I	AJ	T33 removed and replaced	06.06.24
H	EO	Updated in line with landscape layout	17.05.24
G	EO	Updated in line with landscape layout	02.05.24
F	AJ	Updated in line with landscape layout	24.01.24
E	TS	Updated in line with landscape layout	29.11.23
D	AJ	Updated in line with landscape layout	21.11.23
C	EO	Updated in line with latest layout	20.10.23
B	AJ	Updated in line with latest layout	14.03.23
A	FZ	Added 3no medium trees	02.03.23

Client
McCarthy & Stone Retirement
Lifestyles Ltd

Project
Spath Lane, Didsbury

Description
Planting Plan

Status
For Approval

Scale @ A1
1:250

Drawn
JW

Checked
CW

Date
03.01.23

Drawing number
NW-2697-03-LA-201 3712

Revision
I

tpm landscape
chartered landscape architects
address: 4th Floor Studio 10 Little Lever St Manchester M1 1HR
tel: 0161 235 0600 fax 0601 email info@tpmlandscape.co.uk

</