

- ## Floor Finishes

- ## Ceiling Finishes

- | | | | |
|-----------------|--|----|----|
| D
16/01/2025 | Finishes updated | RG | |
| C
08/01/2025 | Finishes updated to reflect existing | RG | |
| B
23.08.24 | Plan revised following duct relocation | RG | |
| A
12/08/24 | Updated to indicate treatment of former stair location following Planner comments. | HW | HW |

77-79 Mosley St, Manchester

Ground Floor Plan - Finishes

K sketch E existing P proposed T tender C construction FI final issue

+44 161 236 0051
ARCHITECT@ATELIERMB.CO.UK

ATELIER.MB



- 1 Existing hoistway metal surround to be retained as existing. Paint to be brushed down to remove loose friable materials only.
- 2 Existing lift enclosure - carefully remove existing mesh infill and replace with new. Paintwork to be carefully brushed down and cleaned of any loose friable paint.
- 3 Existing openings - frame retained and redecorated. New painted partition inserted to suit fire and acoustic separation requirements.