

22987. Fusion – Whitworth Street

Fencing Scoping Overview

Description of works as the following.

- Remove existing hoarding
- Remove all debris, rubbish, loose materials etc
- Make good Cameron Street including new block paving to approx. 50m2
- Prepare existing surfaces for and lay amenity turf including a gravel maintenance strip
- Make good kerb line to the exiting footpath
- Make good existing dwarf wall

Design Notes

Fencing to be provided as a 2.4m high black metal railing with double gate access to be provided. Fencing to include curbing plinth to edge of existing footpath, footpath to be made good accordingly. Posts to be spaced equally Fencing to be sized and detailed by specialist designer. Landscaped area to be turfed with gravel drainage strip to the perimeter. Example of similar style fencing below.

