MANCHESTER CITY COUNCIL

Environmental Health
Internal Memorandum

To	Head of Planning	FAO: David Lawless
From	Head of Compliance, Enforcement and Community Safety	
Contact Officer:	Laura Miller	Our Ref: PR202501-1605859
Date:	20 February 2025	Telephone: 31742

Consultation on Planning Application

Application No: 139878/FO/2024

Description: Erection or a terrace of four 3 storey dwellinghouses, following the demolition of Barway Court; conversion and erection of an extension (3 storey) to the side of no. 28 Edge Lane to form a terrace of three dwellinghouses, with associated car parking and landscaping.

Location: 28 Edge Lane Manchester M21 9JY

I write in response to your memorandum of the 31 January 2025 regarding the above application and to inform you that I have considered the application and recommend that the following conditions are attached to any approval.

DEMOLITION/CONSTRUCTION MANAGEMENT PLAN

Prior to the commencement of development, a demolition/construction management plan outlining working practices shall be submitted to and approved in writing by the City Council as Local Planning authority, which for the avoidance of doubt shall include as a minimum:

- Measures to control noise and vibration;
- Dust suppression measures;
- Compound locations where relevant;
- Details of an emergency contact telephone number;
- A community consultation plan; and
- Sheeting of construction vehicles.

The development shall only be carried out in accordance with the approved management plan.

Reason - To safeguard the amenities of nearby residents pursuant to policies SP1, EN19 and DM1 of the Manchester Core Strategy.

*The applicant should refer to our noise from building sites webpage for further information/guidance and also IAQM/EPUK Construction Guidance on controlling emissions. [Currently January 2024, Version 2.2]

The submitted Construction Method Statement is accepted in principle. We will require a detailed demolition and construction management plans including site layout drawings prior to the activities commencing.

DEMOLITION/CONSTRUCTION HOURS

Construction/demolition works shall be confined to the following hours unless otherwise agreed in writing by the City Council as local planning authority:

- Monday - Friday: 7.30am - 6pm
- Saturday: 8.30am - 2pm
- Sunday / Bank holidays: No work

Reason - To safeguard the amenities of nearby residents pursuant to policies SP1, EN19 and DM1 of the Manchester Core Strategy.

Information for Developers guidance documents can be downloaded using the following link:
http://www.manchester.gov.uk/info/500207/planning_and_regeneration/1962/additional_planning_guidance/3

NSE4(b) (Residential sound insulation AND overheating)

a) Before the development commences a scheme for acoustically insulating the proposed residential accommodation against noise from Edge Lane shall be submitted to and approved in writing by the City Council as local planning authority. There may be other actual or potential sources of noise which require consideration on or near the site, including any local commercial/industrial premises.

The potential for overheating shall also be assessed and the noise insulation scheme shall take this into account. The approved noise insulation and ventilation scheme shall be completed before any of the dwelling units are occupied.

Noise survey data shall include measurements taken during a rush-hour period and night time to determine the appropriate sound insulation measures necessary. The following noise criteria shall be required to be achieved when providing adequate ventilation as defined by Approved Document F of the Building Regulations (whole dwelling ventilation):

Bedrooms (night time - 23.00 - 07.00) 30 dB L_{Aeq} (individual noise events shall not exceed 45 dB $L_{Amax,F}$ by more than 10 times)

Living Rooms (daytime - 07.00 - 23.00) 35 dB L_{Aeq}

Gardens and terraces (daytime) 55 dB L_{Aeq}

Higher internal noise levels than those specified above may be allowed when higher rates of ventilation are required in relation to the overheating condition.

b) Prior to first occupation of the residential units, a verification report shall be required to validate that the work undertaken throughout the development conforms to the recommendations and requirements in the approved acoustic consultant's report. The report shall also undertake post completion testing to confirm that the internal noise criteria have been met. Any instances of non-conformity with the recommendations in the verification report shall be detailed along with any measures required to be undertaken prior to first occupation of the residential units to ensure compliance with the internal noise criteria.

Reason: To secure a reduction in noise from traffic or other sources in order to protect future residents from noise disturbance and to reduce the potential for overheating.

An acoustic report has been submitted (Nova Acoustics, 20/12/2021), the report has suggested that further mitigation measures may be required with regards to overheating, as such a TM59 assessment is required to determine if MVHR or other mechanical ventilation also needs to be installed in the development if opening the windows at night comprises the acoustic comfort of the occupiers. The TM59 assessment needs to be considered alongside the acoustic assessment and not in isolation. This needs to be undertaken to cover part a) of this condition

NSE6 (External plant/equipment/servicing)

a) Externally mounted ancillary plant, equipment and servicing shall be selected and/or acoustically treated in accordance with a scheme designed so as to achieve a rating level of 5dB (L_{Aeq}) below the typical background (L_{A90}) level at the nearest noise sensitive location. Prior to commencement of the use hereby approved the scheme shall be submitted to and approved in writing by the City Council as local planning authority in order to secure a reduction in the level of noise emanating from the site. The scheme shall be implemented in full before the use commences or as otherwise agreed in writing by the City Council as local planning authority.

b) Prior to the operation of the scheme a verification report shall be submitted to and approved in writing by the City Council as local planning authority to validate that the work undertaken throughout the development conforms to the recommendations and requirements in the approved acoustic report. The report shall also undertake post completion testing to confirm that the noise criteria have been met. Any instances of non-conformity with the recommendations in the verification report shall be detailed along with any measures required to be undertaken prior to operation of the scheme to ensure compliance with the agreed noise criteria.

Reason - To minimise the impact of the development and to prevent a general increase in pre-existing background noise levels around the site.

If required for any mechanical ventilation

REF*

a) Before the development commences a scheme for the storage and disposal of refuse shall be submitted to and approved in writing by the City Council as local planning authority.

New developments shall have refuse storage space for segregated waste collection and recycling. Internal and external storage areas are required.

b) The details of the approved scheme shall be implemented as part of the development and shall remain in situ whilst the use or development is in operation.

Reason - In the interests of amenity and public health.

* The submitted drawings show all the houses to have space for three bins, they will need to have four bins to cover all the waste and recycling streams collected by Manchester City Council. The drawings need to be updated and our waste proforma also needs completing to support the application.

CLAND01

a) Before the development hereby approved commences, a report (the Preliminary Risk Assessment) to identify and evaluate all potential sources and impacts of any ground contamination, groundwater contamination and/or ground gas relevant to the site shall be submitted to and approved in writing by the City Council as local planning authority. The Preliminary Risk Assessment shall conform to City Council's current guidance document (Planning Guidance in Relation to Ground Contamination).

In the event of the Preliminary Risk Assessment identifying risks which in the written opinion of the Local Planning Authority require further investigation, the development shall not commence until a scheme for the investigation of the site and the identification of remediation measures (the Site Investigation Proposal) has been submitted to and approved in writing by the City Council as local planning authority.

The measures for investigating the site identified in the Site Investigation Proposal shall be carried out before development commences and a report prepared outlining what measures, if any, are required to remediate the land (the Site Investigation Report and/or Remediation Strategy) which shall be submitted to and approved in writing by the City Council as local planning authority.

b) When the development commences, the development shall be carried out in accordance with the previously agreed Remediation Strategy and prior to occupation a Completion/Verification Report shall be submitted to and approved in writing by the City Council as local planning authority.

In the event that ground contamination, groundwater contamination and/or ground gas, not previously identified, are found to be present on the site at any time before the development is occupied, then development shall cease and/or the development shall not be occupied until, a report outlining what measures, if any, are required to remediate the land (the Revised Remediation Strategy) is submitted to and approved in writing by the City Council as local planning authority and the development shall be carried out prior to occupation in accordance with the Revised Remediation Strategy, which shall take precedence over any Remediation Strategy or earlier Revised Remediation Strategy.

Reason - To ensure that the presence of or the potential for any contaminated land and/or groundwater is detected and appropriate remedial action is taken in the interests of public safety, pursuant to [INSERT] of the Unitary Development Plan for the City of Manchester.

AIR QUALITY 2*

a) Prior to commencement of the development, a scheme for electric vehicle charging and any other considerations, for example boiler emissions, shall be submitted to and approved in writing by the City Council as local planning authority.

b) Prior to occupation of the development any agreed mitigation measures shall be implemented and verified as such in writing by the City Council as local planning authority and shall remain in situ whilst the use or development is in operation.

Reason: To secure a reduction in air pollution from traffic or other sources in order to protect existing and future residents from air pollution, pursuant to policies EN16, SP1 and DM1 of the Core Strategy.

**The developer should refer to MCC's AQ Guidance Note for EV charge point recommendations, and also IAQM Planning guidance for further information on boilers etc if relevant.*

Should you wish to discuss this matter further please contact Laura Miller

Samantha Stabler
Head of Compliance, Enforcement and Community Safety