

Proposed Materials and Electric Vehicle Charging
Specification

Project: Jack Edwards Court, West Didsbury
Application Ref: 132484/FO/2021

Proposed Materials

Brick: Crofters Medley Brick by Wienerberger , see attached technical sheet.

Slate Slips: Black Slate Cladding by London Stone

Windows: New windows to be Anthracite grey UPVC to front and rear extension.
Where windows are being replaced on the existing building these will be white UPVC, to match existing.

Re-con Stone cills: 'Cheshire' coloured re-con stone by The Cast Stone Company ltd.

Samples will be available to view on site by arrangement. Alternatively, if you wish for the samples to be delivered to your office then please provide the address and we will arrange this.

Electric Vehicle Charging Specification

Installation of 3 No. charging stations on mounting post to concrete base

3 No. MER Eve Pro Line 7 KW 230V with RFID

Locations identified on Proposed Landscaping Plan drawing No C-12 Rev B



Crofters Medley

Product Technical Information Sheet



Wienerberger Code	24170480
Production Plant	Denton
Manufacture	Extruded/Wirecut
Configuration	Perforated
Colour	Red Multi
Appearance	Dragfaced
Work Size (mm)	215 x 102.5 x 65
Pack Quantity	400 No.
Individual Dry Brick Weight (kg)	2.1

Technical Properties to BS EN 771-1

Size Tolerance (Mean/Range)	T2/R1
Gross Dry Density (kg/m ³ /Tolerance)	1480 (D1)
Compressive Strength (N/mm ²)	≥40
Thermal Conductivity (W/(m·K))	P=90% 0.69
λ _{10,dry,unit} value (EN 1745 tabulated: S1)	
Durability Designation	F2
Water Absorption (%)	≤12
Initial Rate of Water Absorption (kg/(m ² ·min))	Min. 1.0 Max. 2.2
Active Soluble Salts	S2
Reaction to Fire	Class A1

Issue Date: 07/09/2020

Technical data correct at time of issue. Individual dry brick weights can vary and are for guidance only. Any questions regarding this data should be referred to the Wienerberger Technical Department. Due to the limitations of screen and print colour representation of product images it is advised that brick samples are viewed prior to ordering.



**BIM Objects
Download**



1000+ products to choose from



Expert help and advice



Comprehensive Design Services



Technical Support



COTSWOLD



BATHSTONE



PORTLAND




GREY



CHESHIRE



HAMPTON



HUDDERSFIELD



CARDINAL RED


COLOUR CHART




< Stone Cladding /

BLACK SLATE CLADDING

£52.00 + VAT m² (£62.40 inc VAT)



Andrew Jordan Landscape & Garden Design



ENLARGE

PayPal Pay in 3 interest-free payments on purchases from £30-£2,000. [Learn more](#)

Stock Item

11.63 kg per m²

FREE* Delivery. Get it Tue, 3 Dec 2024*



"Our aim, particularly with London town gardens, is to find ways of breaking up boundaries, and the Black Slate is great even just for cladding a...(Read More)"

Tom Howard Garden Design | tomhowardgardens.co.uk

OPTIONS AVAILABLE

m ²	Ea	M ² / Pack	Stock Level*	Price/m ²	Qty
600x150x15-30mm		17.64	189.36	£52.00	0

Stock levels shown are live and identical to those seen by our staff. For out-of-stock items, please contact us for the next delivery date.

Order Sample

ADD TO BASKET

 Quick Calculator

DESCRIPTION

NATURAL VARIATION INFORMATION

CARBON FOOTPRINT INFORMATION

SPECIFICATION & DIMENSIONS

  Product GuideInstallation Guide	
Dimensions	See Options Available table above
Tolerance	+/- 5mm
Packaging	Wooden Crates, Cardboard Boxes, Plastic Wrap
Suitable for	Walls
Surface Finish	Riven
Edge Profile	Square
Material Type	Slate (metamorphic natural stone)
Country Of Origin	India
Sealing	Optional - Improves maintenance
Application	External & Internal
Weight	Weight per piece: 600x150 = 7.43kg
Frost Resistant	Yes
Water Absorption	0.20%

INSTALLATION & AFTERCARE

FAQS


DELIVERY & RETURNS

ALSO AVAILABLE IN



Brazilian Black Slate Bullnose Step

From £80.00 + VAT Ea



Brazilian Black Slate Pencil Round Coping Stones

From £45.00 + VAT Ea



Brazilian Black Slate Paving

From £45.00 + VAT m²

YOU MAY ALSO LIKE