

GENERAL NOTES

REMOTE DRIVER POSITIONS SHALL BE AGREED ONSITE WITH THE MAIN CONTRACTOR. THE AGREED LOCATIONS ARE TO BE OUT OF DIRECT VIEW BUT ACCESSIBLE FOR POTENTIAL MAINTENANCE REQUIREMENTS.

IF THE REMOTE DRIVER POSITIONS ARE TO BE LOCATED EXTERNALLY, THE MAIN CONTRACTOR SHALL ALLOW FOR THE APPROPRIATE EXTERNAL RATED ACCESSIBLE ENCLOSURES TO HOUSE THE LIGHTING EQUIPMENT. THESE SHALL BE POSITIONED IN AN ACCESSIBLE LOCATION OUT OF DIRECT VIEW FROM GROUND AND FIRST FLOOR LEVEL.

CABLING TO THE LUMINAIRES SHALL BE INSTALLED NEATLY AND CONCEALED FROM DIRECT VIEW WHERE PHYSICALLY POSSIBLE.

ALL ELECTRICAL JUNCTION BOXES SHALL BE INSTALLED NEATLY AND CONCEALED FROM DIRECT VIEW WHERE POSSIBLE. JUNCTION BOXES SHALL BE COLOUR MATCHED TO MATCH ADJACENT STRUCTURES.

FITTING DETAILS

FINING OF ALL LIGHTING EQUIPMENT SHALL BE AGREED ONSITE WITH THE MAIN CONTRACTOR AND PROJECT ARCHITECT / CONSERVATION SPECIALIST.

FINING DETAILS SHOULD HAVE MINIMAL IMPACT ON THE FABRIC OF BUILDING WHERE POSSIBLE, BUT SHALL ENSURE ALL LIGHTING EQUIPMENT IS PERMANENTLY FIXED AND SAFELY INSTALLED.
FINAL FITTING POSITIONS TO BE REVIEWED AND AGREED ONSITE WITH THE MAIN CONTRACTOR FOLLOWING THE LIGHTING MOCK UP REVIEW.

LIGHTING CONTROL

THE EXTERNAL LIGHTING SHALL BE CONTROLLED VIA THE SPECIFIED ARCHITECTURAL LIGHTING CONTROL SYSTEM WITH AUTOMATIC SWITCHING VIA AN EXTERNAL MOUNTED PHOTOCELL. LOCATION TO BE AGREED ONSITE WITH THE MAIN CONTRACTOR. THE MAIN CONTRACTOR SHALL PROVIDE A SCHEDULED LIGHTING CONTROL SYSTEM TO BE USED FOR CONSTRUCTION PURPOSES. THE PROGRAMMING IN MANUAL OVERRIDE OF THE EXTERNAL FACADE LIGHTING SHALL BE PROVIDED VIA THE MASTER SCENE SET CONTROLLER.

ALL EXTERNALLY MOUNTED LUMINAIRES SHALL HAVE DIMMING CONTROL UNLESS STATED OTHERWISE ON THE LUMINAIRE SCHEDULE ARCHITECTURAL LIGHTING MOCK UP.

WHERE FEASIBLE ALL EXTERNAL LIGHTING ELEMENTS SHALL BE MOCKED UP / TESTED WITH THE PROPOSED LIGHTING EQUIPMENT PRIOR TO ORDERING ANY LIGHTING EQUIPMENT. THE MOCK UP SHALL BE VIEWED WITH THE CLIENT, ARCHITECT, CONSERVATION SPECIALIST AND LIGHTING DESIGNER PRESENT. TO ENSURE ALL PARTIES ARE HAPPY WITH THE PROPOSED EFFECTS.

THE MAIN CONTRACTOR SHALL PROVIDE POWER AND SAFE ACCESS FOR THE MOCK UP WITH THE ELECTRICAL CONTRACTOR UNDERGOING THE TEMPORARY INSTALLATION WORKS FOR THE TESTS.

THE MOCK UP SHALL BE VIEWED DURING THE HOURS OF DARKNESS TO VIEW THE PROPOSED LIGHTING EFFECTS. THE MAIN CONTRACTOR / ELECTRICAL INSTALLER SHALL MAKE THE APPROPRIATE ADVANCES FOR UNDERGOING THE MOCK UP WORKS AND EVENING (NIGHTTIME) LIGHT TESTS.

EXTERNAL SIGNAGE

SIGNAGE LIGHTING AND EXTERNALLY ILLUMINATED SIGNAGE TO BE CONFIRMED

