

Schedule of Accommodation							
Unit	Ground Floor GIA	First Floor GIA	TOTAL UNIT GIA	TOTAL UNIT GEA	Total Parking Inc. (Acc.)	Parking Ratio (m²)	Height to underside of Haunch
Unit 1	616m² / 6,630ft²	97 m² / 1,044ft²	713m² / 7,674ft²	777m² / 8,363ft²	11 (2)	1:70	8.0m
Unit 2	989m² / 10,645ft²	110m² / 1,184ft²	1,099m² / 11,829ft²	1,182m² / 12,722ft²	18 (2)	1:66	8.0m
Unit 3	2,460m² / 26,479 ft²	275m² / 2,960ft²	2,735m² / 29,439ft²	2,869m² / 30,881ft²	35 (3)	1:82	10m
Unit 4	2,175m² / 23,411.5ft²	262m² / 2,820ft²	2,437m² / 26,231ft²	2,579m² / 27,760ft²	34 (4)	1:76	10m
TOTAL GIA			6,984m² / 75,175ft²	7,407m² / 79,728ft²	98 (11)	1:76	




- All dimensions and levels are to be checked on site.
- Any discrepancies are to be reported to the architect before any work commences
- This drawing shall not be scaled to ascertain any dimensions. Work to figured dimensions only.
- This drawing shall not be reproduced without express written permission from AEW.
- Title overleaf drawings and ownership boundaries are produced using all reasonable endeavors. AEW cannot be responsible for the accuracy or scale discrepancy of base plans supplied to them.
- All works are to be undertaken in accordance with Building Regulations and the latest British Standards.
- All proprietary materials and products are to be used strictly in accordance with the manufacturers recommendations.

CDM 2015

Client notified of duties: **07/04/21**

Principal Designer: **Client**

Unless noted below, all known hazards have been highlighted on the drawing:



KEY:

- Site Boundary**

Trees to be retained

Trees to be removed

Additional Soft landscaping:

Zone A	1,102m ² / 11,862ft
Zone B	751m ² / 8,084ft ²
Total	1,853m² / 19,946ft²

Tarmac

Concrete

Concrete paving

Gravel

Electric Vehicle Charging spaces (10no.) (10% of parking spaces)

Future provision for EVCPs with cable routes (20no) (20% of parking spaces)

Dropped Kerb

Landscape Planting to Landscape Architect Specification. Existing trees and shrubs to be Retained where possible.

Existing trees to be retained

Proposed tree planting

P13	19/11/24	SG	DRS
EV parking numbers updated further to case officer comments			
P12	15/11/24	SG	DRS
EV parking notes added			
P11	02/05/24	MW	DRS
Title block amended			
P10	26/04/24	MW	DRS
Layout and surface finishes amended, landscaping amended			
P09	13/11/23	SJK	DRS
Layout and surface finishes amended, landscaping updated			
P08	24/07/23	HN	AL
Layout updated			
P07	17/05/23	HN	DRS
Layout updated			
P06	16/12/22	SS	AL
Hardstanding adjacent to new sub increased to allow for maintenance vehicle parking			
P05	08/11/22	HN	SS
Units 3 and 4 updated landscaping updated and increased			
REV	Date	Drawn by -	Checked by -

Status	Purpose of Issue
S3	Information

drawing stage **Planning**

client

NSJV Ltd

project

**Welcomb Street
Openshaw**

drawing title

Proposed External Works Plan

date	10/08/22	drawn	HN
scale@A1	1:500	checked	SS