MattBrookArchitects

manchester

St George's Gardens
1F Spinners Way,
Manchester
M15 4UZ

+44 (0) 161 806 1396

https://www.mattbrookarchitects.co.uk/

windows

Talbot Mill - Mill 1 • window schedule

TM-MBA-M1-ZZ-SH-A-00-W001

status CONSTRUCTION

rev - C02 17.10.24

location	number	type	description	performance							dimensions				material	finishes and colour		glazing	ironmongery	hand (viewed ext.)	drawing location	manufacturer /	comments
				acoustic dB Rw (minimum performance required)	maximum u-value 1.6 W/m2K	g-value	vent / trickle vent	vent / purge	fire	security	structural opening	frame size	leaf size	cill height		external	internal						
courtyard level																							
Mill 01 - Ellesmere Street Elevation	M1-WC-001	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_w + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	0.6sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-B1-DR-A-00-140	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-WC-002	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_w + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	1.6sqm (combined with M1.WC.003)	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-B1-DR-A-00-140	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-WC-003	Type 02	6 pane window. 2no. side hung opening lights. 2no. fixed lights under	glazing $R_w + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	1.6sqm (combined with M1.WC.002)	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-B1-DR-A-00-140	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-WC-004	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_w + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	0.6sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-B1-DR-A-00-140	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-WC-005	Type 02	6 pane window. 2no. side hung opening lights. 2no. fixed lights under	glazing $R_w + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	1.23sqm (combined with M1.WC.006)	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-B1-DR-A-00-140	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-WC-006	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_w + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	1.23sqm (combined with M1.WC.005)	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 2 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-B1-DR-A-00-140	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-WC-007	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_w + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	0.5sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-B1-DR-A-00-140	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-WC-008	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_w + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	0.5sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M-B1-DR-A-00-140	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-WC-009	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_w + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	0.5sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 2 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-B1-DR-A-00-140	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.

MattBrookArchitects

Talbot Mill - Mill 1 • window schedule

status CONSTRUCTION

TM-MBA-M1-ZZ-SH-A-00-W001

rev - C02 17.10.24

location	number	type	description	performance						dimensions				material	finishes and colour		glazing	ironmongery	hand (viewed ext.)	drawing location	manufacturer /	comments
				acoustic dB Rw (minimum performance required)	maximum u-value 1.8 W/m2K	g-value	vent / trickle vent	vent / purge	fire	security	structural opening	frame size	leaf size	cill height		external	internal						
Mill 01 - Courtyard Elevation	M1-WC-010	Type 02	6 pane window. 2no. side hung opening lights. 2no. fixed lights under	glazing $R_w + C_{tr}$ 26dB acoustic trickle ventilator $D_n,e,w + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	1.21sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 2 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-B1-DR-A-00-140	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-WC-011	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_w + C_{tr}$ 26dB acoustic trickle ventilator $D_n,e,w + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	0.6sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 2 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-B1-DR-A-00-140	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-WC-012	Type 22	fixed pane feature window	glazing $R_w + C_{tr}$ 26dB	1.6	0.63	n/a	n/a	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 2 Glass	n/a	fixed	TM-MBA-M1-00-DR-A-00-141	yes - refer to detail	Existing window opening - add new 'Aluprof MB slimline thermally broken system' with opaque coating applied to window base at surface 3 - dark grey colour. Glass coating extents varies. Rebated or flush reveal /arched or flat infill head condition - safety glazing up to 1100mm above FFL. note site dimensions required to confirm height of fixed lights and transom levels. N.B please note - no trickle vent required.
Mill 01 - Courtyard Elevation	M1-WC-013	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_w + C_{tr}$ 26dB acoustic trickle ventilator $D_n,e,w + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	0.6sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 2 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-B1-DR-A-00-140	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Bridge link Elevation	M1-WC-014	Type 19	6 pane window. 6no. fixed lights.	glazing $R_w + C_{tr}$ 26dB	1.6	0.63	n/a	n/a	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 2 Glass	n/a	fixed	TM-MBA-MI-B1-DR-A-00-140	no	carefully remove brickwork to existing window opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Access Elevation	M1-WC-015	Type 14	4 pane window. 1no. top hung opening light with 2no. fixed light	glazing $R_w + C_{tr}$ 26dB acoustic trickle ventilator $D_n,e,w + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	0.6sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 2 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	top hung / inward opening	TM-MBA-MI-B1-DR-A-00-140	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.

-

Talbot Mill - Mill 1 • window schedule

status CONSTRUCTION

TM-MBA-M1-ZZ-SH-A-00-W001

rev - C02 17.10.24

location	number	type	description	performance							dimensions				material	finishes and colour		glazing	ironmongery	hand (viewed ext.)	drawing location	manufacturer /	comments
				acoustic dB Rw (minimum performance required)	maximum u-value 1.6 W/m2K	g-value	vent / trickle vent	vent / purge	fire	security	structural opening	frame size	leaf size	cill height		external	internal						
level 00																							
Mill 01 - Ellesmere Street Elevation	M1-WD-001	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_t + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	0.65sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-WD-002	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_t + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	1.6sqm (combined with M1.WD.003)	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-WD-003	Type 02	6 pane window. 2no. side hung opening lights. 2no. fixed lights under	glazing $R_t + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	1.6sqm (combined with M1.WD.002)	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-WD-004	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_t + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	0.6sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-WD-005	Type 02	6 pane window. 2no. side hung opening lights. 2no. fixed lights under	glazing $R_t + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	1.25sqm (combined with M1.WD.006)	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-WD-006	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_t + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	1.25sqm (combined with M1.WD.005)	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-WD-007	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_t + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	0.6sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-WD-008	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_t + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	0.6sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Access Elevation	M1-WD-009	Type 19	6 pane window. 6no. fixed lights.	glazing $R_t + C_{tr}$ 26dB	1.6	0.63	n/a	n/a	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 2 Glass	n/a	fixed	TM-MBA-M1-00-DR-A-00-141	no	carefully remove brickwork to existing window opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-WD-010	Type 02	6 pane window. 2no. side hung opening lights. 2no. fixed lights under	glazing $R_t + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	1.25sqm (combined with M1.WD.009)	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-WD-011	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_t + C_{tr}$ 26dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	0.5sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-WD-012	Type 02	6 pane window. 2no. side hung opening lights. 2no. fixed lights under	glazing $R_t + C_{tr}$ 26dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	1.25sqm (combined with M1.WD.013)	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-WD-013	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_t + C_{tr}$ 26dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	1.25sqm (combined with M1.WD.012)	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.

MattBrookArchitects

Talbot Mill - Mill 1 • window schedule

status CONSTRUCTION

TM-MBA-M1-ZZ-SH-A-00-W001

rev - C02 17.10.24

location	number	type	description	performance							dimensions				material	finishes and colour		glazing	ironmongery	hand (viewed ext.)	drawing location	manufacturer /	comments
				acoustic dB Rw (minimum performance required)	maximum u-value 1.6 W/m2K	g-value	vent / trickle vent	vent / purge	fire	security	structural opening	frame size	leaf size	cill height		external	internal						
Mill 01 - Courtyard Elevation	M1-W0-014	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_w + C_{tr}$ 26dB acoustic trickle ventilator $D_n,e,w + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	0.6sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-W0-015	Type 22	fixed pane feature window	glazing $R_w + C_{tr}$ 26dB	1.6	0.63	n/a	n/a	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	n/a	fixed	TM-MBA-M1-00-DR-A-00-141	yes - refer to detail	Existing window opening - add new 'Aluprof MB slimline thermally broken system' with opaque coating applied to window base at surface 3 - dark grey colour. Glass coating extents varies. Rebated or flush reveal /arched or flat infill head condition - safety glazing up to 1100mm above FFL. note site dimensions required to confirm height of fixed lights and transom levels. N.B please note - no trickle vent required.
Mill 01 - Courtyard Elevation	M1-W0-016	Type 02	6 pane window. 2no. fixed side lights. 2no. fixed lights under	glazing $R_w + C_{tr}$ 26dB acoustic trickle ventilator $D_n,e,w + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	1.6sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL.
Mill 01 - Courtyard Elevation	M1-W0-017	Type 02	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_w + C_{tr}$ 26dB acoustic trickle ventilator $D_n,e,w + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	n/a	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-W0-018	Type 19	6 pane window. 6no. fixed lights,	glazing $R_w + C_{tr}$ 26dB	1.6	0.63	n/a	n/a	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	n/a	fixed	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Access Elevation	M1-W0-019	Type 15	6 pane window. 1no. top hung opening light with 4 no. fixed lights under	glazing $R_w + C_{tr}$ 26dB acoustic trickle ventilator $D_n,e,w + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	0.6sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	top hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Access Elevation	M1-W0-020	Type 15	6 pane window. 1no. top hung opening light with 4 no. fixed lights under	glazing $R_w + C_{tr}$ 29dB acoustic trickle ventilator $D_n,e,w + C_{tr}$ 35dB	1.6	0.63	2500m m2 trickle vent	0.6sqm	n/a	sbd approved (RC2)	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	top hung / inward opening	TM-MBA-M1-00-DR-A-00-141	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.

Talbot Mill - Mill 1 • window schedule

status CONSTRUCTION

TM-MBA-M1-ZZ-SH-A-00-W001

rev - C02 17.10.24

location	number	type	description	performance							dimensions				material	finishes and colour		glazing	ironmongery	hand (viewed ext.)	drawing location	manufacturer /	comments
				acoustic dB Rw (minimum performance required)	maximum u-value 1.8 W/m2K	g-value	vent / trickle vent	vent / purge	fire	security	structural opening	frame size	leaf size	cill height		external	internal						
level 01																							
Mill 01 - Ellesmere Street Elevation	M1-WX-001	Oriel Window	3 storey projecting oriel window - refer to separate details	glazing $R_r + C_{tr}$ 29dB	1.6	0.63	n/a	n/a	n/a	n/a	site dim. required	site dim. required	site dim. required	site dim. required	structural glass fixed within steel frame with aluminium cladding	ppc - RAL 7021	ppc - RAL 7021		n/a	fixed	TM-MBA-M1-01-DR-A-00-142	no	3 storey oriel window set within ppc perimeter sleeve
Mill 01 - Ellesmere Street Elevation	M1-W1-002	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_r + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500mm2 trickle vent	0.8sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-W1-003	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_r + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500mm2 trickle vent	1.21sqm (combined with M1,W1.004)	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-W1-004	Type 02	6 pane window. 2no. side hung opening lights. 2no. fixed lights under	glazing $R_r + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500mm2 trickle vent	1.21sqm (combined with M1,W1.003)	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-W1-005	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_r + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500mm2 trickle vent	0.6sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-W1-006	Type 02	6 pane window. 2no. side hung opening lights. 2no. fixed lights under	glazing $R_r + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500mm2 trickle vent	1.3sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-W1-007	Oriel Window	single storey projecting oriel window - refer to separate details	glazing $R_r + C_{tr}$ 29dB	1.6	0.63	n/a	n/a	n/a	n/a	site dim. required	site dim. required	site dim. required	site dim. required	structural glass fixed within steel frame with aluminium cladding	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	n/a	fixed	TM-MBA-M1-01-DR-A-00-142	no	single storey oriel window set within ppc perimeter sleeve
Mill 01 - Ellesmere Street Elevation	M1-W1-008	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_r + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500mm2 trickle vent	0.6sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-W1-009	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_r + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500mm2 trickle vent	0.5sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-W1-010	Type 02	6 pane window. 2no. side hung opening lights. 2no. fixed lights under	glazing $R_r + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500mm2 trickle vent	1.53sqm (combined with M1,W1.011)	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Ellesmere Street Elevation	M1-W1-011	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_r + C_{tr}$ 29dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 35dB	1.6	0.63	2500mm2 trickle vent	1.53sqm (combined with M1,W1.010)	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 3 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-W1-012	Type 02	6 pane window. 2no. side hung opening lights. 2no. fixed lights under	glazing $R_r + C_{tr}$ 28dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500mm2 trickle vent	1.54sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-W1-013	Type 19	6 pane window. fixed lights.	glazing $R_r + C_{tr}$ 28dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500mm2 trickle vent	n/a	n/a	n/a	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40.111 – Mills Type 1 Glass	n/a	fixed	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system', rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.

Talbot Mill - Mill 1 • window schedule

status CONSTRUCTION

TM-MBA-M1-ZZ-SH-A-00-W001

rev - C02 17.10.24

location	number	type	description	performance						dimensions				material	finishes and colour		glazing	ironmongery	hand (viewed ext.)	drawing location	manufacturer /	comments
				acoustic dB Rw (minimum performance required)	maximum u-value 1.6 W/m2K	g-value	vent / trickle vent	vent / purge	fire	security	structural opening	frame size	leaf size	cill height		external	internal						
Mill 01 - Courtyard Elevation	M1-W1-014	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_r + C_{tr}$ 26dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	0.5sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-W1-015	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_r + C_{tr}$ 26dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	0.5sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-W1-016	Type 02	6 pane window. 2no. side hung opening lights. 2no. fixed lights under	glazing $R_r + C_{tr}$ 26dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	1.23sqm (combined with M1.W1.017)	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-W1-017	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_r + C_{tr}$ 26dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	1.23sqm (combined with M1.W1.016)	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-W1-018	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_r + C_{tr}$ 26dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	0.6sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-W1-019	Type 22	fixed pane feature window	glazing $R_r + C_{tr}$ 26dB	1.6	0.63	n/a	n/a	n/a	n/a	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	n/a	n / a	TM-MBA-M1-01-DR-A-00-142	yes - refer to detail	Existing window opening - add new 'Aluprof MB slimline thermally broken system' with opaque coating applied to window base at surface 3 - dark grey colour. Glass coating extents varies. Rebated or flush reveal / arched or flat infill head condition - safety glazing up to 1100mm above FFL. note site dimensions required to confirm height of fixed lights and transom levels. N.B please note - no trickle vent required.
Mill 01 - Courtyard Elevation	M1-W1-020	Type 02	6 pane window. 2no. fixed side lights. 2no. fixed lights under	glazing $R_r + C_{tr}$ 26dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	1.23sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-W1-021	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_r + C_{tr}$ 26dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	0.6sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Courtyard Elevation	M1-W1-022	Type 03	6 pane window. 6no. fixed lights.	glazing $R_r + C_{tr}$ 26 dB	1.6	0.63	n/a	n/a	n/a	n/a	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	n/a	n/a	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.
Mill 01 - Bridge link Elevation	M1-W1-023	Type 03	6 pane window. 6no. fixed lights	glazing $R_r + C_{tr}$ 26dB	1.6	0.63	n/a	n/a	60 mins	n/a	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	TBC by subcontractor to meet performance requirements including fire-rating	black spacers	n/a	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB 86 Fire Rated window'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL note site dimensions required to con firm height of fixed lights and transom levels.
Mill 01 - Ellesmere Access Elevation	M1-W1-024	Type 01	6 pane window. 1no. side hung opening light with 1no. fixed side light. 2no. fixed lights under	glazing $R_r + C_{tr}$ 26dB acoustic trickle ventilator $D_{n,e,w} + C_{tr}$ 32dB	1.6	0.63	2500m m2 trickle vent	0.6sqm	n/a	lockable	site dim. required	site dim. required	site dim. required	site dim. required	aluminium - thermally broken	ppc - RAL 7021	ppc - RAL 7021	See NBS L40:111 – Mills Type 1 Glass	satin aluminium • casement stay • locking handle • restrictor • trickle vent • black spacers	side hung / inward opening	TM-MBA-M1-01-DR-A-00-142	no	carefully remove existing window to opening. replacement with new 'Aluprof MB slimline thermally broken system'. rebated reveal / arched in fill head condition - safety glazing up to 1100mm above FFL - 2500mm2 acoustic trickle vent within additional cill transom. note site dimensions required to confirm height of fixed lights and transom levels.