Unit 1A Fountain Mill
Rakefoot, Haslingden
Lancashire. BB4 5RE

Tel no. 01706 244810
Fax no. 01706 244811
E mail: sales@mainlandcateriing .co.uk
Web: www.mainlandcatering.co.uk

Mainland Catering Equipment Limited

EMAQ RISK ASSESSMENT

To:	Mint Studio	**From:**	Chris Aspden
Att:	Louise Grimes	**Pages:**	2
Fax:		**Date:**	5th November 2024
Re:	Doux Chaton, Manchester EMAQ Risk Assessment	**Ref:**	**ORA9140-1A**

Hi Louise

Further to your recent email, we now have pleasure in submitting our EMAQ Risk Assessment for the proposed ventilation system at the above site : -

DOUX CHATON, MANCHESTER – EMAQ RISK ASSESSMENT

The impact risk is determined based on the following factors :-

Impact Risk	Odour Control Requirement	Significance Score
Low / Medium	Low Level Odour Control	Less than 20
High	High Level Odour Control	20 - 35
Very High	Very High Level Odour Control	More than 35

Criteria	Rating	Score	Details
Dispersion	Moderate	25	Low level discharge, discharge into courtyard or restriction on stack
Proximity of Receptors	Far	1	Closest sensitive receptor is more than 100 metres from the kitchen discharge
Size of kitchen	Medium	3	The pub has 50 covers

Cooking Type (Odour / grease loading)	Medium	4	Kebab, Vietnamese, Thai or Indian Cooking.
		33	**TOTAL SCORE – HIGH LEVEL ODOUR CONTROL**

Please note that we would calculate the odour risk impact as high level with the position of the high velocity jet cowl being sited at low level discharging into a courtyard.

Trusting the above is satisfactory, however should you require any further information please do not hesitate to contact me.

Regards,

Chris Aspden