Window frames to be replaced in the same style and colour as the original with individual bank of louvres fixed between transoms and mullions

Sliding grid security shutter fitted internally.

CNC cut 3mm aluminium “Londis” letters powdercoated green and halo lit via LEDs.

1 Proposed North Elevation

1 : 50

Window frames, mullions and transoms reinstated.

Window panels replaced with opaque film.

Blue PPC aluminium framed entrance door with glazed panels, (swing opening). Specification TBC.

Existing projecting signs on North and West elevations removed.

0 0.5 1.0 1.5 2.0 2.5 3.5m

The copyright of this drawing is vested with Corstorphine & Wright Ltd and must not be copied or reproduced without the consent of the company.

Rev.	Description	Date	Drw.	Chk.
P-01	Transon/Mullions added to entrance door. Louvred panels note amended	16/07/24	LS	RE
P-00	Revised Following Client Consultation	23.05.23	FG	RE

* Please note: Elevation and dimensions approximate, subject to further information.

Client
CFW Retail Ltd.

Project
Londis, Pollard St.

Drawing Title
Proposed North Elevation

Drawing Status
SKETCH

Corstorphine & Wright

Manchester Studio
4th Floor Tribeca House 21-27 Dale Street Manchester M1 1EY
0161 272 8100
corstorphine-wright.com

Drawing No.	Revision
23288-CWA-XX-A-SK05	P-01

Drawn	Checked	Paper Size	Scale	Date
FG	RE	A3	1 : 50	23.05.23